

 = CATCH BASIN LOCATION

REPLACE EXISTING CATCH BASIN AND CONNECT TO EXISTING STORM SEWER LINE WITH SCH. 40 P.V.C. (SEE CATCH BASIN DETAIL)

PAINT ALL LINE STRIPPING AND SPACE NUMBERS WHITE

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

BUILDING'S 55 PARKING LOT:



REMOVE 40' X 40' SECTION OF EXISTING GRAVEL AND INSTALL FULL DEPTH PAVEMENT PER ASPHALT DETAIL. (SEE ASPHALT DETAIL ON PAGE 2)

REMOVE EXISTING CONCRETE AND INSTALL NEW CONCRETE PER CONCRETE DETAIL. HOWEVER, THIS SECTION WILL BE 8" THICK.

PAINT ALL LINE STRIPPING AND SPACE NUMBERS WHITE

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

BUILDING'S 173 PARKING LOT:

<div> = CATCH BASIN LOCATION</div>	Approved: Medical Center Director Mark Murdock	Drawing Title BLACK ROAD AND BUILDING 55 AND 173 PARKING LOT DETAIL	Project Title REPAIR ROADS, CATCH BASINS AND OTHER UNDERGROUND STRUCTURES		Project Number 610-11-114	
	Approved: Medical Center Assoc. Director Jay Miller		Location MARION, IN		Building Number VARIOUS	
	Approved: Engineering Department Daniel A. Martin		Date 11/25/2015	Checked D. MARTIN	Drawn Z. MCDANIEL	
					Dwg. 7 of 12	