



REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

REMOVE 42 FEET OF EXISTING CURB. REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

INSTALL A 12' X 22' CONCRETE PAD

REPLACE VALVE BOX. TYP. (SEE STANDARD VALVE BOX DETAIL)

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

INSTALL NEW POST AND HANDICAP PARKING SIGNS FOR SPACE 9. SPACE 9 WILL ALSO HAVE A VAN ACCESSIBLE SIGN.

PAVE 126' X 40' SECTION OF MECHANICS AVE. REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

PAVE 33' X 25' SECTION. REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

REMOVE EXISTING GRAVEL AND INSTALL FULL DEPTH ASPHALT. (SEE FULL DEPTH ASPHALT DETAIL)

REMOVE PAVEMENT (1-1/2" TYPICAL) BY MILLING. REPLACE WITH TACK (BOND) COAT AND 1-1/2" HOT MIXED ASPHALT SURFACE COURSE, TYPE B, PG 64-22, 9.5MM MIX

BUILDING 58, 165, MECHANICS AVE. AND RAILROAD AVE. PAVING DETAIL:

Approved: Medical Center Director
Mark Murdock

Approved: Medical Center Assoc. Director
Jay Miller

Approved: Engineering Department
Daniel A. Martin

Drawing Title
BUILDING 58, 165, MECHANICS AVE. AND RAILROAD AVE. PAVING DETAIL

Approved: Project Director

Project Title
REPAIR ROADS, CATCH BASINS AND OTHER UNDERGROUND STRUCTURES

Location
MARION, IN

Date
11/25/2015

Checked
D. MARTIN

Drawn
Z. MCDANIEL

Project Number
610-11-114

Building Number
VARIOUS

Drawing Number
15-110M

Dwg. 12 of 12



= VALVE BOX REPLACEMENT LOCATION