


GUIDE RAIL DETAIL

NOT TO SCALE

- NOTES:
1. NEW YORK PAY CODES DO NOT APPLY TO THIS PROJECT
 2. SUMPS SHALL HAVE SOLID BOTTOM WITHOUT DRAIN



P.I.V. SUPERVISORY SWITCH WIRING

NOT TO SCALE


- NOTE:
1. IAM - INDIVIDUAL ADDRESSABLE MODULE.
 2. CONTRACTOR TO RECONNECT PIV SUPERVISORY SWITCH, INCLUDING ALL CONUIT AND WIRING TO EXISTING FIRE ALARM SYSTEM. PROVIDE ALL REQUIRED LABOR MATERIALS AND EQUIPMENT FOR FULLY FUNCTIONING SYSTEM. RESTORE P.I.V. SUPERVISORY SWITCH WIRING.
 3. PROVIDE ALL PROGRAMMING, CONNECTIONS AND TESTING FOR FULLY FUNCTION SYSTEM.

TYPICAL FIRE SERVICE CONNECTION


NOT TO SCALE

NOTE:

1. POST INDICATION VALVE (PIV) SHALL BE UL & FM APPROVED.
2. SUPERVISOR SWITCH SHALL BE PCVS-2 TYPE COMPATIBLE WITH P.I.V. AND EXISTING FACILITY FIRE ALARM SYSTEM.
3. PROVIDE CONNECTION OF POST INDICATOR VALVE (P.I.V.) SUPERVISOR SWITCH TO FIRE ALARM CONTROL (FACS) SYSTEM. RUN 1/2" PVC COATED RGS WITH CONTROL WIRE TO FACS AND PROVIDE CONNECTION PER MANUFACTURERS INSTRUCTIONS. COORDINATE EXACT LOCATION OF P.I.V. WITH CIVIL AND ARCHITECTURAL DRAWINGS. COORDINATE CONNECTION REQUIREMENTS WITH EXISTING FIRE ALARM MANUFACTURERS AND MAKE ALL PROVISIONS AS NECESSARY FOR A FULLY FUNCTION SYSTEM.



TYPICAL DETAIL OF GRANITE CURB INSTALLATION
NTS




GRANITE CURB

NOT TO SCALE


NOTES:

1. LENGTHS OF STRAIGHT GRANITE CURB MUST RANGE FROM 4 FT TO 12 FT LONG, 80% OF WHICH MUST BE 6 FT OR GREATER.
2. LENGTHS OF CORNER GRANITE CURB MUST RANGE FROM 3 FT TO 8 FT LONG, 80% OF WHICH MUST BE 4 FT OR GREATER.
3. LENGTH OF TRANSITION CURB (STRAIGHT OR CURVED) AT CORNERS MUST BE 5 FT LONG.
4. EXPOSED SURFACES OF THE GRANITE CURB TO BE DRESSED WITH A BUSH HAMMERED OR THERMAL FINISH, WITH NO DRILL HOLES.
5. GRANITE CURB (SAMPLES OF WHICH MUST BE FURNISHED BY THE CONTRACTOR TO THE VA FOR APPROVAL PRIOR TO CONSTRUCTION) IS TO BE MEDIUM GRAY IN COLOR AS APPROVED BY THE VA.



DIMENSIONS AND FINISH ON GRANITE CURB
NTS

SURFACE FINISH SCHEDULE		
SYMBOL	NO PROJECTION OVER	NO DEPRESSION OVER
(A)	1/8"	1/8"
(B)	1-1/2"	1-1/2"
(C)	1/2"	1"
(D)	0"	1"



GRANITE HEADER

NOT TO SCALE

CONSTRUCTION DOCUMENTS

Project Title: PARKING LOT 7 EXPANSION		Date: 06/23/2016
Building No. LOT 7		Project No. 528A5-16-505
Location: CANANDAIGUA, NEW YORK	Checked: CJC	Drawn: TAD
C-504		Page 13 of 20



Drawing Scale
Drawing Title CONSTRUCTION DETAILS

V.A.