

AMENDMENT NO. 1

VA Medical Center
Building 1 - Third Floor HVAC Mechanical Systems
St. Cloud, MN

- A. Refer to the SPECIFICATIONS of the above project and make the following additions, deletions, corrections and/or interpretations.
 - 1. REFER TO SPECIFICATION SECTION 07 51 00: REMOVE Specification Section 07 51 00 BUILT-UP BITUMINOUS ROOFING from the Specification in its entirety and SUBSTITUTE the attached Section 07 53 23 ETHLENE-PROPYLENE-DIENE-MONOMER ROOFING.
- B. Refer to the DRAWINGS of the above project and make the following additions, deletions, corrections and/or interpretations.
 - 1. REFER TO DRAWING E2. ATTIC POWER and SYSTEMS PLAN, Detail 3/E2:
Provide electrical demolition (disconnect fan and remove all related electrical wiring back to the source) of (2) existing exhaust fans one located adjacent to EF-1 and one located near the return air duct smoke detector on the east side of the attic.
 - 2. REFER to Drawing H1 - Ventilation Plans: ADD Drawing 4/H1 Attic Ventilation Demolition Plan to indicate removal of fans and ducts as illustrated on the attached Drawing H1-R1.
 - 3. REFER to Drawing H1 - Ventilation Plans: REVISE Drawing 1/H Third Floor Ventilation Demolition Plan to indicate removal of exhaust duct and patching of attic floor penetrations as illustrated on attached Drawing H1/R2.
- C. ATTACHMENTS:
 - 1. Section 07 53 23 ETHLENE-PROPYLENE-DIENE-MONOMER ROOFING
 - 2. Drawing Sheet H1-R1 dated January 9, 2012
 - 3. Drawing Sheet H1-R2 dated January 9, 2012

- - - END OF AMENDMENT NO. 1 - - -