



NOTES:

- 1) ANCHOR C CHANNEL TO SIDE OF BUILDING.
- 2) PLACE 3/8" x 4" x 3" BASE PLATE IN NEW CONCRETE BASE.
- 3) WELD C CHANNEL TO BASE PLATE.
- 4) WELD TOP C CHANNEL TO OTHER PLACED C CHANNELS AFTER GLASS BLOCK IS IN PLACE.
- 5) PAINT ALL C CHANNELS TO SPECIFIC COLOR TO BE DETERMINE LATER.
- 6) WHILE WELDING, USE ALL PRECAUTION NECESSARY TO PROTECT THE GLASS BLOCK AND EXISTING BUILDING.
- 7) THIS WILL NEED TO BE DONE TO BOTH THE EAST AND WEST SIDES OF THE PROJECT.

Scale: 1/4" = 1'

Project Title			Date
Glass Block Frame			1/20/2012
Building Number			Drawn
44	Floor	Room No.	A. Wieck
	-	-	DRAWING NO.
Location			1
AMARILLO, TEXAS			Dwg. 1 Of 1