

Statement of Work
Install Components on Security Camera System

1. **Overview** The Contractor for the Sheridan VA Medical Center in Sheridan, Wyoming shall supply and install the equipment on the Bill of Material below; Contractor shall install and configure multiplexor and fiber interconnections from Bldg 86 to VA Police Office. Interconnect 19 existing cameras (6 in VCS store and 13 in SNU) in Bldg 86 to new VA PD DVR for real-time monitoring and recording in VA PD. This system will piggy back off the existing Bldg 86 cameras and monitors (leaving intact) and relay duplicate video signal to VA PD from the cameras. Contractor shall install and configure multiplexor and fiber interconnections from Bldg 6 to VA Police Office. Interconnect 15 existing cameras in Bldg 64 to new VA PD DVR for real-time monitoring and recording in VA PD. This system will piggy back off the existing Bldg 64 cameras and monitors (leaving intact) and relay duplicate video signal to VA PD from the cameras. Contractor shall install and configure multiplexor and fiber interconnections from Bldg 6 to VA Police Office. Interconnect 16 existing cameras in Bldg 6 to new VA PD DVR for real-time monitoring and recording in VAPD. This system will piggy back off the existing Bldg 6 cameras and monitors (leaving intact) and relay duplicate video signal to VAPD from the cameras. Contractor shall install and configure multiplexor and fiber interconnections from Bldg 71 to VA Police Office. Interconnect two (2) existing cameras in Bldg 71 to VA PD DVR for real-time monitoring and recording in VA PD. Contractor shall install and configure multiplexor and fiber interconnections from Bldg 61 to VA Police Office. Interconnect one (1) existing cameras in Bldg 61 to VA PD DVR for real-time monitoring and recording in VA PD
2. **Equipment Warranty:** Contractor shall warrant products sold under this agreement for a period of one (1) year from date of purchase. Contractor's obligation under this warranty is limited to repairing or replacing any part of the products sold under this agreement that we agree is defective in materials or workmanship under normal use and service during the warranty period.
3. **The Contractor will have access to VA sensitive information and a VA form 6500 appendix A must be completed.**

VA Sheridan Medical Center
Bill of Materials

**Building 86 Addition to VA PD Real-Time
Monitoring System
Parts**

- 1 multi16 16 Channel Fiber Optic Video Multiplexor (transmitter and receiver)
- 2 multi4 4 Channel Fiber Optic Video Multiplexor (transmitter and receiver)
- 3 wUPS Wall Mountable UPS \$260.00 1
- 4 Fiber 62.5 Micron Fiber 6 Strand Armored
- 5 LIU LIU
- 6 CAB Wall Mounted Cabinet Black
- 7 CCTVSVR CCTV Server with 32 inputs and 2 TV outputs
- 8 LCD65 65" LCD Monitor with wall bracket
- 9 Splitter BNC Video Splitter 4 BNC Inputs to 8 BNC Outputs
- 10 Matrix 4x4 HDMI Matrix Switch
- 11 Misc Misc. Parts (Tie Wraps, Fire Calk, J-Hooks, Velcro, Connectors, HDMI cables)

Building 64 Addition to VA PD Real-Time

**Monitoring System
Parts**

- 1 multi16 16 Channel Fiber Optic Video Multiplexor (transmitter and receiver)
- 2 wUPS Wall Mountable UPS
- 3 Cat6 Category 6 Plenum 1,000 ft.
- 4 LIU LIU
- 5 CAB Wall Mounted Cabinet Black
- 6 CCTVSVR CCTV Server with 32 inputs and 2 TV outputs
- 7 LCD65 65" LCD Monitor with wall bracket
- 8 Splitter BNC Video Splitter 4 BNC Inputs to 8 BNC Outputs
- 9 Matrix 4x4 HDMI Matrix Switch
- 10 Misc Misc. Parts (Tie Wraps, Fire Calk, J-Hooks, Velcro, Connectors, HDMI cables)

**Building 6 Addition to VA PD Real-Time
Monitoring System
Parts**

- 1 multi16 16 Channel Fiber Optic Video Multiplexor (transmitter and receiver)
- 2 wUPS Wall Mountable UPS
- 3 Fiber 62.5 Micron Fiber 6 Strand Armored
- 4 LIU LIU
- 5 CAB Wall Mounted Cabinet Black
- 6 CCTVSVR CCTV Server with 32 inputs and 2 TV outputs
- 7 LCD65 65" LCD Monitor with wall bracket
- 8 Splitter BNC Video Splitter 4 BNC Inputs to 8 BNC Outputs
- 9 Matrix 4x4 HDMI Matrix Switch
- 10 Misc Misc. Parts (Tie Wraps, Fire Calk, J-Hooks, Velcro, Connectors, HDMI cables)

**Building 71 Addition to VA PD Real-Time
Monitoring System
Parts**

- 1 multi4 4 Channel Fiber Optic Video Multiplexor (transmitter and receiver)
- 2 wUPS Wall Mountable UPS
- 3 Cat6 Category 6 Plenum Cable 1,000 Ft. Box
- 4 LIU LIU
- 5 CAB Wall Mounted Cabinet Black
- 6 Splitter BNC Video Splitter 4 BNC Inputs to 8 BNC Outputs
- 7 Matrix 4x4 HDMI Matrix Switch
- 8 Misc Misc. Parts (Tie Wraps, Fire Calk, J-

**Building 61 Addition to VA PD Real-Time
Monitoring System
Parts**

- 1 multi4 4 Channel Fiber Optic Video Multiplexor (transmitter and receiver)
- 2 wUPS Wall Mountable UPS
- 3 Cat6 Category 6 Plenum Cable 1,000 Ft. Box
- 4 LIU LIU
- 5 CAB Wall Mounted Cabinet Black
- 6 Splitter BNC Video Splitter 4 BNC Inputs to 8 BNC Outputs
- 7 Matrix 4x4 HDMI Matrix Switch
- 8 Misc Misc. Parts (Tie Wraps, Fire Calk, J-

Sheridan VA Medical Center
Facility Management Service
Sheridan, WY 82801

Statement of Work
Sheridan VAMC
Security Camera System