

Coatesville VAMC  
Coatesville, PA

AWE Machine Guard  
#542-12-114

**SECTION 09 06 00  
SCHEDULE FOR FINISHES**

**SECTION 09 06 00-SCHEDULE FOR FINISHES**

VAMC: Coatesville VA Medical Center  
Location:1400 Blackhorse Hill Road, Coatesville, PA 19320  
Project no. and Name:542-12-114  
Submission: 100% Design Development  
Date: 1 December 2014

**SECTION 09 06 00**  
**SCHEDULE FOR FINISHES**

**PART I - GENERAL**

**1.1 DESCRIPTION**

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

**1.2 MANUFACTURERS**

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

**1.3 SUBMITALS**

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

**1.4 APPLICABLE PUBLICATIONS**

A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.

B. MASTER PAINTING INSTITUTE: (MPI)

2001.....Architectural Painting Specification Manual

**PART 2- PRODUCTS**

**2.1 DIGITAL COLOR PHOTOS**

A. Size 24 x 35 mm.

B. Labeled for:

1. Building name and Number.

2. Room Name and Number, as well as equipment name/ID.

3. Before and After view of equipment being guarded/modified.

**2.2 DIVISION 31 - EARTHWORK -DELETED**

**2.3 DIVISION 03 - CONCRETE**

A. SECTION 03 55 11, Gypsum Concrete Floor Decks

Surface	Finish Description
C	XX (patchwork match existing)

**2.4 DIVISION 04 - MASONRY**

A. Section 04 05 13, MASONRY MORTARING and Section 04 05 16, MASONRY GROUTING

Finish Code	Manufacturer	Mfg. Color Name
M-XX (match housekeeping pad)	Hilti or equivalent	-

**2.5 DIVISION 05 - METALS**

A. SECTION 05 50 00, METAL FABRICATION

Item	Finish
Modular Channel Units	EXT-P
Factory Metal Guarding (incl framework & expanded metal)	BE
Fabricated Metal Guarding (incl framework & expanded metal)	EXT-P
Screened Access Door and Frame	BE

**2.6 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES DELETED**

**2.7 DIVISION 07 - THERMAL AND MOISTURE PROTECTION**

A. SECTION 07 92 00, JOINT SEALANTS

Location	Color	Manufacturer	Manufacturer Color
Masonry Expansion Joints	XX	Hilti or equivalent	-
New to Existing Walls	XX	Hilti or equivalent	-
Masonry Sealed Joints	XX	Hilti or equivalent	-

**2.8 DIVISION 08 - OPENINGS**

A. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	EXT-P/XX

## 2.9 DIVISION 09 - FINISHES

### A. SECTION 09 67 23, EPOXY RESINOUS FLOORING (ERF)

Finish code	Manufacturer	Mfg. Color Name/No.
ERF	Sherwin Williams or equivalent	XX

### B. SECTION 09 91 00, PAINT AND COATINGS

#### 1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
P - STRUCTURAL SUPPORT	EXT-P - 1	Sherwin Williams or Equiv	XX (match actual guard)
P - METAL GUARD	BE - 5	As per manufacturer	XX (match equipment)

### 2.10 DIVISION 10 - SPECIALTIES - DELETED

### 2.11 DIVISION II - EQUIPMENT - DELETED

### 2.12 DIVISION 12- FURNISHINGS - DELETED

### 2.13 DIVISION 13 - SPECIAL CONSTRUCTION - DELETED

### 2.14 DIVISION 22 - PLUMBING - DELETED

### 2.15 DIVISON 26 - ELECTRICAL - DELETED

### PART III EXECUTION

### 3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS
-----------------------------------------------

Term	Abbreviation
------	--------------

Coatesville VAMC  
Coatesville, PA

AWE Machine Guard  
#542-12-114

Baked On Enamel	BE
Concrete	C
Epoxy Coating	EC
Epoxy Resin Flooring	ERF
Existing	E
Exterior	EXT

Exterior Paint	EXT-P
Material	MAT
Mortar	M
Paint	P
Plastic Laminate	HPDL

### 3.2 FINISH SCHEDULE SYMBOLS

Symbol Definition

\*\* Same finish as adjoining walls

- No color required

E Existing

XX To match existing

EFTR Existing finish to remain

RM Remove

### 3.3 ROOM FINISH SCHEDULE - DELETED

--- E N D---