

## **PROJECT 509-318E**

### **SCIU E-WING RENOVATION**

#### **SCOPE OF WORK FOR ABATEMENT OF ASBESTOS FROM FLOOR TILE MASTIC**

Remove and abate approximately 9000 square feet of floor tile mastic that contains asbestos materials. The work area is in the Spinal Cord Injury Unit E-wing of Building 801. The abatement procedure will be in accordance with the VA specification 02821319- ASBESTOS FLOOR TILE AND MASTIC ABATEMENT. The work will be performed in two phases to comply with the construction plan. The contractor performing the work must comply with Federal and State abatement regulations and qualifications. The abatement process will be coordinated through the VAMC Industrial Hygienist (to be identified at the start of the project).