

Domain File: \\Projects\1313 Renovate Radiology & SPS - VA Shreveport\Renovate Radiology & SPS - VA Shreveport\Sheets\4602 FINISH SCHEDULES.dwg  
 Plotted by: hamed  
 Plotted Date: May 20, 2015 11:40:29am  
 one-eighth inch = one foot  
 one-quarter inch = one foot  
 three-eighths inch = one foot  
 one-half inch = one foot  
 three-quarters inch = one foot  
 one inch = one foot  
 one and one-half inches = one foot  
 three inches = one foot

FINISHES	
FINISH NO.	DESCRIPTION
<b>PAINT</b>	
P1	TO MATCH SHERWIN WILLIAMS, SW6107 NOMADIC DESERT
P2	TO MATCH SHERWIN WILLIAMS, SW6194 BASIL
P3	TO MATCH SHERWIN WILLIAMS, SW7618 DEEP SEA DIVE
P4	TO MATCH SHERWIN WILLIAMS, SW6105 DIVINE WHITE
P5	TO MATCH SHERWIN WILLIAMS, SW0012 EMPIRE GOLD
P6	TO MATCH SHERWIN WILLIAMS, SW6242 BRACING BLUE
P7	TO MATCH SHERWIN WILLIAMS, SW7538 TAMARIND
<b>SPECIAL COATING</b>	
SC	STONHARD STONGLAZE USF BLUE STEEL
<b>DOOR STAIN</b>	
DS	MARSHFIELD, #26-95 HONEY
<b>CARPET TILE</b>	
CPT	MANNINGTON, TERRAIN II, FISCAL YEAR
<b>LUXURY VINYL TILE</b>	
LVT1	ARMSTRONG NATURAL CREATIONS, ARBOR ART TP020 WALNUT MEDIUM
LVT2	ARMSTRONG NATURAL CREATIONS, MYSTIX TP769 CHROMA STONE SPAR
LVT3	ARMSTRONG NATURAL CREATIONS, MYSTIX TP773 CHROMA STONE LUNA
LVT4	
LVT5	
LVT6	ARMSTRONG NATURAL CREATIONS, MYSTIX TP771 CHROMA STONE BLOSSOM
<b>PORCELAIN AND CERAMIC TILE</b>	
CT1	DALTILE PORCEALTO GRIGIO SCURO CD42, 12" X 12"
<b>GROUT</b>	
G	PRO-SPEC, TAUPE 65
<b>RESINOUS FLOORING (RES-3)</b>	
RES1	STONHARD STONSHIELD HRI FLAGSTONE
RES2	STONHARD STONSHIELD HRI BRICK RED
<b>EPOXY FLOORING</b>	
EPY	TO BE SELECTED FROM MANUFACTURER'S FULL RANGE OF COLORS
<b>WELDED SHEET FLOORING</b>	
WSF1	MANNINGTON BIOSPEC MD BRIGHT WHITE 15246
WSF2	MANNINGTON BIOSPEC MD TAUPESTONE 15348
WSF3	MANNINGTON BIOSPEC MD DENIM 15337
<b>BASE</b>	
B1	JOHNSONITE 92-BLUE LAGOON, 4" COVED RUBBER BASE OR EQUAL
B2	ROPPE, 193 BLACK BROWN, 4" COVED RUBBER BASE OR EQUAL
CT1	DALTILE PORCEALTO GRIGIO SCURO CD42, 6" X 12" COVE BASE
RES	STONHARD STONSHIELD HRI FLAGSTONE
WSF1	MANNINGTON BIOSPEC MD BRIGHT WHITE 15246
<b>CEILING</b>	
ACT1	TO MATCH EXISTING HOSPITAL STANDARD (TYPE III)
ACT2	TO MATCH EXISTING HOSPITAL MOISTURE RESISTANT STANDARD (TYPE IV)
GYP	GYP. BD. CEILING; P4 U.N.O.
<b>PLASTIC LAMINATE</b>	
PL1	NEVAMAR, NAVY MATRIX
<b>SOLID SURFACE MATERIAL</b>	
SSM1	CORIAN FOSSIL OR EQUAL
<b>RUBBER TREAD</b>	
RT	TO BE SELECTED FROM MANUFACTURER'S FULL RANGE OF COLORS
<b>SOUND-ABSORBING WALL UNITS</b>	
SA	TO BE SELECTED FROM MANUFACTURER'S FULL RANGE OF COLORS

SUBJECT TO COMPLIANCE WITH SPECIFICATIONS PRODUCTS OF OTHER MANUFACTURERS THAT MATCH INDICATED FINISH ARE ACCEPTABLE FOR USE.

### 4TH FLOOR ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WAIN	WALLS			CEILING		REMARKS
					N	E	S	W	MATL	
400	STAIR 11	LVT1	B2		P1	P2	P1	ACT1	8'-0"	---
401	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT/GWB	VARIES	1,2
402	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1	8'-0"	---
403	IT	EPY	B1		P4	P4	P4	OTS	12'-6"	---
404	HAC	CT	CT	CT@48"	SC	SC	SC	ACT2	8'-0"	---
405	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1	8'-0"	---
406	OFFICE	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
407	WAITING	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
408	CT HOLDING	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
409	CT CONTROL	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
410	STORAGE	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
411	CT SCAN	WSF 1/2/3	WSF1		P4	P4	P4	ACT1	8'-3"	---
412	CT EQUIP	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
413	TOILET	CT	CT	CT@48"	P6	P4	P4	ACT1	8'-0"	---
414	TOILET	CT	CT	CT@48"	P6	P4	P4	ACT1	8'-0"	---
415	WAITING	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
416	MRI HOLDING	LVT 1/4	B2		P4	P4	P4	ACT1	8'-0"	---
417	RECEPTION	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
418	TOILET	CT	CT	CT@48"	P4	P4	P4	ACT1	8'-0"	---
419	DRESS	LVT1	B2		P4	P5	P4	ACT1	8'-0"	---
420	DRESS	LVT1	B2		P4	P5	P4	ACT1	8'-0"	---
421	DRESS	LVT1	B2		P4	P5	P4	ACT1	8'-0"	---
422	DRESS	LVT1	B2		P4	P5	P4	ACT1	8'-0"	---
423	CORRIDOR	LVT 1/5	B2		P4	P4	P4	ACT1	8'-0"	---
424	MRI SCAN	LVT 1/6	B2		SA	SA	SA	ACT1	VARIES	1
425	CONTROL	LVT 1/5	B2		P4	P4	P4	ACT1	8'-0"	---
426	CORRIDOR	LVT 1/5	B2		P4	P4	P4	ACT1	8'-0"	---
427	MRI EQUIPMENT	WSF1	WSF1		P4	P4	P4	ACT1	8'-0"	---
428	MRI SCAN	WSF 1/6	B2		SA	SA	SA	ACT1	9'-0"	---
429	CONTROL	LVT 1/5	B2		P4	P4	P4	ACT1	8'-0"	---
430	ELECTRICAL	EPY	B1		P4	P4	P4	OTS	12'-6"	---
431	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1	8'-0"	---
432	STAFF BREAK	LVT1	B2		P5	P4	P4	ACT1	8'-0"	---
433	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1	8'-0"	---
434	TOILET	CT	CT	CT@48"	P4	P4	P4	ACT1	8'-0"	---
435	ELECTRICAL	EPY	B1		P4	P4	P4	OTS	12'-6"	---
436	COPY	LVT1	B2		P5	P4	P4	ACT1	8'-0"	---
437	CONFERENCE	CPT/LVT1	B1		P5	P4	P4	ACT1	8'-0"	---
438	SEC	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
439	CHIEF OFFICE	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
440	STAIR 10	LVT1	B2		P1	P1	P1	ACT1	8'-0"	---
441	TOILET	CT	CT	CT @48"	P4	P6	P4	ACT1	8'-0"	---
442	LOUNGE	CPT/LVT1	B1		P4	P4	P4	ACT1	8'-0"	---
443	READING	CPT	B1		P7	P7	P7	ACT1	8'-0"	---
444	READING	CPT	B1		P7	P7	P7	ACT1	8'-0"	---
445	READING	CPT	B1		P7	P7	P7	ACT1	8'-0"	---
446	READING	CPT	B1		P7	P7	P7	ACT1	8'-0"	---
447	READING	CPT	B1		P7	P7	P7	ACT1	8'-0"	---
448	READING	CPT	B1		P7	P7	P7	ACT1	8'-0"	---
449	SOIL HOLD	WSF1	WSF1		SC	SC	SC	ACT2	8'-0"	---
450	CLEAN UTIL.	WSF1	WSF1		SC	SC	SC	ACT2	8'-0"	---
451	MINOR PROC.	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
453	US 1	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
454	TOILET	CT	CT	CT@48"	P4	P4	P4	ACT1	8'-0"	---
455	US 2	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
456	US 3	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
4W-17	SUBWAITING	LVT1	B2		P4	P4	P4	LVT1	8'-0"	---
4W-18	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1/GWB	VARIES	1
4W-19	RECEPTION	CPT	B1		P4	P4	P4	ACT1	8'-0"	---

NOTES  
 1. CEILING HEIGHT VARIES-SEE REFLECTED CEILING PLAN.  
 2. SEE INTERIOR ELEVATIONS FOR EXTENT OF PAINT COLORS.

### 5TH FLOOR ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WAIN	WALLS			CEILING		REMARKS
					N	E	S	W	MATL	
500	STAIR 11	LVT1	B2		P1	P2	P1	ACT1	8'-0"	---
501	ELEVATOR MACHINE ROOM	EPY	B1		P4	P4	P4	OTS	---	---

### 3RD FLOOR ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WAIN	WALLS			CEILING		REMARKS
					N	E	S	W	MATL	
300	STAIR 11	LVT1	B2		P1	P2	P1	ACT1	8'-0"	---
301	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1	8'-6"	---
302	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1	8'-0"	---
303	ANTEROOM	CT	CT		SC	SC	SC	GWB/SC	8'-0"	---
304	M LOCKER	CT	CT		P4	P4	P4	ACT2	8'-0"	---
305	M TOIL/SH	CT	CT	CT@48"	P4	P4	P4	GWB/P4	8'-0"	---
306	W LOCKER	CT	CT		P4	P4	P4	ACT2	8'-0"	---
307	W TOIL/SH	CT	CT	CT@48"	P4	P4	P4	GWB/P4	8'-0"	---
308	DECONTAMINATION	RES 1/2	RES1		SC	SC	SC	GWB/SC	8'-0"	---
309	HAC	RES1	RES1		SC	SC	SC	ACT2	8'-0"	---
310	IT	RES1	RES1		P4	P4	P4	OTS	12'-6"	---
311	WATER SYS.	RES1	RES1		SC	SC	SC	GWB/SC	8'-0"	---
312	COMPRESSOR	RES1	RES1		P4	P4	P4	OTS	12'-6"	---
313	DECONTAMINATION	RES1	RES1		SC	SC	SC	GWB/SC	8'-0"	---
314	SCOPE CLEAN	RES1	RES1		SC	SC	SC	GWB/SC	8'-0"	---
315	DECON RECEIVING	RES 1/2	RES1		SC	SC	SC	GWB/SC	8'-0"	---
316	CART WASH	RES1	RES1		CT1	CT1	CT1	GWB/SC	10'-0"	---
317	MANUAL WASH	RES1	RES1		CT1	CT1	CT1	GWB/SC	8'-0"	---
318	ELECT	EPY	B1		P4	P4	P4	OTS	12'-6"	---
319	STOR	RES1	RES1		SC	SC	SC	GWB/SC	8'-0"	---
320	PREP & SUPPLY	LVT2	B1		P4	P4	P4	ACT1	8'-0"	---
321	BREAKOUT	LVT2	B1		SC	SC	SC	ACT2	8'-0"	---
322	ALCOVE	LVT1	B2		P4	P4	P4	ACT1	8'-0"	---
323	DISPATCH	WSF1	WSF1		SC	SC	SC	ACT2	8'-0"	---
324	CORRIDOR	WSF1	WSF1		SC	SC	SC	ACT2	8'-0"	---
325	CORRIDOR	WSF1	WSF1		SC	SC	SC	ACT2	8'-0"	---
326	MEDIVATORS	RES1	RES1		SC	SC	SC	GWB/SC	8'-0"	---
327	PREP & PACK	RES 1/2	RES1		SC	SC	SC	GWB/SC	8'-0"	---
328	PREP & PACK	RES1	RES1		SC	SC	SC	GWB/SC	8'-0"	---
329	STEAM STERIL	RES1	RES1		SC	SC	SC	GWB/SC	8'-0"	---
330	M LOCKER	CT	CT	CT@48"	P4	P4	P4	ACT1	8'-0"	---
331	W LOCKER	CT	CT	CT@48"	P4	P4	P4	ACT1	8'-0"	---
332	PSA	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
333	STERILE/NON-STERILE STOR	WSF1	WSF1		SC	SC	SC	ACT2	8'-0"	---
334	HAC	CT	CT	CT@48"	SC	SC	SC	ACT2	8'-0"	---
335	LOUNGE	LVT1	B2		P4	P5	P4	ACT1	8'-0"	---
336	TOILET	CT	CT	CT@48"	P4	P6	P4	ACT1	8'-0"	---
337	STAIR 10	LVT1	B2		P1	P1	P1	ACT1	8'-0"	---
338	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1	8'-0"	---
339	COPY	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
340	CONFERENCE	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
341	CHIEF OFFICE	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
342	CLERK	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
343	ASSIST CHIEF	CPT	B1		P4	P4	P4	ACT1	8'-0"	---
3W-20	OFFICE	EXIST.	B1		P4	P4	P4	EXIST.	EXIST.	---
3W-21	CORRIDOR	LVT 1/2/3	B2		P4	P4	P4	ACT1	8'-0"	---
3W-22	OFFICE	EXIST.	B1		P4	P4	P4	EXIST.	EXIST.	---

### FINAL SUBMITTAL

Revisions:	Date	CONSULTANTS:		ARCHITECT: 	590 Means Street NW, Suite 200 Atlanta, GA 30318 404.214.9774	Drawing Title: <b>FINISH SCHEDULES</b>	Project Number: <b>667-083</b>	Project Title: <b>EXPAND RADIOLOGY AND SPS OVERTON BROOKS VAMC</b>	Building Number: <b>1</b>	Drawing Number: <b>A602</b>	Office of Construction and Facilities Management 