



- 1 REMOVE SUPPLY DUCT TO APPROXIMATE LOCATION AND PREPARE DUCT FOR NEW. COORDINATE THE SCOPE OF REMOVAL OF DUCT FOR NEW LOCATION OF NEW PIPING.
- 2 TEMPORARY REMOVE 6" DUCT FOR NEW PIPING. SEE NEW WORK SHEETS.
- 3 RELOCATE EXISTING VARIABLE VOLUME BOXES AS NECESSARY TO ROUTE NEW PIPING. SEE NEW WORK SHEETS.
- 4 REMOVE EXHAUST DUCT TO APPROXIMATE SCOPE OF WORK IN MECHANICAL ROOM AND PREPARE FOR NEW ROOM. REMOVE EXISTING ROOF-TOP EXHAUST FAN AND TURN OVER TO GOVERNMENT. SEE NEW WORK SHEETS.
- 5 REMOVE SUPPLY DUCT TO APPROXIMATE LOCATION AND PREPARE DUCT FOR NEW. SEE NEW WORK SHEETS.
- 6 REMOVE EXISTING 3" STEAM PRV TIE THROUGH ROOF. PROVIDE NEW VENT AS INDICATED ON NEW WORK PLAN.
- 7 REMOVE EXISTING VENT CAP ON CONDENSATE PUMP PIPING AT THIS LOCATION. PROVIDE NEW VENT AS INDICATED ON NEW WORK PLAN.

[illegible]

**APPLIED ENGINEERING
SOLUTIONS**
440 Martin Luther King, Jr. Blvd., Suite 401
Macon, Georgia 31201
Phone: (478) 314-1270 - Fax: (478) 314-1271
www.aes-pe.com



TOLAND
MIZELL
MOLNAR

VA |  U.S. Department
of Veterans Affairs