

Steelcase Universal Storage Cabinet or Equal Salient Characteristics

1. General

Product installed in the State of California only: Anchor brackets secure the cabinet to the floor in compliance with OSHPD (California Office of Statewide Planning and Development) rules. This is a requirement for anchorage of furniture in healthcare facilities.

Cabinet is visually compatible with manufacturer's systems products

2. Warranty Requirements

Manufacturer offers a lifetime warranty that product is free from defects in materials and workmanship (includes shipping, parts and labor for the repair or replacement of defective item.)

- a. The following lifetime warranty exceptions are allowed:
 - a. Laminates and wood veneers have a minimum 10 year warranty.
 - b. Paint colorfastness has a 4 year warranty.

3. Technical Specification and Code Requirement

- a. Meets or exceeds ANSI/BIFMA X5.9 – 2004 Storage Unit Tests
- b. Note: ANSI/BIFMA X5.2-1997 Lateral File is considered obsolete, replaced by X5.9-2004
- c. Has documented proof that packaged product undergone shipping vibration and shock testing to ensure product received at customer site is undamaged.

4. Environmental Features

- a. Is constructed free of environmentally hazardous materials such as PVC, CFC, solvent-based adhesives, heavy metals (chrome, lead and mercury) and benzene.
- b. Is constructed free of environmentally hazardous processes such as those that produce VOC's and deplete ozone:
 - a. Paint is VOC-free powder coat type. Powder coat paint overspray is to be collected, reprocessed, and used on interior components.
 - b. Water-based stains and topcoats are available for specifying a wood finish. These help reduce VOC emissions.
- c. Recyclability:
 - a. Storage cabinet file with steel top are up to 90% recyclable at end of life.
- d. Files are shipped in heavy-duty, recyclable stretch wrap to reduce the amount of corrugated board needed.
- e. Powder coat paint overspray used in the finishing process of this product is collected by the Manufacturer, reprocessed, and used on interior components.

- f. In lieu of disposing furniture in a landfill at the end of its useful life, the Manufacturer provides opportunities for the Customer to recycle, resell or refurbish their used furniture

5. Dimensions and Features

- a. Storage Cabinet
 - a. Depths: 18"D
 - b. Widths: 36"W
 - c. Heights: 28"H
 - d. A no top version is available for a 28"H storage cabinet to be located beneath a worksurface.
- b. Overall Storage Features
 - a. Unit shall ship with a lock plug and have the option of field installed master lock cores.
 - b. Lock is easily accessible to a seated user.
 - c. Keys and locks are numbered for easy identification.
 - d. Counterweight is optional

6. Construction Method

- a. Case back is constructed of at least 22 gauge steel, hemmed on the exposed sides for safety and stiffness.
- b. Is reinforced with welded 22 gauge horizontal steel braces.
- c. Case sides are constructed of at least 22 gauge steel, flanged on top and sides for safety and stiffness.
- d. Is reinforced with welded 20 gauge vertical steel upright braces with slots for precision placement of adjustable shelves.

7. Surface Materials

- a. Storage cabinet body, steel tops and shelves, are available in at least 19 paint finishes.
 - a. Paint offering includes both smooth and textured metallic finishes.
 - b. Color match finishes are also available as an option
 - c. Pulls on proud doors are available in 4 plated metal finishes
 - d. Lock core option are available in polished chrome finish
- b. Optional counterweight cover matches the paint finish of the cabinet body.

8. Miscellaneous

- a. Service parts are available.
- b. Customer testimonials/endorsements are made available upon request.
- c. Manufacturer has the ability to create custom solutions based on customer's needs.
- d. Detailed assembly directions are available in paper and electronically