HVAC UNIT

REINSTALL LIGHTNING RODS - TYPICAL RECERTIFY SYSTEM

REMOVE & REPLACE METAL VALLEY FLASHING TYPICAL.

EXISTING STANDING SEAM METAL ROOF TO REMAIN. NOT IN CONTRACT

REMOVE SLATE SHINGLES AT WALLS OF PENTHOUSE. INSTALL NEW UNDERLAYMENT AND NEW POLYMERIC SLATE SHINGLE SYSTEM PER THE SPECIFICATIONS AND DETAILS.

GUTTER OUTLET AND DOWNSPOUT TYP. REPLACE LEADER HEAD AND DOWNSPOUT TO MATCH EXISTING, TYP.

EXTERIOR CORRIDOR ROOF TO BUILDING 39. N.I.C.

EXISTING CAPTURED GUTTER COAT WITH LIQUID MEMBRANE PER SPECIFICATIONS TYPICAL ALL GUTTERS.

GUTTER OUTLET AND DOWNSPOUT TYP. REPLACE LEADER HEAD AND DOWNSPOUT TO MATCH EXISTING, TYP.

AC

AC

KEY NOTES

01 EXISTING VENT STACK. INSTALL NEW LEAD BOOT SEE DETAIL 4/A6.1

02 REMOVE AND REPLACE EXISTING SLATE AND UNDERLAYMENT, TYPICAL ENTIRE ROOF.

03 EXISTING LIGHTNING PROTECTION MAST TYPICAL. REMOVE ALL MASTS, COMPONENTS ETC. AS NEEDED TO INSTALL NEW ROOF. REWORK, REINSTALL AND RECERTIFY LIGHTNING PROTECTION SYSTEM PER SPECIFICATIONS.

04 EXISTING ROOF HATCH TO BE REMOVED IN BASE BID. INSTALL NEW ROOF HATCH AND REFLASH.

05 REMOVE EXISTING EAVE FLASHING AND INSTALL NEW COPPER FLASHING PER DETAIL 1/A6.2 TYPICAL AT ALL GABLE ENDS.

1 BUILDING 40 - ROOF PLAN

SCALE: 1/8"=1'-0"

Revisions	Date

BIRCHFIELD PENUEL & ASSOCIATES, ARCHITECTS

2805 CRESCENT AVENUE · SUITE 200 ·BIRMINGHAM, ALABAMA 35209

STATE OF ALABAMA
CHARLES E. PENUEL
NO. 2395
WILLIAM C. BIRCHFIELD
NO. 2341
BIRMINGHAM, ALABAMA
REGISTERED ARCHITECT

Replace Roofs - Building 39 - 40
Department of Veterans Affairs
MEDICAL CENTER
TUSCALOOSA, ALABAMA

Drawing Title: BUILDING 40 - ROOF PLAN

Approved: Chief Engineer

Project Title: REPLACE ROOFS - BUILDINGS 39 & 40 DEPARTMENT OF VETERANS AFFAIRS

Date: 08-30-2010

Project Number: 679-10-103

Building Numbers: 39 & 40

Checked: WCB

Drawn: DB

Location: VA MEDICAL CENTER TUSCALOOSA, ALABAMA

DRAWING NO. 40-A2.1

Dwg. 05 Of 10

Veterans Administration