

- A. Means and methods used in the demolition efforts are the sole responsibility of the contractor.
- B. Original Building 322 construction drawings are available for additional information regarding the demolition effort. Building 322 has been remodeled since original construction and interior partitions, finishes, materials, etc. may vary from original construction drawings. See demolition drawings for current configuration of interior partitions. Contractor to verify all condition prior to demolition efforts.
- C. Remove all existing partitions shown with dashed line. Repair wall and floor finishes to match adjacent surfaces at areas of removal or scheduled new surfaces as required.
- D. Computer and communication cables and/or other wiring, piping, tubing, etc. serving other areas and functions located above ceiling or in walls of area to be remodeled shall be maintained during demolition/construction process. Coordinate any required changes to these systems with the C.O.R.
- E. See Hazardous Materials Abatement Specifications for requirements for removal of hazardous materials prior to demolition.
- F. Salvage removed ceiling tiles for use in patching and repairing existing ceilings where new walls occur.

2.03	Existing corridor wall to remain.
2.50	Remove existing stud partition wall construction or furring indicated in its entirety.
2.51	Remove existing door, frame and associated hardware. Re-use existing security access controls for new work.
2.66	Remove existing plumbing fixture, re-use plumbing connection for new work.
2.67	Remove existing wall and base cabinets and countertop.
2.69	Remove existing lockers and provide storage for re-use.
2.70	Limits of existing suspended acoustical ceiling tile, grid, lights and all ceiling mounted accessories this area to be removed.
2.71	Limits of VCT flooring and rubber base removal. Prepare subfloor for new scheduled finish and base this area.
2.90	Existing medical gas system to remain for new work.

