

**STATEMENT OF WORK
ABATEMENT IN W634
VA MEDICAL CENTER MANCHESTER NH**

1. Introduction

The objective of this project is to remove, clean-up and disposal of ACM flooring and asbestos contaminated elements in an appropriate regulated area in the following approximate quantities: 810 square feet of flooring materials and associated mastic – floor tiles below carpet (2% chrysotile) and black mastic associated with the tiles (5% chrysotile), as required by drawings and specifications. Work location is W633, W633A and W634 in Building 1.

Work is to be performed by a New Hampshire licensed asbestos abatement contractor.

ALL FLOOR COVERINGS SHALL BE REMOVED AS ASBESTOS
CONTAINING MATERIALS
ALL WORK IS TO BE DONE OFF HOURS.

2. Period of Performance

This project has a thirty day performance period.