




**CEILING DEMOLITION PLAN GENERAL NOTES:**

- DISMOUNT AND RETAIN CEILING MOUNTED ITEMS INCLUDING EXISTING LIGHTING FIXTURES, PRESERVE THE REMAINING FOR REUSE. (E.G. EXIT LIGHTS, ESCUTCHEONS, BEAUTY RINGS, ETC.)
- CURTAIN/CURTAIN TRACK, SMOKE DETECTORS, CAMERAS, SPEAKERS, ETC.) WORK INVOLVING EXIT LIGHTS, SPEAKERS, SMOKE DETECTORS, CAMERAS SHALL BE COORDINATED WITH THE COTR AND MUST REMAIN IN OPERATION UNTIL THE PROJECT IS COMPLETED.
- REMOVE AND DISPOSE OF CEILING TILES, EXISTING CEILING GRID TO REMAIN UNALTERED AND UNDAMAGED. REPAIR CEILING GRID AS NEEDED.
- MIRROR AND DIFFUSER LIGHTING GRILLES SHALL REMAIN UNDAMAGED AND UNALTERED.
- EXISTING LIGHTING FIXTURES TO REMAIN, FOLLOW LOCKOUT/TAGOUT PROCEDURES. PROVIDE TEMPORARY LIGHTING AS NEEDED.
- ALL WORK SHALL BE PERFORMED IN CONFORMANCE WITH THE LATEST VERSION OF NEC.

		VA Northern Indiana Health Care System, Fort Wayne 2121 Lake Avenue Fort Wayne, IN 46805	Approved: Medical Center Director Daniel D. Hendee, FACHE	Drawing Title  <b>REFLECTED CEILING PLAN- 2nd Floor</b>	Project Title  <b>Interior Halls and Walls</b>		Project Number <b>610A4-11-149</b>					
			Approved: Associate Director for Operations Helen Rhodes				Building Number <b>1</b>					
			Approved: Engineering Service Charles Applewhite	Approved: Project Director		Location <b>VA NIHCS, Fort Wayne, IN</b>		Drawing Number  <b>A-105</b>				
						Date <b>08/05/2011</b>		Checked <b>CDA</b>		Drawn <b>VM</b>	Dwg. <b>5</b> of <b>12</b>	
Revisions:												

