ROOM FINISH SCHEDULE ROOM ROOM NAME **FLOOR** TRIM REMARKS BASE C100 | AUDITORIUM CORRIDOR PAINT GWB AND EXPOSED CONCRETE ABOVE (PT4) C101 | CHAPEL CORRIDOR C102 | CORRIDOR A167 | VENDING MACHINE ROOM C103 ELEVATOR LOBBY VSF1, VSF2 RCB1, TCB C104 | SERVICE ELEVATOR CORRIDOR VSF1, VSF2 RCB1 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C105 MAIN CORRIDOR (WEST-EAST) VSF1, VSF2 | RCB1, PT6, TCB | PT1 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C106 | CORRIDOR C200 CORRIDOR RCB1 C201 | ELEVATOR LOBBY VSF1, VSF2 | RCB1, PT6, TCB | PT2 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) VSF1, VSF2 C202 | MAIN CORRIDOR (WEST-EAST) | RCB1, PT6, TCB | PT1 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) PAINT GWB (PT4), PAINT CGMCT (PT6) SERVICE ELEVATOR CORRIDOR C204 CORRIDOR RCB1. PT6 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) VSF1, VSF2 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C300 | ELEVATOR LOBBY VSF1, VSF2 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C301 | MAIN CORRIDOR (WEST-EAST) C302 CORRIDOR PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) VSF1 C303 | SERVICE ELEVATOR CORRIDOR INSTALL VSF (VSF1) IN RM 321B, PAINT CGMCT (PT6) VSF1 VSF1 RCB1, PT6 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C304 | CORRIDOR 328 WAITING AREA VSF1, VSF2 RCB1 PT3 PT3 | ACT1, GWB | 9'-2", 7'-4" 385 | NURSES' STATION VSF1 RCB1 C400 | ELEVATOR LOBBY VSF1, VSF2 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C401 | MAIN CORRIDOR (WEST-EAST) VSF1, VSF2 | RCB1, PT6, TCB | PT1 C402 CORRIDOR VSF1 7'-10" PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C403 CORRIDOR VSF1 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C404 CORRIDOR PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C405 | SERVICE ELEVATOR CORRIDOR PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) RCB1, PT6 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C406 CORRIDOR 412 WAITING AREA VSF1, VSF2 VSF1 472 | NURSES' STATION VSF1, VSF2 PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C500 | ELEVATOR LOBBY C501 | MAIN CORRIDOR (WEST-EAST) VSF1, VSF2 | RCB1, PT6, TCB | PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C502 | CORRIDOR PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) C503 CORRIDOR PAINT METAL HATCHWAY (PT4), PAINT CGMCT (PT6) C504 | SERVICE ELEVATOR CORRIDOR 528 WAITING AREA PT3 PT3 PT3 PT3 ACT1 C001 ELEVATOR LOBBY COO2 | MAIN CORRIDOR (WEST-EAST) PAINT EXISTING COVE GLAZED MASONRY CLAY TILE (PT6) CO05 EMS CORRIDOR

E = EXISTINGU.N.O. = UNLESS NOTED OTHERWISE NIC = NOT IN CONTRACT TME = NEW TO MATCH EXISTING ACT-1 = NEW ACOUSTIC CEILING TILE VCT = VINYL COMPOSITION TILE GCT= GLAZED COVE TILE TERR = TERRAZZO

VSF-1 = SHEET VINYL FLOORING WOOD PATTERN: TROPICAL BEECH/LIGHTER 'WOOD' - PATTERN MUST BE SELECTED AND APPROVED BY VANIHCS INTERIOR DESIGNER

WOOD PATTERN: DARK OAK/ DARK 'WOOD' - CONTRASTING COLOR/ PATTERN MUST BE SELECTED AND APPROVED BY VA INTERIOR

VSF-2 = SHEET VINYL FLOORING

LCT-1 = LINOLEUM COMPOSITE TILE (WITH

RECYCLABLE CONTENT)

RCB-1 = RUBBER COVE BASE

PT-1 = SHERWIN WILLIAMS PAINT SW 6135 ECRU OR EQUAL - EGGSHELL FINISH / NO VOC PAINT ONLY PT-2* = SHERWIN WILLIAMS PAINT SW 6500 OPEN SEAS OR EQUAL - EGGSHELL

ACCENT WALLS ONLY PT-3 = SHERWIN WILLIAMS PAINT SW 7728 SPROUT OR EQUAL - EGGSHELL FINISH - / NO VOC PAINT ONLY

FINISH / NO VOC PAINT ONLY

ACCENT WALLS ONLY PT-4 = CEILING PAINT- SHERWIN WILLIAMS SW 7008 ALABASTER OR EQUAL - EGGSHELL FINISH / NO VOC PAINT ONLY

PT-5 = DOOR FRAMES, WINDOW FRAMES, AND ELEVATOR DOOR FRAMES. COLOR: TBD to match resilient rubber base color

EGGSHELL FINISH/ NO VOC PAINT ONLY PT-6 = PAINTED COVED BASE COLOR - HIGH PERFORMANCE COATING - COLOR: TBD to match resilient rubber base color - EGGSHELL FINISH/ NO VOC PAINT ONLY

ALL INTERIOR FINISHES MUST BE APPROVED BY VANIHCS INTERIOR DESIGNER.

*OR EQUAL. THE INCLUSION OF A BRAND NAME AND SPECIFIC COLOR IS FOR THE EXPRESS PURPOSE OF OBTAINING THIS SPECIFIC COLOR, WHICH IS FURTHER DEFINED BY IT'S SALIENT CHARACTERISTICS: "HUE, VALUE AND INTENSITY". ANY OTHER COLOR MUST BE APPROVED BY VA

FINISH GENERAL NOTES:

COVER AND PROTECT FROM PAINT: CORNER GUARDS, HANDRAILS, BUILT-IN CABINETS (I.E. FIRE EXTINGUISHERS, FIRE ALARM CABINETS, ETC.), OUTLETS (ELECTRICAL AND DATA), COVER PLATES,

PULL STATIONS, ETC. . PATCH AND REPAIR ALL WALLS PRIOR TO PAINTING. 3. PAINT ALL WALL SURFACES (NEW AND EXISTING), PLASTER/GYPSUM CEILINGS AND BULK HEADS, PLASTER/GYPSUM WINDOW SILLS, NOTED DOORS, AND ALL DOOR FRAMES AS NOTED ON THE ROOM FINISH SCHEDULE. PREP SURFACES PER MANUFACTURERS' RECOMMENDATIONS.

3.1. ONE (1) COAT PRIME 3.2. TWO (2) COATS PAINT

4. DO NOT REMOVE OR PAINT RATING TAGS ON DOORS AND/OR DOOR FRAMES. PROTECT ALL DOOR HARDWARE FROM PAINT. 6. CEILING GRID TO REMAIN UNDAMAGED AND

UNALTERED. (EXCEPT 5TH FLOOR DEMO) PROTECT FROM PAINT. 7. REMOVE ALL EXISTING DOOR SILENCERS AND REPLACE WITH NEW AFTER PAINTING OF ALL DOOR

FRAMES. INSTALL NEW IN ALL LOCATIONS THAT OLD WAS REMOVED. 8. ALL DIMENSIONS ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY.

PAINT ENTIRE DOOR FRAME AND/OR WINDOW FRAME (INSIDE AND OUT). PREP PER PAINT MANUFACTURERS' RECOMMENDATIONS.

2. PAINT ENTIRE DOOR AND ENTIRE DOOR FRAME. PREP PER PAINT MANUFACTURERS' RECOMMENDATIONS.

3. PREP AND PAINT ELEVATOR DOOR FRAMES (FRAMES ONLY). 4. USE NO VOC PAINT ONLY.

1. PREPARE FLOOR, PROVIDE AND INSTALL VINYL SHEET GOODS WITH BREAK PATTERN ON CORRIDORS AS

INDICATED. CONTRACTOR TO FIELD VERIFY. 2. PROVIDE AND INSTALL FLOOR LEVELING COMPOUND AS NECESSARY TO PREPARE THE FLOOR TO RECEIVE NEW

FINISHES. 3. PROVIDE AND INSTALL NEW RUBBER COVE BASE (RCB) -

CONTRACTOR TO FIELD VERIFY. 4. PROVIDE AND INSTALL MANUFACTURER RECOMMENDED

TRANSITIONS WHERE NEW SHEET FLOORING MEETS EXISTING CARPET FLOORING.

5. USE WATER-BASED MASTIC ADHESIVES. 6. REDUCE OUTGASSING OF SHEET VINYL FLOORING AND

RUBBER BASE BY UNROLLING IT OUTDOORS/VENTILATED AREA PRIOR TO ON SITE INSTALLATION.

Drawing Title Project Title Approved: Medical Center Director Daniel D. Hendee, FACHE Interior Halls and Walls Finish Schedule and Notes Approved: Associate Director for Operations Helen Rhodes Approved: Project Director VA NIHCS, Fort Wayne, IN Approved: Engineering Service Charles Applewhite CDA 08/05/2011



VA Northern Indiana Health Care System, Fort Wayne 2121 Lake Avenue

Fort Wayne, IN 46805

VA FORM 08-6231, OCT 1978

Drawing Number

Project Number 610A4-11-149

A-204

Dwg.12 of 12