

SECTION 31 31 16.13  
CHEMICAL TERMITE CONTROL

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 QUALITY ASSURANCE
  - 1.3.1 Qualifications
  - 1.3.2 Safety Requirements
- 1.4 DELIVERY, STORAGE, AND HANDLING
  - 1.4.1 Delivery
  - 1.4.2 Inspection
  - 1.4.3 Storage
  - 1.4.4 Handling
- 1.5 SITE CONDITIONS
  - 1.5.1 Soil Moisture
  - 1.5.2 Runoff and Wind Drift
    - 1.5.2.1 Vapor Barriers and Waterproof Membranes
    - 1.5.2.2 Utilities and Vents
  - 1.5.3 Placement of Concrete
- 1.6 WARRANTY

PART 2 PRODUCTS

- 2.1 TERMITICIDES

PART 3 EXECUTION

- 3.1 VERIFICATION OF MEASUREMENT
- 3.2 TECHNICAL REPRESENTATIVE
- 3.3 SITE PREPARATION
  - 3.3.1 Ground Preparation
  - 3.3.2 Verification
  - 3.3.3 Foundation Exterior
  - 3.3.4 Utilities and Vents
  - 3.3.5 Crawl and Plenum Air Spaces
  - 3.3.6 Application Plan

- 3.4 TERMITICIDE TREATMENT
  - 3.4.1 Equipment Calibration and Tank Measurement
  - 3.4.2 Mixing and Application
  - 3.4.3 Treatment Method
    - 3.4.3.1 Surface Application
    - 3.4.3.2 Rodding and Trenching
  - 3.4.4 Sampling
- 3.5 CLEAN UP, DISPOSAL, AND PROTECTION
  - 3.5.1 Clean Up
  - 3.5.2 Disposal of Termiticide
  - 3.5.3 Protection of Treated Area
- 3.6 CONDITIONS FOR SATISFACTORY TREATMENT
  - 3.6.1 Equipment Calibrations and Measurements
  - 3.6.2 Testing
  - 3.6.3 Disturbance of Treated Soils
  - 3.6.4 Termites Found Within the Warranty Period
- 3.7 RE-TREATMENT

-- End of Section Table of Contents --

## PART 1 GENERAL

## 1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

DODI 4150.07

DOD Pest Management Program

## 1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 23

## SUBMITTAL PROCEDURES:

## SD-03 Product Data

Termiticide Application Plan  
 Termiticides  
 Foundation Exterior  
 Utilities and Vents  
 Crawl and Plenum Air Spaces  
 Verification of Measurement  
 Application Equipment  
 Warranty

## SD-04 Samples

Termiticides

## SD-06 Test Reports

Equipment Calibration and Tank Measurement  
 Soil Moisture  
 Quality Assurance

## SD-07 Certificates

Qualifications

## 1.3 QUALITY ASSURANCE

Comply with DODI 4150.07 for requirements on Contractor's licensing, certification, and record keeping. Maintain daily records using the Pest Management Maintenance Record, DD Form 1532-1, or a computer generated equivalent, and submit copies of records when requested by the Contracting Officer. These forms may be obtained from the main web site:  
<https://www.dtic.mil/whs/directives/infomgt/forms/dd/ddforms1500-1999.htm>

Upon completion of this work, submit the Pest Management Report DD Form 1532, or an equivalent computer product, to the Integrated Pest Management Coordinator. This form identifies the target pest, type of operation, brand name and manufacturer of pesticide, formulation, concentration or rate of application used.

### 1.3.1 Qualifications

For the application of pesticides, use the services of a applicator whose principal business is pest control. The applicator shall be licensed and certified in the state where the work is to be performed. Termiticide applicators shall also be certified in the U.S. Environmental Protection Agency (EPA) pesticide applicator category which includes structural pest control. Submit a copy of the pest control business license and pesticide applicator certificate(s).

- a. Have personnel with a commercial state certification as required by DODI 4150.07.
- b. Provide a submittal with the following information to the Contracting Officer and installation Integrated Pest Management Coordinator:
  - (1) Quantity of pesticide used.
  - (2) Rate of dispersion.
  - (3) Percent of use.
  - (4) Total amount used.]

### 1.3.2 Safety Requirements

Formulate, treat, and dispose of termiticides and their containers in accordance with label directions. Draw water for formulating only from sites designated by the Contracting Officer, and fit the filling hose with a backflow preventer meeting local plumbing codes or standards. The filling operation shall be under the direct and continuous observation of a contractor's representative to prevent overflow. Secure pesticides and related materials under lock and key when unattended. Ensure that proper protective clothing and equipment are worn and used during all phases of termiticide application. Dispose of used pesticide containers off Government property.

## 1.4 DELIVERY, STORAGE, AND HANDLING

### 1.4.1 Delivery

Deliver termiticide material to the site in the original unopened containers bearing legible labels indicating the EPA registration number and manufacturer's registered uses. All other materials, to be used on site for the purpose of termite control, shall be delivered in new or otherwise good condition as supplied by the manufacturer or formulator.

### 1.4.2 Inspection

Inspect termiticides upon arrival at the job site for conformity to type and quality in accordance with paragraph TERMITICIDES. Each label shall bear evidence of registration under the Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA), as amended or under appropriate regulations of the host county. Other materials shall be inspected for conformance with specified requirements. Remove unacceptable materials from the job site.

### 1.4.3 Storage

Contractors shall not store pesticides on the installation unless it is written into the contract.

### 1.4.4 Handling

Termiticides shall be handled and mixed in accordance with the

manufacturer's label and SDS, preventing contamination by dirt, water, and organic material. Protect termiticides from weather elements as recommended by the manufacturer's label and Safety Data Sheet (SDS). Spill kits must be maintained on pest control vehicles and must be available at the mixing site. Termiticide mixing must be conducted in an area with adequate spill containment.

## 1.5 SITE CONDITIONS

The following conditions will determine the time of application.

### 1.5.1 Soil Moisture

Soils to be treated shall be tested immediately before application. Test soil moisture content to a minimum depth of 75 mm 3 inches. The soil moisture shall be as recommended by the termiticide manufacturer. The termiticide will not be applied when soil moisture exceeds manufacturer's recommendations because termiticides do not adhere to the soil particles in saturated soils.

### 1.5.2 Runoff and Wind Drift

Do not apply termiticide during or immediately following heavy rains. Applications shall not be performed when conditions may cause runoff or create an environmental hazard. Applications shall not be performed when average wind speed exceeds 16 km 10 miles per hour. The termiticide shall not be allowed to enter water systems, aquifers, or endanger humans or animals.

#### 1.5.2.1 Vapor Barriers and Waterproof Membranes

Termiticide shall be applied prior to placement of a vapor barrier or waterproof membrane.

#### 1.5.2.2 Utilities and Vents

Prior to application, HVAC ducts and vents located in treatment area shall be turned off and blocked to protect people and animals from termiticide. Submit written verification that utilities and vents have been located and treated as specified.

### 1.5.3 Placement of Concrete

Place concrete covering treated soils as soon as the termiticide has reached maximum penetration into the soil. Time for maximum penetration shall be as recommended by the manufacturer.

## 1.6 WARRANTY

Provide a 5-year written warranty against infestations or reinfestations by subterranean termites of the buildings or building additions constructed under this contract. Warranty shall include annual inspections of the buildings or building additions. If live subterranean termite infestation or subterranean termite damage is discovered during the warranty period, and the soil and building conditions have not been altered in the interim:

- a. Retreat the soil and perform other treatment as may be necessary for elimination of subterranean termite infestation;
- b. Repair damage caused by termite infestation; and

- c. Reinspect the building approximately 180 days after the retreatment.

## PART 2 PRODUCTS

### 2.1 TERMITICIDES

Submit manufacturer's label and SDS for termiticides proposed for use. Provide termiticides currently registered by the EPA or approved for such use by the appropriate agency of the host county. Non-repellant termiticides shall be selected for maximum effectiveness and duration after application. The selected termiticide shall be suitable for the soil and climatic conditions at the project site and applied at the highest labeled rate. Submit samples of the pesticides used in this work. The Contracting Officer may draw, at any time and without prior notice, from stocks at the job site; should analysis, performed by the Government, indicate such samples to contain less than the amount of active ingredient specified on the label, work performed with such products shall be repeated, with pesticides conforming to this specification, at no additional cost to the Government.

## PART 3 EXECUTION

### 3.1 VERIFICATION OF MEASUREMENT

Once termiticide application has been completed, measure tank contents to determine the remaining volume. The total volume measurement of used contents for the application shall equal the established application rate for the project site conditions. Provide written verification that the volume of termiticide used meets the application rate.

### 3.2 TECHNICAL REPRESENTATIVE

A DOD certified pesticide applicator or Pest Management Quality Assurance Evaluator (QAE)/Performance Assessment Representative (PAR) shall be the technical representative, shall be present at all meetings concerning treatment measures for subterranean termites, and shall be present during treatment application. The command Integrated Pest Management Coordinator shall be contacted prior to starting work.

### 3.3 SITE PREPARATION

Work related to final grades, landscape plantings, foundations, or any other alterations to finished construction which might alter the condition of treated soils, must be coordinated with this specification.

#### 3.3.1 Ground Preparation

Eliminate food sources by removing debris from clearing and grubbing and post construction wood scraps such as ground stakes, form boards, and scrap lumber from the site, before termiticide application begins.

#### 3.3.2 Verification

Before work starts, verify that final grades are as indicated and smooth grading has been completed in accordance with Section 31 00 00 EARTHWORK. Soil particles shall be finely graded with particles no larger than 25 mm 1

inch and compacted to eliminate soil movement to the greatest degree.

### 3.3.3 Foundation Exterior

Provide written verification that final grading and landscape planting operations will not disturb treatment of the soil on the exterior sides of foundation walls, grade beams, and similar structures.

### 3.3.4 Utilities and Vents

Provide written verification that the location and identity of HVAC ducts and vents, water and sewer lines, and plumbing have been accomplished prior to the termiticide application.

### 3.3.5 Crawl and Plenum Air Spaces

Provide written verification that the location and identity of crawl and plenum air spaces have been accomplished prior to the termiticide application.

### 3.3.6 Application Plan

Submit a Termiticide Application Plan with proposed sequence of treatment work with dates and times for approval before starting the specified treatment. Include the termiticide trade name, EPA registration number, chemical composition, formulation, concentration of original and diluted material, application rate of active ingredients, method of application, area/volume treated, and amount applied. Also include a copy of the pest control business license and pesticide applicator certificate(s).

## 3.4 TERMITICIDE TREATMENT

### 3.4.1 Equipment Calibration and Tank Measurement

Submit a listing of equipment to be used. Immediately prior to commencement of termiticide application, calibration tests shall be conducted on the application equipment to be used and the application tank shall be measured to determine the volume and contents. These tests shall confirm that the application equipment is operating within the manufacturer's specifications and will meet the specified requirements. Submit written certification of the equipment calibration test results within 1 week of testing.

### 3.4.2 Mixing and Application

Formulating, mixing, and application shall be performed in the presence of a DOD certified pesticide applicator, Pest Management QAE/PAR, or Integrated Pest Management Coordinator. A closed system is recommended as it prevents the termiticide from coming into contact with the applicator or other persons. Water for formulating shall only come from designated locations. Filling hoses shall be fitted with a backflow preventer meeting local plumbing codes or standards. Overflow shall be prevented during the filling operation. Spill kits must be maintained on pest control vehicles and must be available at the mixing site. Termiticide mixing must be conducted in an area that has been designated by the government representative and that has adequate spill containment. Prior to each day of use, the equipment used for applying termiticides shall be inspected for leaks, clogging, wear, or damage. Any repairs are to be performed immediately.

### 3.4.3 Treatment Method

For areas to be treated, establish complete and unbroken vertical and horizontal soil poison barriers between the soil and all portions of the intended structure which may allow termite access to wood and wood related products. Applications to crawl spaces shall be made in accordance with (IAW) label directions. Applications shall not be made to crawl space areas that are used as plenum air spaces.

#### 3.4.3.1 Surface Application

Use surface application for establishing horizontal barriers. Surface applicants shall be applied as a coarse spray and provide uniform distribution over the soil surface. Termiticide shall penetrate a minimum of 25 mm 1 inch into the soil, or as recommended by the manufacturer.

#### 3.4.3.2 Rodding and Trenching

Use rodding and trenching for establishing vertical soil barriers. Trenching shall be to the depth of the foundation footing. Width of trench shall be as recommended by the manufacturer, or as indicated. Rodding or other approved method may be implemented for saturating the base of the trench with termiticide. Immediately after termiticide has reached maximum penetration as recommended by the manufacturer, backfilling of the trench shall commence. Backfilling shall be in 150 mm 6 inch rises or layers. Each rise shall be treated with termiticide.

#### 3.4.4 Sampling

The Contracting Officer may draw from stocks at the job site, at any time and without prior notice, take samples of the termiticides used to determine if the amount of active ingredient specified on the label is being applied.

### 3.5 CLEAN UP, DISPOSAL, AND PROTECTION

Once application has been completed, proceed with clean up and protection of the site without delay.

#### 3.5.1 Clean Up

The site shall be cleaned of all material associated with the treatment measures, according to label instructions, and as indicated. Excess and waste material shall be removed and disposed off site.

#### 3.5.2 Disposal of Termiticide

Dispose of residual termiticides and containers off Government property, and in accordance with label instructions and EPA criteria.

#### 3.5.3 Protection of Treated Area

Immediately after the application, the area shall be protected from other use by erecting barricades and providing signage as required or directed. Signage shall be in accordance with Section 10 14 00.10 EXTERIOR SIGNAGE. Signage shall be placed inside the entrances to crawl spaces and shall identify the space as treated with termiticide and not safe for children and animals. Treated areas should be covered with plastic if slab is not to be poured immediately following termiticide application.



### 3.6 CONDITIONS FOR SATISFACTORY TREATMENT

#### 3.6.1 Equipment Calibrations and Measurements

Where results from the equipment calibration and tank measurements tests are unsatisfactory, re-treatment will be required.

#### 3.6.2 Testing

Should an analysis, performed by a third party, indicate that the samples of the applied termiticide contain less than the amount of active ingredient specified on the label, or if soils are treated to a depth less than specified or approved, re-treat.

#### 3.6.3 Disturbance of Treated Soils

Retreat soil and fill material disturbed after treatment before placement of slabs or other covering structures.

#### 3.6.4 Termites Found Within the Warranty Period

If live subterranean termite infestation or termite damage is discovered during the warranty period, re-treat the site.

### 3.7 RE-TREATMENT

Where re-treatment is required, comply with the requirements specified in paragraph WARRANTY.

-- End of Section --