GENERAL NOTES:

A. ALL AREAS ARE LIGHT HAZARD UNLESS OTHERWISE NOTED ON THIS PAGE.
B. ALL DRYWALL CEILINGS (HARD CEILING) AT 8'-0".
C. ALL ACOUSTICAL TILE CEILINGS AT 8'-6".
D. ALL SPRINKLER LOCATIONS FIELD VERIFIED.
E. ALL PIPING LOCATIONS AND SIZES ARE ESTIMATED FROM FIELD SURVEY. PRIOR TO START OF SHOP DRAWINGS, A DETAILED FIELD SURVEY SHALL BE PERFORMED TO DETERMINE ACCURATE LOCATION AND PIPE SIZES AND PROVIDE ACCURATE AS BUILT DRAWING SET.

KEYED NOTES:

1. DEFICIENCY NUMBER 28 IN FIELD REPORT.



1 FP-202 2ND FLOOR EXISTING FIRE SUPPRESSION PLAN
SCALE: 1/8" = 1'-0"

ISSUED FOR CONSTRUCTION
FULLY SPRINKLERED

Revisions		Date
0	CONSTRUCTION DRAWINGS	06 MAY 11

ENGINEERS:

APOGEE Consulting Group, PA
7330 Chapel Hill Road
Suite 202
Raleigh, N.C. 27607
(919) 858-7420 Fax (919) 858-7423
Apogee Project # 2010 242
Alabama COA# CA-2180-E

STANTON ENGINEERING SERVICES, LLC
FIRE PROTECTION ENGINEERS
10280 OLD COLUMBIA RD., STE. 275
COLUMBIA, MD 21046
ph 410-290-9301 fax 410-290-9305

Professional Stamp/Seal
STATE OF MARYLAND STEPHEN HAND 33598 PROFESSIONAL ENGINEER
05/06/2011

ARCHITECT/CONSULTANT:

Drawing Title: 2ND FLOOR EXISTING FIRE SUPPRESSION PLAN

Approved: Mariano Roman, CO
Approved:
Approved: Priscilla Humphrey-Parker, COTR
Approved:

Project Title: FIRE ALARM & SPRINKLER HEAD REPLACEMENT

Building No.: ---
Scale: AS SHOWN
Drawn/Checked: KST
Location: DEPT. OF VETERANS AFFAIRS REGIONAL OFFICE, 345 PERRY HILL ROAD, MONTGOMERY, AL 36109

Date: 05/06/11
Project No.: VA322-P-0006
DRAWING NO.: FP-202
Dwg. 14 of 19

Office of Facilities Management
Department of Veterans Affairs

*U.S. GOVERNMENT PRINTING OFFICE: 1983-400-285

VA FORM 08-6231, FEB. 1983