GENERAL NOTES:

A. ALL AREAS ARE LIGHT HAZARD UNLESS OTHERWISE NOTED ON THIS PAGE.
B. ALL DRYWALL CEILINGS (HARD CEILING) AT 8'-0".
C. ALL ACOUSTICAL TILE CEILINGS AT 8'-6".
D. ALL SPRINKLER LOCATIONS FIELD VERIFIED.
E. ALL PIPING LOCATIONS AND SIZES ARE ESTIMATED FROM FIELD SURVEY. PRIOR TO START OF SHOP DRAWINGS, A DETAILED FIELD SURVEY SHALL BE PERFORMED TO DETERMINE ACCURATE LOCATION AND PIPE SIZES AND PROVIDE ACCURATE AS BUILT DRAWING SET.
F. NO MATERIALS OF ANY KIND ARE TO BE HUNG OFF OF SPRINKLER LINES.



1 FP-202N 2ND FLOOR NEW FIRE SUPPRESSION PLAN
SCALE: 1/8" = 1'-0"

ISSUED FOR CONSTRUCTION
FULLY SPRINKLERED

Revisions		Date
0	CONSTRUCTION DRAWINGS	06 MAY 11

ENGINEERS:

APOGEE Consulting Group, PA
7330 Chapel Hill Road
Suite 202
Raleigh, N.C. 27607
(919) 858-7420 Fax (919) 858-7423
Apogee Project # 2010 242
Alabama COA# CA-2180-E

STANTON ENGINEERING SERVICES, LLC
FIRE PROTECTION ENGINEERS
10280 OLD COLUMBIA RD., STE. 275
COLUMBIA, MD 21046
ph 410-290-9301 fax 410-290-9305

Professional Stamp/Seal
STATE OF MARYLAND STEPHEN HAMILTON BOYD 33598 PROFESSIONAL ENGINEER
05/06/2011

ARCHITECT/CONSULTANT:

Drawing Title: 2ND FLOOR NEW FIRE SUPPRESSION PLAN

Project Title: FIRE ALARM & SPRINKLER HEAD REPLACEMENT

Date: 05/06/11

Project No. VA322-P-0006

Approved: Mariano Roman, CO
Approved:
Approved: Priscilla Humphrey-Parker, COTR
Approved:

Building No. ---
Scale: AS SHOWN
Drawn/Checked: KST

Location: DEPT. OF VETERANS AFFAIRS REGIONAL OFFICE, 345 PERRY HILL ROAD, MONTGOMERY, AL 36109

DRAWING NO. FP-202N
Dwg. 15 of 19

Office of Facilities Management
Department of Veterans Affairs

*U.S. GOVERNMENT PRINTING OFFICE: 1983-400-285

VA FORM 08-6231, FEB. 1983