

- ①. ABATE EXISTING ASBESTOS CONTAINING FLOORING AND MASTIC IN ACCORDANCE WITH SPECIFICATION SECTION 02 82 13.19. REMOVE EXISTING BASE.
- ②. INSTALL NEW TILE FLOORING AND BASE IN THIS AREA.
- ③. INSTALL NEW NON-SKID TILE ON RAMPS, ARMSTRONG 12" X 12" SAFETY ZONE OR EQUAL. COLOR TBD.
REPLACE EXISTING 6" BASE ON RAMPS WITH NEW 6" BASE.

