KEYED NOTES:

1. — DISCONNECT AND REMOVE ALL EXISTING LIGHTING FIXTURES THIS AREA. HOLD EXISTING BRANCH CIRCUITRY FOR RECONNECTION. RECONNECT NEW FIXTURES TO EXISTING BRANCH CIRCUITS UPON COMPLETION OF NEW CEILING GRID. MODIFY OR EXTEND EXISTING CIRCUITRY AS REQUIRED.
2. — RECONNECT NEW LIGHTING FIXTURE TO EXISTING EMERGENCY POWER BRANCH CIRCUIT. MODIFY OR EXTEND EXISTING CIRCUITRY AS REQUIRED.
3. — DISCONNECT EXISTING EXIT SIGN AND HOLD FOR REINSTALLATION. RECONNECT EXISTING EXIT SIGN UPON COMPLETION OF NEW CEILING GRID.

LIGHTING FIXTURE SCHEDULE

SYMBOL	DESCRIPTION	MANUFACTURER & CATALOG NUMBER	LAMPS	MOUNTING	REMARKS
L2	2' X 4' FLUORESCENT TROFFER WITH K15 ACRYLIC LENS, SPRING LOADED LATCHES, GRID TRIM, ALUMINUM DOOR, STATIC AND 120 VOLT ELECTRONIC BALLAST.	COLUMBIA 4PS24-232G-FA-A15-EB8(1/2)120-SLL-PAF DAY-BRITE 2DPG232-FA15-120-1/2 EB LITHONIA 2SPG 232 FW A15 120 1/2 GEB SLL LGNG PAF METALUX 2GCFA-232A15-120-EB81(1/2)-G1	2-32W T-8	RECESSED IN CEILING	
L3	2' X 4' FLUORESCENT TROFFER WITH K15 ACRYLIC LENS, SPRING LOADED LATCHES, GRID TRIM, ALUMINUM DOOR, STATIC AND 120 VOLT ELECTRONIC BALLAST.	COLUMBIA 4PS24-332G-FA-A15-EB8(1/2)120-SLL-PAF DAY-BRITE 2DPG332-FA15-120-1/2 EB LITHONIA 2SPG 332 FW A15 120 1/2 GEB SLL LGNG PAF METALUX 2GCFA-332A15-120-EB81(1/2)-G1	3-32W T-8	RECESSED IN CEILING	



BUILDING 90, FIRST FLOOR LIGHTING PLAN

SCALE: 3/32" (0.24CM) = 1'-0" (30.5CM)

Revisions	Date

MCE MILLS-CONOLY ENGINEERING, P.C.
8218 Old Federal Road
TELEPHONE: (334) 270-0010
Montgomery, AL 36117
FAX: (334) 270-0040

CAVHCS
Central Alabama Veterans Health Care System

Approved:	Approved:
Approved:	Approved:
Approved:	Approved:
Approved:	Approved:

Drawing Title: BUILDING 90, FIRST FLOOR LIGHTING PLAN, FIXTURE SCHEDULE AND NOTES

Safety Officer:

Clinical Representative:

Project Title: HVAC MODIFICATIONS TO BUILDINGS 83, 90, & 93 TUSKEGEE, ALABAMA

Building Number: 93 | Checked: CCM | Drawn: ACM

Location: East Campus, Tuskegee, AL

Date: 12/21/10

Project No.: 619-10-445

DRAWING NO.: 90E2.2

Dwg. 58 of 59

Veterans Administration

VA FORM 08-6231A, MAR 1984