


MEMBRANE/CRAWLSPACE DETAIL
NO SCALE

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND CONDITIONS PRIOR TO BEGINNING ANY OTHER WORK.
2. ANY ITEM NOT NOTED AS EXISTING IS NEW AND SHALL BE PROVIDED AND INSTALLED UNDER THE TERMS OF THIS CONTRACT.
3. REMOVE AND DISPOSE OF TWO INCHES DEPTH OF ASBESTOS CONTAMINATED SOIL FROM THE ENTIRE TOP SURFACE OF THE DESIGNATED CRAWLSPACE AREA. REMOVE AND DISPOSE OF ALL LOOSE STONES, MASONRY, PLASTIC SHEETING, DEBRIS AND LOOSE ASBESTOS. RAKE SMOOTH THE EXISTING TOP SURFACE OF THE SOIL WITHOUT SIGNIFICANT REGRADING OF THE EXISTING SOIL.
4. PROVIDE AND INSTALL A NEW EPDM ISOLATION MEMBRANE WITH CONTINUOUSLY WELDED SEAMS OVER THE ENTIRE DESIGNATED CRAWLSPACE TOP SURFACE AND PERIMETER WALL.
5. REMOVE AND DISPOSE OF ALL INSULATION ON EXISTING PIPE BUT DO NOT REINSULATE.



Revisions	Date	Professional Seal	Drawing Title	Project Title			Date
			BASEMENT/CRAWLSPACE FLOOR PLAN			Project No.	
			Approved: Project Manager	Drawing No.	Checked	Drawn GT	Building Number
			Approved: Service Chief	Location VAMC, NORTHAMPTON MASS.		6	