SECTION 09 06 00
SCHEDULE FOR FINISHES

SECTION 09 06 00-SCHEDULE FOR FINISHES

VAMC: Long Beach Healthcare System

Location: 5901 E Seventh Street, Long Beach, CA 90822

Project no. and Name: Project No. 600-15-102, Morgue Renovation for Family Access

Submission: Final Construction Documents

Date: April 29th, 2016

SECTION 09 06 00
SCHEDULE FOR FINISHES

PART I – GENERAL

1.1 DESCRIPTION

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

1.2 MANUFACTURERS

Manufacturer’s trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer’s equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

1.3 SUBMITALS

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

1.4 APPLICABLE PUBLICATIONS

A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.

B. MASTER PAINTING INSTITUTE: (MPI)

2001.....Architectural Painting Specification Manual

PART 2- PRODUCTS

2.1 DIGITAL COLOR PHOTOS

A. Size 24 x 35 mm.

B. Labeled for:

1. Building name and Number.
2. Room Name and Number.

B. SECTION 06 20 00, FINISH CARPENTRY

1. OFFICE COUNTER

Room No. and Name	Component	Material	Manufacturer	Color
OFFICE #041	Task Surface	Solid Surface	Corian	Linen
	Cabinets	Plastic Laminate	Wilsonart	Monticello Maple (7925-38)

R. SECTION 07 92 00, JOINT SEALANTS

Location	Color	Manufacturer	Manufacturer Color

Interior		GE SilPruf SCS 2000 or Approved Equal	
Interior		GE SilPruf SCS 1700 or Approved Equal	
Interior		GE RCS 20 or Approved Equal	

2.8 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door	
Component	Color of Paint Type and Gloss
Door	Steel Painted Semi-Gloss Finish
Frame	Steel Painted Semi-Gloss Finish
Window frame	Steel Painted Semi-Gloss Finish

C. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	Painted Semi-Gloss Finish
Stainless steel	Stainless Steel (BA) Finish

R. SECTION 08 56 19, PASS WINDOWS

Room No. and Name	Finish	Glazing	Manufacturer	Mfg. Color Name/No.
Office	Aluminum (Satin Anodized)	Clear Tempered	C.R. Laurence Co., Inc. or Approved Equal	TBD

U. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges	Stainless Steel	630
Door Closers	Stainless Steel	630
Floor Closers	Stainless Steel	630
Closer/ Holder	Stainless Steel	630
Floor Stops	Stainless Steel	630
Door Holders	Stainless Steel	630
Lock/ Latches	Stainless Steel	630
Key Cabinet	Steel	
Armor Plates	Stainless Steel	630
Kick Mop Plates	Stainless Steel	630
Door Edging	Stainless Steel	630
Exit Device	Stainless Steel	630
Flush Bolts	Stainless Steel	630
Door Pulls	Stainless Steel	630
Push Plates	Stainless Steel	630
Combination Push Pull Plate	Stainless Steel	630
Coordinators	Stainless Steel	630

Light Proof Seals	Stainless Steel	630
Weather Strip	Stainless Steel	630
Threshold	Stainless Steel	630

V. SECTION 08 80 00, GLAZING

Glazing Type	Manufacturer	Mfg. Color Name/No.
G-1		Tempered Glass Clear

2.9 DIVISION 09 - FINISHES

B. SECTION 09 30 13, CERAMIC TILING

2. SECTION 09 30 13, CERAMIC TILING

Finish code	Manufacturer	Mfg. Color Name/No
CT-1	DALTILE NATURAL HUES	PEARL WHITE
PT-1	CROSSVILLE RETROACTIVE	C370 FEATHERSONTE (POLISHED)
PT-2	CROSSVILLE RETROACTIVE	A215 EMPRESS WHITE (POLISHED)

9. SECTION 09 30 13, MARBLE THRESHOLDS

Marble Type	Manufacturer	Mfg. Color Name/No.
Natural Stone	Daltile or Approved Equal	TBD

F. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
AT-1	Exposed Suspension System (2’x2’)	HealthZone Ultima 9/16” Beveled Tegular Model #1936 (White)	Armstrong or Approved Equal	Prelude 9/16” Suprafine Tee Grid

K. SECTION 09 65 16, VINYL SHEET FLOORING(RSF)

Finish Code	Pattern name	Manufacturer	Mfg. Color Name/No.
RSF	Rejuvenations (SHEET)	Armstrong or Approved Equal	TimberLine Oak 37355

Q. SECTION 09 67 23, EPOXY RESINOUS FLOORING (ERF)

Finish code	Manufacturer	Mfg. Color Name/No.
RES-3	Tnemec or Approved Equal	222-Q212 Deci-Tread/284-0000 Deco-Clear
RES-6B	Tnemec or Approved Equal	222-Q212 Deci-Tread/284-0000 Deco-Clear

R. SECTION 09 96 59, HIGH-BUILD GLAZED COATING (SC)

Finish code	Manufacturer	Mfg. Color Name/No.
SC	Dunn Edwards	Monochem 200 / WHITE

T. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-“a velvet-like” finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional “egg-shell like” finish	10-25 units, and	10-35 units

Gloss Level 4	a “satin-like” finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
P1, P2	See D1/AF-602 Room Finish Schedule	Dunn Edwards	Color TBD

2.10 DIVISION 10 - SPECIALTIES

F. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

Item	Material	Manufacturer	Mfg. Color Name/No.
Corner Guards	Stainless Steel		630
Wall Guards and Handrail	See Drawings		
Wall Guard	Stainless Steel		630
Door Frame Protection	Stainless Steel		630

J. SECTION 10 13 00 / 10 14 00, INTERIOR SIGNS

Sign Type	Component	Manufacturer	Mfg. Color Name/No.
See Drawings			

P. SECTION 10 28 00, TOILET AND BATH ACCESSORIES

Item	Material	Manufacturer	Mfg. Color Name/No.
See Drawings			

C. SECTION 12 36 00, COUNTERTOPS AND ACCESSORIES

Type	Finish/Color
Plastic Laminate	Wilsonart / Monticello Maple (7925-38)
Solid Surface	Corian / Linen

PART III EXECUTION

3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS	
Term	Abbreviation
Access Flooring	AF
Accordion Folding Partition	AFP
Acoustical Ceiling	AT
Acoustical Ceiling, Special Faced	AT (SP)
Acoustical Metal Pan Ceiling	AMP
Acoustical Wall Panel	AWP
Acoustical Wall Treatment	AWT
Acoustical Wallcovering	AWF
Anodized Aluminum Colored	AAC
Anodized Aluminum	AA

Natural Finish	
Baked On Enamel	BE
Brick Face	BR
Brick Flooring	BF
Brick Paving	BP
Carpet	CP
Carpet Athletic Flooring	CAF
Carpet Module Tile	CPT
Ceramic Glazed Facing Brick	CGFB
Ceramic Mosaic Tile	FTCT
Concrete	C
Concrete Masonry Unit	CMU
Divider Strips Marble	DS MB
Epoxy Coating	EC
Epoxy Resin Flooring	ERF
Existing	E
Exposed Divider Strips	EXP
Exterior	EXT
Exterior Finish System	EFS

Exterior Paint	EXT-P
Exterior Stain	EXT-ST
Fabric Wallcovering	WF
Facing Tile	SCT
Feature Strips	FS
Floor Mats & Frames	FM
Floor Tile, Mosaic	FT
Fluorocarbon	FC
Folding Panel Partition	FP
Foot Grille	FG
Glass Masonry Unit	GUMU
Glazed Face CMU	GCMU
Glazed Structural Facing Tile	SFTU
Granite	GT
Gypsum Wallboard	GWB
High Glazed Coating	SC
Latex Mastic Flooring	LM
Linear Metal Ceiling	LMC
Linear Wood Ceiling	LWC
Marble	MB
Material	MAT
Mortar	M
Multi-Color Coating	MC
Natural Finish	NF
Paint	P
Paver Tile	PVT
Perforated Metal Facing (Tile or Panels)	PMF
Plaster	PL
Plaster High Strength	HSPL
Plaster Keene Cement	KC
Plastic Laminate	HPDL
Polypropylene Fabric Wallcovering	PFW

Porcelain Paver Tile	PPT
Quarry Tile	QT
Radiant Ceiling Panel System	RCP
Resilient Stair Tread	RST
Rubber Base	RB
Rubber Tile Flooring	RT
Spandrel Glass	SLG
Stain	ST
Stone Flooring	SF
Structural Clay	SC
Suspension Decorative Grids Grids	SDG
Terrazzo Portland Cement	PCT
Terrazzo Tile	TT
Terrazzo, Thin Set	
Textured Gypsum Ceiling Panel	TGC
Textured Metal Ceiling Panel	TMC
Thin set Terrazzo	TST
Veneer Plaster	VP
Vinyl Base	VB
Vinyl Coated Fabric Wallcovering	W
Vinyl Composition Tile	VCT
Vinyl Sheet Flooring	VSF
Vinyl Sheet Flooring (Welded Seams)	WSF
Wall Border	WB
Wood	WD

3.2 FINSIH SCHEDULE SYMBOLS

Symbol	Definition
**	Same finish as adjoining walls
-	No color required
E	Existing
XX	To match existing
EFTR	Existing finish to remain
RM	Remove

3.3 ROOM FINISH SCHEDULE

A. Match adjoining or existing similar surfaces colors, textures or patterns where disturbed or damaged by alterations or new work when not scheduled.

B. ROOM FINISH SCHEDULE

See drawing AE-602

--- E N D---