

LEGEND

--- AREA OF WORK



GENERAL KEY PLAN NOTES

- 1 INFECTION CONTROL:
ALL TEMPORARY CONSTRUCTION PARTITIONS TO BE IN PLACE PRIOR TO START OF DEMOLITION. ALL TEMPORARY CONSTRUCTION BARRIERS TO BE CONSTRUCTED AS PER GENERAL REQUIREMENTS 01 00 00 IN THE SPECIFICATIONS.
CAP RETURN AIR DUCTS AND MODIFY HVAC TO MAINTAIN NEGATIVE AIR PRESSURE.
CONTRACTOR TO SUPPLY HEPA FILTER FANS AS NECESSARY TO MAINTAIN CLEAN AIR CONDITIONS WITHIN DEMOLITION AREAS.
CONSTRUCTION ENTRY TO HAVE STICKY MATS ON INSIDE ONLY. CONTRACTOR TO SUPPLY CARPET SQUARE WITH SPRAY STATION.
- 2 ALL WORK MUST OCCUR AFTER NORMAL WORKING HOURS: 8:00 PM - 6:00 AM OR ON WEEKENDS.

1. NEW FLOOR KEY PLAN

SCALE: 1/8" = 1'-0"

SCALE: AS NOTED

		 ANDERSON ARCHITECTS DABROWSKI 1430 SE 3RD AVE SUITE 200 PORTLAND, OR 97214 Tel 503.239.7377 Fax 503.239.7372	 VETERANS AFFAIRS MEDICAL CENTER PORTLAND, OREGON	Drawing Title FLOOR KEY PLAN - 1/8"				Project Title VA Medical Center Portland, Oregon Bldg. 100 Third Floor - Hybrid OR		Date 04.11.16	US DEPARTMENT OF VETERANS AFFAIRS
Revisions				Approved: Infection Ctrl. Approved: Service Chief		Approved: Safety Mgr. Approved: Chief PM5		Approved: Chief P&O Approved: Director, VAMC		Building No. 100C Checked/Project Mgr. JMA / APB Drawing No. A3.0 Location PORTLAND, OREGON Rev. 4 of 37	