

DOOR SCHEDULE

Project Title: 111 Upgrade Pool Locker Rooms

Project No. 695-14-114

DOOR NO.	ROOM NO.	ROOM NAME	DOOR					FRAME		Hdwre Group	Ass'y Rating	NOTES
			Size (W x H)	Type	Mat'l	Finish	Glass	Mat'l	Finish			
B0526A	B0526	MENS LOCKER ROOM	3'-6" x 7'-0"	A	MTL	PA-2	--	HM1	PA-2	1	45 MIN	6
B0526B	B0526	MENS LOCKER ROOM	3'-6" x 7'-0"	A	MTL	PA-2	--	HM1	PA-2	4	45 MIN	5
B0515A	B0515	WOMENS LOCKER ROOM	3'-0" x 7'-0"	A	MTL	PA-2	--	HM1	PA-2	1	45 MIN	6
B0515B	B0515	WOMENS LOCKER ROOM	3'-6" x 7'-0"	A	MTL	PA-2	--	HM1	PA-2	4	45 MIN	5
B0520	B0520	POOL	MEASURE EXISTING	A	MTL	PA-2	--	HM1	PA-2	2	45 MIN	-
IFC/CB-1	IFC/CB-1	TEMPORARY IFC/CB DOOR	3'-0" x 7'-0"	A	MTL	--	--	HM1	--		45 MIN	1,2,3
IFC/CB-2	IFC/CB-2	TEMPORARY IFC/CB DOOR	3'-0" x 7'-0"	A	MTL	--	--	HM1	--		45 MIN	1,2,3

NOTES: ALL DOORS TO BE ROTARY CUT BIRCH WITH CLEAR STAIN TO MATCH EXISTING UNLESS NOTED OTHERWISE
ALL HARDWARE PREP DONE PRIOR TO PREFINISHING

- 1 ACROVYN 45 MIN RATED RED DOOR.
- 2 DOOR TO BE REUSED FOR EACH PHASE
- 3 PROVIDE TEMPORARY CARD READER FOR IFC-CB DOOR.
- 4 EXISITING HARDWARE TO REMAIN, CONTRACTOR TO PAINT DOOR AND FRAME ON BOTH SIDES
- 5 CONTRACTOR TO PROVIDE AND MOUNT A PERMANENT 12"x18" PHOTOILLUMINICIENT "POOL - NOT AN EXIT" SIGNAGE ON THE LOCKER ROOM SIDE OF THE DOOR

6 PROVIDE 14" x 12" DOOR TRANSFER GRILL

Revised Door Schedule