

Vendor Print Name:

Signature \_\_\_\_\_ DATE: \_\_\_\_\_

ITEM NO	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	Total Price
0001	Bobcat Brand 55" Utility Grapple-GP (#7176783) with Grapple Stop Kit (#7120201)	1	EACH		
0002	Bobcat SG-60 Stump Grinder (90 Degree Angle Mount) (#6808034)	1	EACH		
<b>TOTAL:</b>					

Please fill out the right column in the matrix below for **BRAND NAME OR EQUAL** and return a signed copy as part of the submission. The Vendor shall comment on each specification as instructed in the Buy Terms, Technical Evaluation of Quotes.

<u>Specifications</u>	<u>Vendor's Submission</u>
<b>Vendor shall replace at own cost if item does not operate to Government's standards.</b>	
<b>Annotate your best delivery date to the right for both Line Items (0001 &amp; 0002) Delivery shall be within 30 calendar days after award.</b>	
<b>Line Item 0001</b>	
55" Grapple must be low profile, compact design for easy access in tight areas. Grapple must pair to a bobcat toolcat front mounted loader general purpose bucket.	
Must not weight more than 185lbs, must have at least 4 standard teeth, length of 33", Grapple must have over all height of 30" at closed position & 42" high at open position	
Must have a grapple stop kit for mounting utility grapple to the Bobcat standard general purpose bucket.	

<b>Line Item 0002</b>	
90 degree angle mount stump grinder must be able to mount to the front carrier loader of a year 2015 Bobcat brand Toolcat 5600 Utility Work Machine for easy maneuverability in tight areas and easy positioning over stumps. Hydraulics must operate off the carrier's auxiliary hydraulics; have a unique valve design eliminating cutting wheel stalling while in the cut.	
Must not weight more than 1000lbs or less than 950lbs.	
Overall length shall not exceed 45 inches, 66 inches in width and 60 inches in height for easy access to tight areas.	
Wheel diameter shall be 27" with 32 carbide tipped teeth, have a grinder reach at ground level of 74", maximum cutting arc of 80 degrees, maximum cutting depth of 15", maximum cutting height of 32". Easy transport width not to exceed 48". Tip speed range of 4480-6330ft./min (1366-1990m./min). Must have rubber deflecting shields to protect operators from wood chips	