



Not to Scale

8' 5" Ceiling

Hospital: VA Medical Center
 City, State: Erie, PA

Date:

Ventilation System Evaluation **Comments and Recommendations**

1. All the rooms within the Sterile Processing Department have the proper directional flow of air and have excellent fresh air exchanges.

<u>Fresh Air Exchanges:</u>	<u>Actual</u>	<u>Minimum</u>		
<u>Room</u>	<u>Air Exchange</u>	<u>Air Exchange</u>	<u>Room Pressure</u>	<u>Pass/Fail</u>
Decontamination	30.9	6	Negative	Pass
Prep Room	20.4	4	Positive	Pass
ETO Sterilizer Room	18.6	10	Negative	Pass
ETO Maintenance Room	48.9	10	Negative	Pass
Steam Maintenance Room	97.3	10	Negative	Pass
Clean Pack & Prep	21.3	4	Positive	Pass
CS Lobby	24.9	4	Positive	Pass
Break Room	10.5	4	Positive	Pass
Office	11.8	4	Positive	Pass
Bio Med Office	7.4	4	Positive	Pass
Bio Med	8.4	4	Positive	Pass
Sterile Storage	18.8	4	Positive	Pass
Storage	8.5	2	Positive	Pass

2. The arrow at each entrance way shows the direction of the flow of air between rooms.
3. See back of page for drawing.

Report Received by: _____

Signature: _____

Signature: _____