

three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot

ITEM NO.	ROOM NAME	EXISTING LOCATION	NEW ROOM #	JSN#	DESCRIPTION	MANUFACTURER	MODEL	NEW/ EXSTNG	FURNISH INSTALL	MOUNTING	WEIGHT	WIDTH	DEPTH	HEIGHT	VOLTS	AMP	WATER	DRAIN	VENT	DATA	NEMA	REMARKS
1	AUTOPSY	WAREHOUSE BLDG 47	43	L9711	TWO AUTOPSY TABLES	THERMO SCIENTIFIC	LM 10 PART # 10175	N	OF/CI	F	870 lbs	88.5"	29.5"	37"			Y	Y	N	N		
2	AUTOPSY				TWO SIDE TABLES			E	OF/CI	F							N	N	N	N		
3	AUTOPSY		43		DISPLAY TABLE	MOPEC	HA-200	N	CF/CI	F							N	N	N	N		
4	AUTOPSY	2ND FLOOR LAB	43		PATHOLOGY GROSSING STATION	SHANDON	GROSS LAB SENIOR	E	OF/CI	F							Y	Y	Y			RECERTIFY AFTER INSTALLATION
5	AUTOPSY	RAMP	43		BLEACHERS			E	OF/CI	F	VIF						N	N	N	N		
6	AUTOPSY		43		WHITE BOARD			N	CF/CI	F							N	N	N	N		
7	AUTOPSY		43		NON-STERILE WORKBENCH	MORTECH OR MOPEC		N	CF/CI	F		48in	36in	32in			N	N	N	N		SS STEEL ADJUSTABLE HEIGHT
8	AUTOPSY	43	43		FORMALIN DISPENSER			E	OF/OI	F							N	N	N	N		
9	AUTOPSY	45	43		CRYOSTAT	LEICA	CM1900	E	OF/CI	F							N	Y	N	N		RECERTIFY AFTER INSTALLATION
10	AUTOPSY		43		SURGICAL LIGHTS (2)	MORTECH	SLALED	N	CF/CI	C					120V		N	N	N	N		DOUBLE HEAD LIGHT CEILING MOUNT
11	AUTOPSY	43	43		CAMERA STAND	PHOTODYNE		E	OF/OI	F							N	N	N	N		
12	AUTOPSY	43	43		COMPUTER CART			E	OF/OI	F							N	N	-	Y		
13	AUTOPSY		43		BODY LIFT STATION	GULDMANN	GH 3 SWL 550 lbs	N	CF/CI	C	38 lbs					115/230V AC	N	N	N	N		BATTERY WITH SUPPLY TRANSFORMER
14	CORRIDOR		CC2-BM1		BODY LIFT STATION	GULDMANN	GH 3 SWL 550 lbs	N	CF/CI	C	38 lbs					115/230 V AC	N	N	N	N		BATTERY WITH SUPPLY TRANSFORMER
15	AUTOPSY		43/45		SINK			N	CF/CI	W							Y	Y	Y	N		
16	AUTOPSY		43		NON-DIGITAL WEIGHING SCALES(2)	MOPEC	BB002,BB037	N	CF/CI	C							N	N	N	N		AUTOPSY SCALE, PAN BOW AND RING ASSEMBLY
17	AUTOPSY		43		NEGATIVE PRESSURE MONITORING	AIR FLOW DIRECTION INC.	ADI-69-V-N	N	CF/CI	W					N	N	N	N	N	N		BALL IN WALL INDICATOR
18	AUTOPSY		43		EYE WASH	GUARDIAN	GBF 1994	N	CF/CI	F							Y	N	N	N		
19	AUTOPSY		43		SINK STATION	MOPEC	CE 800 with BL 800	N	CF/CI	W		40 in	39 in	29 in			Y	Y	Y	N		WITH WASTE DISPOSAL UNIT
20	AUTOPSY		43/45		BASE CABINET	MOPEC	C-SERIES	N	CF/CI	F		SEE ELEV.	30in	37in			N	N	N	N		
21	AUTOPSY		43/45		WALL CABINET	MOPEC	C-SERIES	N	CF/CI	W		48in/36in	12in	36in			N	N	N	N		SS STEEL AND GLASS
22	AUTOPSY		43		TALL CABINET	MORTECH	SC 347-48	N	CF/CI	F		48in	24in	84in			N	N	N	N		SS STEEL AND GLASS SWING DOORS
23	ISOLATION AUTOPSY ROOM	45	45		ONE AUTOPSY TABLE			E	OF/CI	F							Y	Y	Y	N		
24	ISOLATION AUTOPSY ROOM		45		STAINLESS STEEL GLASS STORAGE CABINET (48" WIDE)			E	OF/CI	F							N	N	N	N		
25	CORRIDOR		CC2-BM1		EYE WASH	GUARDIAN	GBF 1994	N	CF/CI	F							Y	N	N	N		
26	CORRIDOR	CC2-BM1	46A		AUTOPSY TRANSPORT TABLE & CARTS			E	OF/OI	F							N	N	N	N		
27	REFRIGERATOR ROOM		42		NINE BODY REFRIGERATOR	MORTECH	1036-R112	N	CF/CI	F	3800 lbs	108 in	97 in	109.5 in	208-230V	50-60 Hz						INNER ROLLER TRAYS
28	REFRIGERATOR ROOM		42		SIX BODY REFRIGERATOR	MORTECH	1036-R109	N	CF/CI	F	2700 lbs	73 in	97 in	109.5 in	208 - 230V	50-60 Hz						INNER ROLLER TRAYS
29	REFRIGERATOR ROOM		42		THREE BODY REFRIGERATOR	MORTECH	1039-R105	N	CF/CI	F	1500 lbs	96.5 in	40 in	110.5 in	2080-- 230 V	50-60 Hz	N	N	N	Y		INNER ROLLER TRAYS
30	SPECIMEN STORAGE		46		SHELVES WITH SLOPED TOP	MORTECH	SC338-36	N	CF/CI	F		36in	18in	84in			N	N	N	N		OPEN FRONT SIX ADJUSTABLE SHELVES
31	MORGUE FILE STORAGE		58		SHELVES WITH SLOPED TOP	MORTECH	SC 338-36	N	CF/CI	F		36in	18in	84in			N	N	N	N		OPEN FRONT SIX ADJUSTABLE SHELVES
32	AUTOPSY		43		EXTRACTION ARM	NEDERMAN	FX -100	N	CF/CI	C												CEILING MOUNTED WITH MUTIPURPOSE HOOD
33	REFRIGERATOR ROOM		42		TEMPERATURE ALARM LED/LAG CONTROLLER	MORTECH	MODEL 75	N	CF/CI	W												
34	STORAGE		35		STAINLESS STEEL GLASS STORAGE CABINET 16" DEEP	MORTECH	SC 358-48	N	CF/CI	F		24in	48in	84in								HINGED DOORS
35	ISOLATION AUTOPSY ROOM		45		STAINLESS STEEL GLASS STORAGE CABINET (30" WIDE)			E	OF/CI	F							N	N	N	N		SS STEEL AND GLASS
36	HALLWAY		37B		TALL CABINET	MOPEC	LD-345-48	N	CF/CI	F							N	N	N	N		SS STEEL AND GLASS
37	HALLWAY		37B		TALL CABINET	MOPEC	LD-345-30	N	CF/CI	F							N	N	N	N		SS STEEL AND GLASS
38	HAC		38		WALL CABINET	MOPEC	LB234-18	N	CF/CI	W		18in	12in	36in			N	N	N	N		SS STEEL AND GLASS
39	HAC		38		WALL CABINET	MOPEC	LB235-36	N	CF/CI	W		18in	12in	36in			N	N	N	N		SS STEEL AND GLASS
40	AUTOPSY		43		INTEGRAL SINK	MOPEC	C-SERIES	N	CF/CI	CO		24in	17in	7in			Y	Y	Y	N		INTEGRAL SINK IN SS STEEL COUNTER TOP W/ FOOT CONTROL AND WASTE DISPOSAL UNIT

LEGEND
NEW/EXISTING
N - NEW
E - EXISTING
FURNISH INSTALL
OF/OI - OWNER FURNISH/OWNER INSTALL
OF/CI - OWNER FURNISH/CONTRACTOR INSTALL
OF/VI - CONTRACTOR FURNISH/VENDOR INSTALL
CF/CI - CONTRACTOR/CONTRACTOR INSTALL

MOUNTING
F - FLOOR
CO - COUNTER
C - CEILING
W - WALL

D1 EQUIPMENT SCHEDULE
NOT TO SCALE

EQUIPMENT GENERAL NOTES:

- BEFORE COMMENCEMENT OF EACH PHASE, THE GENERAL CONTRACTOR SHALL COORDINATE WITH THE VA REPRESENTATIVE, ACTIVITIES RELATED TO EXISTING EQUIPMENT RELOCATION.
- BEFORE RELOCATION OF EQUIPMENT CONTRACTOR TO RECORD EXISTING CONDITIONS BY PHOTOGRAPHS AND TAG THE EQUIPMENT IN COORDINATION WITH VA REPRESENTATIVE. STORE EQUIPMENT AT LOCATION PROVIDED BY VA COR.
- ALL EQUIPMENT SHALL BE MOVED BY THE CONTRACTOR. HIRE A SPECIALIZED VENDOR TO DISCONNECT, RELOCATE AND REINSTALL EXISTING EQUIPMENT AS REQUIRED BY CONTRACT DOCUMENTS. CONTRACTOR TO OBTAIN RE-CERTIFICATION OF EQUIPMENT FROM SPECIALIZED VENDOR. SUBMIT QUALIFICATIONS OF THE MOVER TO VA FOR APPROVAL.
- SEE EQUIPMENT SCHEDULE SHEET AE-105 FOR EXISTING EQUIPMENT NUMBER TAG AND EXISTING ROOM NUMBER FROM WHICH THE EQUIPMENT NEEDS TO BE RELOCATED.
- PROVIDE ALL UTILITIES, MECHANICAL, PLUMBING, ELECTRICAL, DATA CONNECTIONS AS REQUIRED FOR THE EQUIPMENT.
- VERIFY SIZE AND LOCATION OF FINAL EQUIPMENT PRIOR TO INSTALLATION OF CASEWORK INSTALLATION.
- DETERMINE THE EQUIPMENT ANCHORAGE REQUIREMENTS BASED ON EQUIPMENT SELECTION.
- EQUIPMENT LOCATION, CLEARANCE, MOUNTING AND ANCHORAGE REQUIREMENTS OF ALL EQUIPMENT PRIOR TO FINAL INSTALLATION.
- PROVIDE SEISMIC BRACES FOR EQUIPMENT PER SPECIFICATIONS AND DETAIL F6/AE-501.
- PROVIDE BACKING PER DETAIL D7/AE-504 IN WALLS TO SEISMICALLY ANCHOR THE EQUIPMENT AT TOP, BOTTOM & MIDDLE AND EQUIPMENT MANUFACTURER'S INSTRUCTIONS.
- PROVIDE BODY REFRIGERATORS WITH ALL UTILITIES NECESSARY FOR A FULLY FUNCTIONAL EQUIPMENT INCLUDING POWER, CONDENSERS AND CHILLED WATER LINES. PROVIDE SHOP DRAWINGS INCLUDING ANCHORAGE DETAILS FOR REVIEW AND APPROVAL.
- BODY REFRIGERATORS SHALL BE EQUIPPED WITH TEMPERATURE MONITORING AND ALARM SIGNALS THAT ANNUNCIATE AT THE OFFICE ROOM 041 AND SHALL TRANSMIT REMOTELY OVER VA NETWORK TO MORGUE SUPERVISOR 24 HOURS A DAY ON A PORTABLE DEVICE.
- TRANSPORT OWNER FURNISHED AUTOPSY TABLES FROM VA WAREHOUSE BLDG 47 TO ROOM 43 FOR FINAL INSTALLATION. PROVIDE ALL NEW MECHANICAL/PLUMBING/ELECTRICAL INFRASTRUCTURE FOR FULLY FUNCTIONAL AUTOPSY TABLES.
- PROVIDE SEISMIC BRACES FOR STORAGE CABINET ANCHOR TO WALL TOP, MIDDLE AND BOTTOM OR PER MANUFACTURER'S INSTRUCTIONS.
- SUBMIT PRODUCT DATA/SHOP DRAWINGS OF ALL EQUIPMENT FOR REVIEW AND APPROVAL PRIOR TO PROCUREMENT/INSTALLATION.
- FOR BODY LIFT STATION STRUCTURAL SUPPORT SYSTEM SEE QH-101, QH-102. SUBMIT SHOP DRAWINGS OF STRUCTURAL SUPPORT SYSTEM WITH STRUCTURAL CALCULATIONS SIGNED AND SEALED STRUCTURAL ENGINEER LICENSED IN CALIFORNIA FOR 770LBS OF MAXIMUM LOAD. PROVIDE TESTING BY AN INDEPENDENT TESTING AGENCY.
- FOR FOLDING PARTITION STRUCTURAL SUPPORT SYSTEM SEE STRUCTURAL DRAWINGS. SUBMIT SHOP DRAWINGS OF STRUCTURAL SUPPORT SYSTEM WITH STRUCTURAL CALCULATIONS SIGNED AND SEALED STRUCTURAL ENGINEER LICENSED IN CALIFORNIA. PROVIDE TESTING BY AN INDEPENDENT TESTING AGENCY.

FULLY SPRINKLERED
FINAL CONSTRUCTION DOCUMENTS

35% SCHEMATIC SUBMISSION	09/12/15
95% CONSTRUCTION DOCUMENTS	03/14/16
100% CONSTRUCTION DOCUMENTS	04/01/16
FINAL CONSTRUCTION DOCUMENTS	04/29/16
ADDENDUM 1	09/13/16
Revisions	Date

CONSULTANTS:



ARCHITECT/ENGINEERS:



3920 E. CORONADO STREET, SUITE 201
ANAHEIM CALIFORNIA 92807
1000 S FREMONT AVE, UNIT 53,
BLDG. A1, SUITE 1218
ALHAMBRA CALIFORNIA 91803
www.SRDarchitectsinc.com
O: 714 688 0212 • 626 202 0546 • FAX: 714 688 0244

Drawing Title
EQUIPMENT SCHEDULE

Approved
CHIEF CONSTRUCTION MANAGEMENT/DESIGN SECTION

PROJECT ENGINEER

Project Title
MORGUE RENOVATION FOR
FAMILY ACCESS

Location
5901 EAST SEVENTH STREET
LONG BEACH, CA 90822

Date
04/29/16

Checked
WH

Drawn
MK

Project Number
600-15-102
Building Number
2

Drawing Number
AE-105
Dwg. 24 of 81

Office of
Construction
and Facilities
Management

