

VA244-16-B-1679 Bldg 138 Entrance Doors Questions & Answers

Q1. removal of the pressure activated mats will leave a void in the concrete and in the vestibule flooring.

Q1.a) shall we include the concrete repairs?

Q1.b) shall we patch the vestibule flooring to match the existing?

A 1.

A 1. a) Contractor shall fill the void of the removed actuator mats x 2 which is an area of 3 ft. wide by 10 ft. long by ½" deep.

A1. b) match the existing vestibule tile floor with similar tile finish and color; COR to approve tile prior to contractor replacing.

Q 2. does the VA want to keep the existing door openers?

A 2. Contractor shall remove existing automatic door openers intact and give to the CVAMC COR.

Q 3. shall we re-use the existing door locks?

A 3. Existing door locks shall be re-used or replaced if damaged with a BEST 7 pin core

Q 4. the ceiling will require repair after demolition of the revolving doors. Shall the ceilings be patched and/or repainted to match existing?

A 4. Upon removal of the revolving door, patch and paint the ceiling to match paint; COR to approve finish and paint color before proceeding.