

2 Ea., John Deere ProGator UTV 2030A 4x4 Diesel or similar item.

Color: Green

3 Cylinder liquid cooled diesel

Horsepower: 22.1

Maximum speed (With standard tires) 19.1 MPH

4-Wheel Drive

Hydraulic dump bed

Transmission: Five-speed synchro-mesh with five forward gears and one reverse gear.

Hydraulic power steering

Suspension: Heavy duty Dual leaf springs and shocks

4-wheel hydraulic disk brakes

Fuel capacity: 8 Gallons

Dimensions:

|                                  |                    |
|----------------------------------|--------------------|
| Ground clearance (unloaded)      | 168 mm/6.6 in.     |
| Bed height (loaded)              | 832 mm/32.75 in.   |
| Wheelbase                        | 167.6 cm/66 in.    |
| Wheel tread, front               | 123.2 cm/48.5 in.  |
| Wheel tread, rear standard       | 129 cm/50.8 in.    |
| Width, overall (standard tires)  | 158.6 cm/62.4 in.  |
| Length, overall (standard tires) | 319.2 cm/125.7 in. |
| Length, overall with box         | 328.5 cm/129.3 in. |
| Length, overall without box      | 319.2 cm/125.7 in. |
| Height, overall                  | 193.6 cm/76.25 in. |

Turning circle clearance:

|                       |                        |
|-----------------------|------------------------|
| Inside diameter - 2WD | Radius: 457 mm/18 in.  |
| Inside diameter - 4WD | Radius: 1752 mm/69 in. |

|   |                |
|---|----------------|
| Maximum gross vehicle weight(includes 200-lb operator, 200-lb passenger, loaded attachment) | ---            |
| 4WD with heavy-duty suspension, wide rear tire, and four-post ROPS                          | 2841 kg6264 lb |
| Base machine weight (no passenger, no operator, no loaded attachment, full fluids)          | ---            |
| 4WD with heavy-duty suspension, wide rear tire, and four-post ROPS                          | 971 kg2140 lb  |
| Payload capacity (includes 200-lb operator, 200-lb passenger, and loaded attachment)        | ---            |
| 4WD with heavy-duty suspension, wide rear tire, and four-post ROPS                          | 1871 kg4125 lb |
|   | ---            |

Cargo box internal dimensions

Length

160 cm/63 in.

Width

128.3 cm/50.5  
in.

Height

26.7 cm/10.5 in.

Towing capacity (rear hitch): 680kg/ 1500 lb