


three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
three eighths inch = one foot
one quarter inch = one foot
one eighth inch = one foot
one sixteenth inch = one foot

"IN THE EVENT THAT BONES OR HISTORIC ARCHAEOLOGICAL MATERIAL ARE UNCOVERED DURING CONSTRUCTION OR EARTH DISTURBING ACTIVITIES, CEASE WORK IMMEDIATELY AND PROTECT THE REMAINS FROM FURTHER DISTURBANCE. NOTIFY THE OWNER, THE DIRECTOR OF FORT BLISS NATIONAL CEMETERY AT 915-564-0201. THE OWNER WILL CONTACT THE NEW MEXICO HISTORIC PRESERVATION DIVISION (SHPO). THE OWNER AND SHPO MAY DISCUSS THE APPROPRIATE WAY TO PROCEED. DIRECTION TO THE CONTRACTOR WILL BE PROVIDED BY THE OWNER."



GENERAL CONSTRUCTION SEQUENCE

1. THE CONTRACTOR SHALL CONTACT NEW MEXICO ONE-CALL "811" NUMBER AND SHALL COORDINATE WITH THE PROPER LOCAL AUTHORITIES OR RESPECTIVE UTILITY COMPANIES TO LOCATE UNDERGROUND UTILITIES PRIOR TO COMMENCING WORK.
2. CONTRACTOR SHOULD NOTIFY THE COTR AT LEAST 72 HOURS IN ADVANCE OF ANY WORK.
3. SCHEDULE A PRE-CONSTRUCTION SITE MEETING TO DISCUSS ALL ELEMENTS OF THE CONSTRUCTION PROGRAM.
4. INSTALL THE STABILIZED CONSTRUCTION ENTRANCE AND STAGING AREA.
5. INSTALL SILT FENCE BARRIER AS SHOWN ON THE PLAN.
6. REMOVE TREES AND CONDUCT DEMOLITION WORK.
7. PERFORM ROUGH GRADING.
8. INSTALL PERIMETER UNDERDRAIN.
9. COMPLETE SITE CONSTRUCTION AND STABILIZE ALL DISTURBED AREAS. ALL AREAS TO BE LANDSCAPED SHALL BE PERMANENTLY SODDED.
10. UPON AUTHORIZATION FROM THE CONTRACTING OFFICER, REMOVE EROSION AND SEDIMENT CONTROL MEASURES.
11. DEMOLIBLIZE FROM SITE.

NOTES



1. EXACT LOCATION AND DIMENSIONS OF STAGING AREA TO BE FIELD LOCATED AND APPROVED BY THE COTR AND THE CEMETERY STAFF.
2. PROVIDE CHAINLINK FENCE WITH PRIVACY SCREEN AROUND STAGING AREA.
3. PUBLIC ACCESS SHALL BE MAINTAINED AT THE EXISTING ENTRANCE THROUGHOUT CONSTRUCTION OPERATIONS.

EROSION AND SEDIMENT CONTROL NOTES:






1. CONTRACTOR SHALL BE RESPONSIBLE FOR APPLYING AND SECURING ANY PERMITS NECESSARY FOR CONSTRUCTION.
2. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
3. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
4. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE E&SC PLAN APPROVING AUTHORITY.
5. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE E&SC PLAN APPROVING AUTHORITY.
6. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.
7. THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH RUN-OFF PRODUCING EVENT. ANY NECESSARY REPAIRS OR CLEAN-UP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
9. CONTRACTOR SHALL INSTITUTE MEASURES AS NECESSARY FOR FUGITIVE DUST CONTROL. DUST CONTROL MEASURES TO BE APPROVED BY THE COTR.
10. GRASS SHALL BE ESTABLISHED ON DISTURBED AREAS WHICH ARE AT FINAL GRADE OR WILL NOT BE WORKED FOR LONGER THAN 14 DAYS. ALTERNATIVES TO GRASS INCLUDE 2" MINIMUM STRAW MULCH COVER, EROSION BLANKETS WITH ANCHORS, 6-MIL PLASTICS. IF AFTER 14 DAYS, THE TEMPORARILY SEEDED AREAS HAVE NOT ATTAINED 98% COVER, THESE AREAS SHALL BE RESEEDDED.
11. SLOPES STEEPER THAN 1V:3H SHALL BE SODDED, OR MULCHED AND SEEDED, OR STABILIZED USING EROSION CONTROL MATTING.
12. AT CONCLUSION OF PROJECT, ALL DISTURBED AREAS WITHIN SHALL BE SODDED.

LEGEND

- LIMITS OF DISTURBANCE
- SILT FENCE
- TREE PROTECTION
- STORM INLET PROTECTION



100% CONSTRUCTION DRAWINGS

REVISION 1		2-24-12		SUB-CONSULTANTS		PRIME CONSULTANT		Drawing Title		Project Title		Project Number		NATIONAL CEMETERY ADMINISTRATION OFFICE OF DESIGN AND CONSTRUCTION					
				 MORROW REARDON WILKINSON MILLER, LTD., LANDSCAPE ARCHITECTS 210 Le Veta NE, Albuquerque, NM 87108 505-266-2246 FAX 505-265-9637 MLTW@MILLERLTD.COM		 CHERRY SEIREAMES ARCHITECTS, LLP 225 SIO AVE. SUITE 200 HOUSTON, TX 77058 800-840-1278 FAX 281-366-0289		 11/18/2011		 2020 K STREET, SUITE 300 WASHINGTON, DC 20006 TELEPHONE: (202)872-0277 FAX: (202)872-0282.		EROSION AND SEDIMENT CONTROL PLAN OVERALL				CEMETERY IMPROVEMENTS AND NEW MAINTENANCE BUILDING		885CM3007	
								Approved: Director Office of Design and Construction		Location		Building Number				Drawing Number			
										FORT BAYARD, NEW MEXICO		-				L-101			
Revisions:		Date								Date		Checked				Drawn			
										NOVEMBER 18, 2011		JMUH		OS					
														Dwg. 015 of 120					
														 Department of Veterans Affairs					