

My Health eVet: Renovate Rooms 1C07-1 and 1 C08-1  
Amendment #2:

Questions:

**1) WHAT IS THE HEIGHT AND WIDTH OF THE LUMICOR PANELS A/B SIDES?**

**A. 3'9"x 6'5"**

**B. 5'1-1/2" x 6'5"**

**Please see resin elevation drawing A-3.**

**2) AFTER TALKING TO THE SUPPLIER THE LUMICOR PRODUCT COMES IN 3/8" NOT 1/4" THICKNESS?**

**Correction: This resin is only available in 3/8" product. Please see Resin Product Information page.**

**3) IS THIS PRODUCT TO BE ATTACHED TO THE WALL AT ANY POINT?**

**The panels will be suspended at bottom, on the hinge point, and both sides abutting the drywall. A decorative mounting hardware system like Gyford Stand Off Systems or equivalent will be used. Grippers with appropriate assemblies will need to be purchased. Quantities are to be: 3 Bottom Grippers, 3 Hinges, and 6 (3 per side) Edge/Side Grippers. The standoff finish will be Clear Anodize, Aluminum. Please see resin elevation drawing A-3.**

**4) AT THE POINT OF THE STAR WILL THE TWO PIECES MEET AT A POINT OR WILL IT BE SEPARATED TO ALLOW FOR BRACKETS?**

**Please see the response to question #3.**

**5) THE DRAWINGS SHOW THESE PANELS TO BE SOLID PIECES. WILL THEY BE SOLID PANELS OR IN MULTIPLE PANELS?**

**They will be two separate solid panels.**

**6) HOW FAR OFF THE FLOOR AND CEILING DO YOU WANT THE PANELS TO BE?**

**The gap will be determined by the space of the attachment hardware. The gap is estimated to be between 3/4" and 1 1/4".**

**7) DOOR FRAMES AND WALL PANELS WILL THEY BE A MILL FINISH?**

**Please refer to the solicitation specifications Division 08 XX XX Sections.**

My Health eVet: Renovate Rooms 1C07-1 & 1C08-1  
Amendment #2:

8) DOES THE VA HAVE A CONTRACT FOR THE SPRINKLER SYSTEM?

No, the VA does not have a contract for the sprinkler system. The work on the sprinkler system will have to be provided by the construction contractor.

9) PLEASE EXPLAIN THE WL1 FORMICA/WILD CHERRY. WHERE IS THIS BEING USED?

As noted on Amendment 1 page 2 drawing A-2 on the left hand side under Other Finish Reference Notes: four notes down the list, WL1 is the laminate finish for the Resin Panel Base. This base is referenced on drawing A-1 in Note #3. Wood construction base with suspended resin wall. Also, please see elevation drawing A-3.

10) IS THE SOLID SURFACE GOING ON A CABINET PROVIDED BY THE VA?

No, the solid surface is to be provided by the construction contractor and to be installed by the construction contractor on the built-in casework.

11) WILL ALL CABINETS AND FURNITURE BE PROVIDED BY THE VA.

The built-in casework that will be in place of the existing Storage Closet 1C07A-1 will be provided and installed by the construction contractor as noted on drawing A-1 Note #1 & #7. The office desk furniture and chairs will be provided by the VA. The office desk furniture is indicated on drawing A-1 in yellow with the words ARROWOOD.

12) DOOR SHOWN ON DRAWING A/2 SHOWS TO BE A SLIDER BUT ON PG. 4 SHOWS TO BE STANDARD SWING DOORS. PLEASE CLARIFY.

Page 4 & Page 5 of Amendment 1 are the correct configuration of the storefront doors. Please look closely, as they are sliding doors (barn-door style). These doors are not swing doors.

13) IS THERE A WAY TO GET ANOTHER SITE VISIT?

No.