

Questions:

1. Drawing AR-102; Demo Note 4. Existing stainless steel cladding to remain. However on Drawing AR-103, it states that new stainless steel cladding is being installed. Which is correct? Please advise.
Dwg AR-103 is correct, We are furring out the wall behind the equipment to conceal the piping.
2. Is there any plumbing associated with the VA supplied eye wash station?
The eyewash station is a 'waterless' unit, so no plumbing associated.
3. Drawing AR-103; specification for new lockers?
Metal lockers to be standard, 12"w, 18" d, 72" ht, double tier, with solid base, with the capability to accommodate padlocks. Color to be selected by VA.
4. Drawing AR-103; there is no detail 2 for the sealed opening from the kitchen area to the adjacent hallway.
Correction: Sealed opening on the construction plan should refer to detail 4 on dwg. AR-500.
5. Please provide more information as to which specific rooms are included in each of the individual phases. For example, which rooms make up Phase 1: Cooking Area, etc.?
The contractor would have full access to the canteen kitchen (second floor) during construction. Please refer to dwg. AR-101 for phasing issues at the first floor.