







- | DEMOLITION SHEET TAG NOTES | | WORK OF SS 02.05.00 UNLESS OTHERWISE NOTED. |
|----------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------|
| 1 | REMOVE SHEET METAL COVERINGS TO EXPOSE ORIGINAL WOOD MILLWORK AND WINDOW CASINGS. TEMPORARILY REMOVE METAL GRATES FOR REFURBISHMENT. REMOVE ALUMINUM FRAMED STORM SASHES (WHERE APPLICABLE). | |
| 2 | REMOVE EXISTING MASONRY WALL, COLUMNS AND WINDOWS ON TWO FLOORS OF PORCH. PROVIDE TEMPORARY SHORING AND BRACING OF ROOF STRUCTURE ABOVE AS NECESSARY. | |
| 3 | REMOVE METAL STAIR RAILING. | |
| 4 | REMOVE STORM DOOR AND FRAME. | |
| 5 | REMOVE ALUMINUM FRAMED STORM WINDOW SASHES. | |
| 6 | CAREFULLY REMOVE EXTERIOR SHEET METAL AND METAL SIDING FINISHES WHICH CONCEAL WOOD MILLWORK AT EAVES, SOFFITS, FREEZE, FASCIA, WINDOW DORMERS, ETC. USE CARE TO PREVENT UNNECESSARY DAMAGE TO CONCEALED WOOD MATERIALS. | |
| 7 | REMOVE SHEET METAL ON ROOF SURFACE OF DORMERS. | |
| 8 | REMOVE EXISTING METAL ROOFING OVER KITCHEN ROOF. | |
| 9 | STRIP PAINT FINISH FROM EXISTING CONCRETE AND STONE PORCH SURFACES. | |
| 10 | REMOVE EXISTING TRANSITE SHINGLES ON MANSARD PORTION OF ROOF. WORK OF SPECIFICATION SECTION 07 01 50. | |
| 11 | CAREFULLY REMOVE CEMENTITIOUS MATERIAL USED TO SEAL THE FIREPLACE OPENING CLOSED WITHOUT COMPROMISING THE SURROUNDING MASONRY STRUCTURE. | |
| 12 | REMOVE DOUBLE HUNG WOOD WINDOWS LOCATED ON SECOND FLOOR. | |
| 13 | REMOVE WINDOW MOUNTED AIR CONDITIONING UNITS, TRANSMIT TO OWNER. | |
| 14 | REMOVE EXISTING CONCRETE PAVEMENT. | |
| 15 | CUT OPENING IN MASONRY WALL AS NECESSARY FOR THE RETURN AIR CHASE ASSOCIATED WITH THE NEW MECHANICAL SYSTEM. COORDINATE OPENING REQUIREMENTS WITH MECHANICAL DRAWINGS. PROVIDE STEEL ANGLE UNTEL TO SUPPORT NEW MASONRY OPENING AS REQUIRED. | |
| 16 | REMOVE EXISTING DOWNSPOUT. | |
| 17 | CUT OPENINGS IN FLORICOR OR CLG LATICAST ASSEMBLY FOR NEW AC SUPPLY REGISTER/DIFFUSERS OR LIGHT FIXTURES. COORDINATE WITH MECHANICAL DRAWINGS AND WITH BID ALTERNATE #1 WORK. | |
| 18 | REMOVE EXISTING DOOR; SALVAGE CASINGS FOR REUSE. | |
| 19 | REMOVE STAIR LANDING NEVEL POST - WORK OF BID ALTERNATE #1. | |
| 20 | REMOVE EXISTING DOOR AND FRAME. | |
| 21 | REMOVE EXISTING PLYWOOD PANEL AT CRAWL SPACE ACCESS. | |
| 22 | REMOVE EXISTING STORAGE CLOSET DOOR HARDWARE, FRAME AND CASING TRIM. COORDINATE WITH INSTALLATION OF RETURN AIR GRILLE. | |

- ## GENERAL DEMOLITION NOTES
1. THE OWNER WILL OCCUPY THE BUILDING AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THE SAFETY OF OWNER PERSONNEL AND THE PUBLIC. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN ALL NECESSARY TEMPORARY MOVEMENTS AND TEMPORARY BARRIERS REQUIRED TO COMPLETE THE WORK. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE BUILDING IN AN INSULATED, WEATHERTIGHT, SECURE MANNER AT ALL TIMES DURING THE WORK.
 2. PRIOR TO COMMENCEMENT OF WORK THE OWNER WILL TEMPORARILY RELOCATE LOOSE FURNISHINGS/EQUIPMENT FROM AREAS SCHEDULED FOR INTERIOR RENOVATION. THE OWNER WILL TEMPORARILY MOVE FURNISHINGS AND OTHER OPERATIONS TO ROOMS 102, 103, AND 104. IF BID ALTERNATE ONE IS ACCEPTED, THE CONTRACTOR SHALL PHASE INTERIOR WORK IN SUCH A MANNER THAT ALL RENOVATION WORK IN ROOM 101 SHALL BE COMPLETED PRIOR TO COMMENCEMENT OF ANY DEMOLITION &/OR NEW WORK ASSOCIATED WITH BID ALTERNATE NUMBER ONE.
 3. THE CONTRACTOR SHALL COORDINATE WITH THE OWNER'S REPRESENTATIVE FOR SALVAGE OF MATERIALS SCHEDULED FOR PERMANENT REMOVAL INCLUDING, BUT NOT LIMITED TO WINDOW MOUNTED AIR CONDITIONERS. MATERIALS IDENTIFIED BY THE OWNER TO BE SALVAGED SHALL BE DELIVERED TO THE LOCATION SPECIFIED BY THE OWNER. UNLESS OTHERWISE PROVIDED, ALL OTHER PERMANENTLY REMOVED MATERIAL SHALL BE CONSIDERED TRASH. COLLECTION AND LEGALLY DISPOSE OF TRASH FROM THE CONSTRUCTION SITE IS THE CONTRACTOR'S RESPONSIBILITY.
 4. IDENTIFICATION OF MATERIALS TO BE DEMOLISHED AND/OR REMOVED IS PROVIDED AS A CONVENIENCE TO THE CONTRACTOR. FAILURE TO IDENTIFY COMPLETE REMOVAL/DEMOLITION REQUIREMENTS NECESSARY FOR THE NEW PROJECT DOES NOT CONSTITUTE THE CONTRACTOR'S RESPONSIBILITY TO PERFORM THE NECESSARY WORK.
 5. CUT AND PATCH TO MATCH EXISTING CONDITIONS ALL CONSTRUCTION ASSEMBLIES AS NECESSARY TO COMPLETE THE NEW MECHANICAL AND ELECTRICAL WORK. ALL NEW ELECTRICAL CONDUIT AND WIRING SHALL BE FULLY CONCEALED. ROUTE OUT RACEWAYS IN PLASTER/MASONRY ASSEMBLIES AS NECESSARY TO COMPLETE THE REQUIREMENTS WITH MECHANICAL AND ELECTRICAL DRAWINGS.
 6. REMOVE AND LEGALLY DISPOSE OF ALL PLANT MATERIAL LOCATED WITHIN 5 FEET OF THE FOUNDATION WALL ON ALL SIDES OF THE BUILDING.
 7. **GENERAL INTERIOR DEMOLITION REQUIREMENTS BASE BID:**
RECEPTION 101: REMOVE CARPET, SUSPENDED CEILING, WOOD PANELING AND ASSOCIATED FLOOR FINISHES IN ROOMS 102, 103 AND 104. REMOVE PAINT AND SALVAGE FOR REUSE. REMOVE LIGHT FIXTURES MOUNTED ABOVE SUSPENDED CEILING. REMOVE ALL ELECTRICAL DEVICE COVERS AND PROTECT DEVICES/WIRING FROM DAMAGE.
 8. **GENERAL INTERIOR DEMOLITION REQUIREMENTS: BID ALTERNATE NO. ONE:**
DIRECTOR'S OFFICE 103, RESTROOM 102A, WORKROOM 102, KITCHEN 104 AND STAIR (S1-1). PROTECT WOOD FLOORING IN 103 and 102 FROM DAMAGE AND REMOVE SHIP LUGS IN ROOMS 102, 103 AND 104. REMOVE EXISTING W/S S2 02 13 13. REMOVE CARPET FROM RISERS, TREADS AND LANDING ON STAIR (S1-1). REMOVE WOOD PANELING AND WOOD BASE IN ROOMS 102, 103 AND 104. REMOVE CONCEALED SPLINE CEILINGS AND ALL ASSOCIATED SUSPENSION SYSTEMS IN ROOMS 102, 103 AND 104. REMOVE ALL ELECTRICAL DEVICE COVERS AND PROTECT DEVICES/WIRING FROM DAMAGE.
KITCHEN & RESTROOM CABINETS APPLIANCES AND PLUMBING FIXTURES TO REMAIN; PROTECT THEM FROM DAMAGE. REMOVE WALL COVERING IN ROOM 104.

- # DEMOLITION PLAN LEGEND
- | | |
|---------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------|
|  | EXISTING WINDOW & EXTERIOR SILLS TO BE REMOVED. PREPARE OPENING TO RECEIVE NEW WINDOWS. |
|  | EXISTING DOOR, FRAME, & HARDWARE TO REMAIN |
|  | EXISTING DOOR & HARDWARE TO BE REMOVED. PREPARE OPENING TO RECEIVE NEW DOOR & HARDWARE UNLESS OTHERWISE DETAILED. |
|  | EXISTING ROOFING TO BE REMOVED. |
|  | EXISTING CONCRETE PAVEMENT TO BE REMOVED. |
|  | EXISTING ELECTRICAL / COMMUNICATION DEVICE TO REMAIN. COORDINATE WITH NEW CONSTRUCTION DRAWINGS. |

100% BID DOCUMENTS	4/07/11
95% DESIGN DOCUMENTS	1/11/11
90% DESIGN DOCUMENTS	11/22/10
50% DESIGN DOCUMENTS	10/08/10
Revisions:	Date

CONSULTANTS:

Tate•Hill•Jacobs: Architects

346 East Main Street•Lexington•Kentucky•40507
Telephone 859•252•5994 Facsimile 859•253•1607



ARCHITECT/ENGINEERS:

SMITHGROUP
architecture engineering interiors planning

SMITHGROUP, INC.
500 GRISWOLD
SUITE 1700
DETROIT, MICHIGAN 48226
T 313.983.3600
F 313.983.3636
www.smithgroup.com



NATIONAL
CEMETERY
ADMINISTRATION

Drawing Title
DEMOLITION FLOOR PLANS
Approved: Project Director

100% BID DOCUMENTS			
Project Title Renovate Meigs Lodge Building Lebanon National Cemetery		Project Number	
		Building Number	
Location Marion County, Kentucky		Drawing Number D-1	
Date APRIL 7, 2011	Checked MJ	Drawn JES	
		Dwg. 2 of 12	