three inches = one foot
one and one-half inch = one foot
one inch = one foot
three-quarters inch = one foot
one-half inch = one foot
three-eighths inch = one foot
one-quarter inch = one foot
one-eight inch = one foot

ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR		WALLS								CEILING			MILLWORK	
				NORTH		EAST		SOUTH		WEST		TYPICAL	TYPICAL	TYPICAL	COUNTERTOPS &	CABINETS &
		FINISH	BASE	SURFACE	FINISH	SURFACE	FINISH	SURFACE	FINISH	SURFACE	FINISH	SURFACE	FINISH	HEIGHT	BACKSPLASHES	SUPPORTS
01	WAITING ROOM	LVT-1,2	RB-1	-	P-4	-	P-4	-	P-4	-	P-4	-	-	-	-	-
02	VESTIBULE	LVT-2,3	RB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
03	VESTIBULE	LVT-2	RB-1	-	P-4	-	P-3	-	P-4	-	-	-	-	-	-	-
04	MASS SHOWER	PT-4	PTB-1	-	P-1,PT-1	-	P-1,PT-1	-	P-1,PT-1	-	P-1,PT-1	-	-	-	-	-
05	TRIAGE	LVT-2	RB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
06	VESTIBULE	LVT-2,3	RB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
07	DECON SHOWER	PT-4	PTB-1	-	P-1,PT-1	-	P-1,PT-1	-	P-1,PT-1	-	P-1,PT-1	-	-	-	-	-
08	PARAMEDIC	LVT-2	RB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
09	ADMIN/INFO/REGISTRATION	LVT-1,2	RB-1	-	P-4	-	P-3	-	P-4	-	P-4	-	-	-	SS-2	HPL-1,3
10	SECURED CHECK IN	LVT-1,2	RB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	SS-2	HPL-1,3
11	TEMP WAITING	LVT-1,2	RB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
12	SECURITY CHECK IN	LVT-1,2	RB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	SS-2	HPL-1,3
13	EQUIP/STORAGE	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
14	WHEELCHAIR /STRETCHER	LVT-2	RB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
15	ANTE ROOM	SV-1	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
17	ADO STORAGE	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
18	TRIAGE	LVT-2	RB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
19	WOMEN	PT-1	PTB-1	-	P-4, PT-1, 2, 3, PTB1, PTBN1	-	P-4,PT-1, 2, 3, PTB1, PTBN1	-	P-4,PT-1,2,& 3, PTB1, PTBN1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	-	-	SS-1	HPL-2
19	WOMEN	PT-1	PTB-1	-	P-4, PT-1, 2, 3, PTB1, PTBN1	-	P-4,PT-1,2,& 3, PTB1, TTBN1	-	P-4, PT-1,2,&3, PTB1, PTBN1	-	P-4,PT-1,2, &3, PTB1, PTBN1	-	-	-	SS-1	HPL-2
21	BEREAVEMENT	CPT-1,2	RB-1	-	P-2	-	P-3	-	P-2	-	P-2	-	-	-	-	-
22	CORRIDOR	LVT-1,2	RB-1	-	P-2	-	P-3	-	P-2	-	P-2	-	-	-	-	-
23	VESTIBULE	LVT-2	RB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
24	DECON SHOWER CORRIDOR	PT-1, PT-4	PTB-1	-	P-1,PT-1	-	P-1,PT-1	-	P-1,PT-1	-	P-1,PT-1	-	-	-	-	-
26	ASSIGNMENT AREA	SV-1,2	SVB-2	-	P-2	-	P-2	-	P-2	-	P-3	-	-	-	-	-
27	XRAY ALC	SV-2	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
28	ELECTRICAL ROOM	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
30	NURSES STATION	SV-2,3	SVB-2	-	P-2	-	P-4	-	P-2	-	P-2	-	-	-	SS-2	HPL-2
31	TRAUMA ISOLATION	SV-1,2	SVB-1	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
32	TRAUMA	SV-1,2	SVB-1	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
33	TRAUMA	SV-1,2	SVB-1	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
34	TRAUMA	SV-1,2	SVB-1	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
35	CONTROL ROOM	SV-1,2	SVB-1	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
36	CT SCAN	SV-1,2	SVB-1	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
37-38	X-RAY/CONTROL ROOM	SV-1,2	SVB-1	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
40	EXAM ISOLATION	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
41	EYE EXAM	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
42	EXAM ROOM	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
43	EXAM ROOM	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
44	EXAM ROOM	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
45	EXAM ROOM	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
46	GYNE EXAM ROOM	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-3	-	P-2	-	-	-	-	-
47	OXY FULL	SV-1	SVB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
48	OXY EMPTY	SV-1	SVB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
49	WOMEN	PT-1	PTB-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,& 3, PTB1, PTBN1	-	P-4, PT-1,2,&3, PTB1, PTBN1	-	P-4,PT-1,2, &3, PTB1, PTBN1	-	-	-	-	-
50	MEN	PT-1	PTB-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	-	-	-	-
51	PSYCH OBSERVATION	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
52	OPEN PATIO	CON	-	-	-	-	-	-	-	-	-	-	-	-	-	-
53	PSYCH OBSERVATION	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
54	OPEN PATIO	CON	-	-	-	-	-	-	-	-	-	-	-	-	-	-
55	PHYSICIAN	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
55A	STORAGE	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
56	ON-CALL	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
57	TOILET	PT-1	PTB-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	-	-	-	-
58	BREAK ROOM	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
59	TRAINING/SOC. WORKER	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
60	GE STORAGE	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
61	HEAD NURSE	SV-1,2	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
62	HAC	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
63	SOIL UTILITY	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
64	SOIL LINEN	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
66	CLEAN SUPPLY	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
66A	CLEAN LINEN	VCT-1	RB-1	-	P-1	-	P-1	-	P-1	-	P-1	-	-	-	-	-
67	SPLINTING	SV-1	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
68	PROCEEDURE ROOM	SV-1	SVB-1	-	P-2	-	P-2	-	P-2	-	P-2	-	-	-	-	-
69	PATIENT TOILET	PT-1	PTB-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	-	-	-	-
70	PATIENT TOILET	PT-1	PTB-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1,PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	-	-	-	-
71	CORRIDOR	SV-1,2,3	SVB-2	-	P-2	-	P-4	-	P-2	-	P-2	-	-	-	-	-
73	CORRIDOR	SV-1,2,3	SVB-2	-	P-2	-	P-4	-	P-2	-	P-2	-	-	-	-	-
75	CORRIDOR	SV-1,2,3	SVB-2	-	P-2	-	P-4	-	P-2	-	P-2	-	-	-	-	-
76	CORRIDOR	SV-1,2,3	SVB-2	-	P-2	-	P-3	-	P-2	-	P-2	-	-	-	-	-
77	CORRIDOR	SV-1,2,3	SVB-2	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
77A	VESTIBULE	SV-1,2	SVB-2	-	P-3	-	P-2	-	P-2	-	P-2	-	-	-	-	-
78	ADO TOILET	PT-1	PTB-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	P-4,PT-1,2,&3, PTB1, PTBN-1	-	-	-	-	-

ROOM FINISH SCHEDULE GENERAL NOTES

1. IT SHALL BE THE SPECIFIC DUTY AND RESPONSIBILITY OF EACH TRADE AND/OR SUPPLIER TO EXAMINE ALL DRAWINGS AND SPECIFICATIONS, AND TO PROVIDE AND/OR INSTALL ALL PROPER MATERIALS PERTAINING TO THEIR PART OF THE WORK AS NECESSARY FOR A COMPLETE INSTALLATION. THE INSTALLATION OF ALL MATERIALS SHALL CONFORM TO THE RECOMMENDED INSTALLATION INSTRUCTIONS OF THE APPROPRIATE MANUFACTURER, UNLESS NOTED OTHERWISE.

2. THE ROOM FINISH SCHEDULE(S) ARE FOR THE CONVENIENCE OF THE CONTRACTOR(S) TO ASSIST THEM IN UNDERSTANDING AND CONSTRUCTING THE PROJECT. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THAT ALL ITEMS IN THE SCHEDULE(S) REFLECT THE DRAWINGS AND SPECIFICATIONS.

3. ANY OMISSIONS OR DISCREPANCIES IN THE DRAWINGS AND SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT BY THE CONTRACTOR PRIOR TO BID OPENING. BIDS RECEIVED SHALL BE CONSIDERED TO INCLUDE ALL ITEMS FOR A COMPLETE PROJECT. NO EXTRAS SHALL BE ALLOWED.

4. REFER TO THE ARCHITECTURAL REFLECTED CEILING PLAN(S) FOR THE LOCATIONS, HEIGHTS, AND EXTENT OF SOFFITS. ALL SOFFITS SHALL RECEIVE THE SAME FINISH AS THE ADJACENT WALL(S), UNLESS NOTED OTHERWISE.

5. REFER TO THE PLANS AND INTERIOR ELEVATIONS FOR THE LOCATION(S) AND EXTENT OF VARIOUS SURFACE AND FINISH MATERIALS IF MORE THAN ONE MATERIAL AND/OR FINISH IS NOTED FOR AN INDIVIDUAL ROOM OR AREA IN THE ROOM FINISH SCHEDULE.

6. PROVIDE TWO PERCENT (2%) EXCESS MATERIALS FOR ALL ROOM FINISH MATERIALS IN EACH STYLE, TYPE AND COLOR. EXCESS MATERIALS SHALL INCLUDE BUT NOT BE LIMITED TO ACOUSTICAL CEILING PANELS, CARPET, TILE, BASE, SHEET VINYL, LINOLEUM, VINYL WALL COVERING, CORNER GUARDS, HANDRAILS, WALL PROTECTION, CUBICLE CURTAINS, VERTICAL WINDOW BLINDS, ETC. REFER TO THE PAINT SPECIFICATIONS FOR EXCESS PAINT MATERIALS.

ROOM FINISH SCHEDULE SPECIFICATIONS

1. ALL TILE WORK SHALL COMPLY WITH THE HANDBOOK FOR TILE INSTALLATION, LATEST EDITION, AS PUBLISHED BY THE TILE COUNCIL OF AMERICA, INC., AND ANSI STANDARD NOS. A108, A118, AND A137.1.

2. ALL SHEET VINYL AND SHEET LINOLEUM FLOORING SEAMS SHALL BE HEAT-WELDED WITH MATCHING PATTERNED WELD RODS TO CAMOUFLAGE THE SEAMS TO BE NEARLY INVISIBLE. FINISH ALL SHEET FLOORING AND SEAMS FLUSH TO THE FLOOR AND FREE FROM VOIDS, RECESSES AND RAISED AREAS. PROVIDE INTEGRAL FLASH COVED BASE, WHERE SCHEDULED, WITH CONTINUOUS RIGID PLASTIC COVE FORMED WEDGES (3/4" OR 1" RADIUS) AND SLOPED CLEAR ANODIZED ALUMINUM RESILIENT FLOORING CAP EQUAL TO BENGARD MANUFACTURING #CM1122 OR #CM1125. SECURELY ATTACH CAP TO WALL WITH SCREWS AT 8" MAX. O.C.

ROOM FINISH SCHEDULE ABBREVIATIONS

CON	SLAB ON GRADE LIGHT BROOM FINISH
CG-1	CORNER GUARD: CS ACROVYN STYLE/COLOR:CHAMELEON/ # 410 BRUSHED SILVER PATTERN:METAL/SUEDE TEXTURE
CPT-1	CARPET TILE:J&J INVISION STYLE/COLOR: IMPRESSIONISM 7484/1262 PAINTBRUSH
CPT-2	CARPET TILE:J&J INVISION STYLE/COLOR:POMBALINE 7140/1473 PLUSH
HPL-1	HIGH PRESSURE LAMINATE:FORMICA STYLE/COLOR: 7708-58/FAUX GLAZ
HPL-2	HIGH PRESSURE LAMINATE:NEVAMAR STYLE/COLOR: MH4001T/MANHATTAN GLITZ
HPL-3	HIGH PRESSURE LAMINATE:FORMICA STYLE/COLOR: 2200-MC/DARK CHOCOLATE MICRODOT FINISH
LVT-1	LUXURY VINYL TILE: AMTICO SIZE: 18"X18" STYLE/COLOR:LA11/LINEAR CHALK
LVT-2	LUXURY VINYL TILE: AMTICO/SPACIA SIZE: 18"X18" STYLE/COLOR: CN34/CONCRETE MEDIUM
LVT-3	LUXURY VINYL TILE: AMTICO SIZE: 18"X18" STYLE/COLOR:SN36/NORWEGIAN SLATE
LVT-4	LUXURY VINYL TILE FEATURE STRIP: AMTICO SIZE: 1/4"X36" STYLE/COLOR:MP38/SILVER-T
P-1	PAINT:DUNN EDWARDS COLOR: DEW346/SWAN WHITE
P-2	PAINT:DUNN EDWARDS COLOR: DEC767/RIVERBED
P-3	PAINT:DUNN EDWARDS COLOR: DE5773/STONE SILVER
P-4	PAINT:DUNN EDWARDS COLOR: DE6180 NEW CORK
PT-1	PORCELAIN FLOOR TILE: AMERICAN OLEAN SIZE: 12"X24" STYLE/COLOR: AUO3 PLAYGROUND/SAND GROUT: STAR QUARTZ- LOCK GROUT # 240/LINEN
PT-2	PORCELAIN FLOOR TILE: AMERICAN OLEAN SIZE: 12"X12" STYLE/COLOR: AUO3 PLAYGROUND/SAND GROUT: STAR QUARTZ- LOCK GROUT # 240/LINEN
PT-3	PORCELAIN FLOOR TILE: AMERICAN OLEAN SIZE: 2"X12" DECO STYLE/COLOR: AU15/STREETLAMP/SIDEWALK GROUT: STAR QUARTZ- LOCK GROUT # 240/LINEN
PT-4	PORCELAIN FLOOR TILE: AMERICAN OLEAN SIZE: 3"X3" MOSAIC STYLE/COLOR: SH50/MORNING MIST GROUT: STAR QUARTZ- LOCK GROUT # 240/LINEN
PTB-1	PORCELAIN FLOOR TILE BASE: AMERICAN OLEAN SIZE: 6"X12" COVE BASE STYLE/COLOR: AUO3 PLAYGROUND/SAND GROUT: STAR QUARTZ- LOCK GROUT # 240/LINEN
PTBN-1	PORCELAIN FLOOR TILE BULLNOSE: AMERICAN OLEAN SIZE: 3"X12" BULLNOSE STYLE/COLOR: AUO3 PLAYGROUND/SAND GROUT: STAR QUARTZ- LOCK GROUT # 240/LINEN
RB-1	RUBBER COVED BASE: JOHNSONITE 4" COLOR: 150 WEATLANDS
SS-1	SOLID SURFACE: CORIAN COLOR: WITCH HAZEL
SS-2	SOLID SURFACE: CORIAN COLOR: SUEDE
SV-1	SHEET VINYL: ARMSTRONG STYLE/COLOR: MARMORETTE LP045/PARCHMENT BEIGE WELDING ROD: W1245 CREME ANGORA
SV-2	SHEET VINYL: ARMSTRONG STYLE/COLOR: MARMORETTE LP023/SERENE BLUE WELDING ROD: W1223 SEASIDE
SV-3	SHEET VINYL: ARMSTRONG STYLE/COLOR: COLORETTE LP401/YUKA TAN WELDING ROD: W1601 TURTLE BROWN
SVB-1	SHEET VINYL FLASH COVE BASE: ARMSTRONG STYLE/COLOR: MARMORETTE LP045/PARCHMENT BEIGE WELDING ROD: W1245 CREME ANGORA
SVB-2	SHEET VINYL FLASH COVE BASE: ARMSTRONG STYLE/COLOR: MARMORETTE LP023/SERENE BLUE WELDING ROD: W1223 SEASIDE
VCT-1	VINYL COMPOSITION TILE: ARMSTRONG IMPERIAL TEXTURE STYLE/COLOR: STANDARD EXCELON/ 51869 HUMUS
WP1	WALL PROTECTION: CS ACROVYN STYLE/COLOR: CHAMELEON/#410 BRUSHED SILVER PATTERN: METAL/SUEDE TEXTURE

Sheet Name

Department of Veterans Affairs

ARCHITECT OF :

SBBL Architecture + Planning
1001 North Alvernon Way # 105, Tucson, Arizona 85711
t: (520)320.0255 f: (520)320.0555 e: sbbl@sbbl.biz

EMERGENCY DEPARTMENT

AMARILLO VA HEALTH CARE SYSTEM
AMARILLO, TEXAS

Approved: VA Area Proj. Mgr.

V.A. PROJECT NO: VA258-P-0196
SBBL PROJECT NO: 0110.00.0
DRAWN BY: RBT
CHECKED BY: KI
DATE: 07/15/2011

△	Date	Revision

Approved: Med. Cter. Director

Approved: Asst. Admin Engineering Service

Approved: Asst. VA Medical Director

Approved: Chief of Facilities

Approved: Chief of Engineering

Approved: Chief of Projects

48-IS-1