

**FUJIFILM MEDICAL SYSTEMS USA, INC.**

419 WEST AVENUE, SUITE 165

STAMFORD, CT 06902-6300

203-363-3934 203-363-1887 (FAX)

<b>Ermon Owens</b> <b>VA Jacksonville Outpatient Clinic</b> 1833 Boulevard St. Jacksonville, FL 32206 Purchasing Group: VA
--

Date:	1/18/2012
Quote #:	0394003201100344-6
Expires:	2/17/2012
PO:	

<u>SHIPVIA</u>	<u>REQDELIVER</u>	<u>FOB</u>	<u>TERMS</u>
Best Way	03/28/2012	Destination	80% on delivery, 20% on acceptance

<u>QTY</u>	<u>CATALOG</u>	<u>DESCRIPTION</u>	<u>LIST PRICE</u>	<u>EXTENDED</u>	<u>%</u>	<u>NET PRICE</u>
1	MISC_Dscent	VA Contract Number V797-6023b				
1	XRADRM-WS-R-TLT-8	XRADRM-WS-R-TLT-8 RAD RM WS TRK RT TLT 80KW ===== Complete X-ray Room Package - High end components includes high capacity generator and tube for heavy workloads and high penetration exams. Built-in safety features extend system life with built in tube heat protection and intelligent automated self-tests to confirm essential functions at start up and throughout the day. A standard generator control console is included for manual adjustments but Fujifilm's SpeedLink X-ray Control Software™ simplifies these steps by automatically mapping preferred techniques to the exam menu selected at the FDX Console workstation. System includes: Motorized Ceiling-mounted tube System, tilting upright chest stand and Polydoras IT 80kW generator system.  > Fujifilm Full System Warranty (1 Yr) with the exception of consumables, X-ray Tube 12 mos pro-rated > Professional Services 2 Days Included with Package ----- > Siemens Polydoras IT Generator (80kW GEN/600,000 HU tube) - > ACSS and tracking of tube to detector elevations > Ceiling Mounted Tube System with motorized elevation, 59" vert. travel > ION Chambers & AEC, > Auto Collimator (to cassette size) > Built-in selectable filters included reduce patient dose. > Up to four (4) copper filters (0, 0.1, 0.2, 0.3 mm Cu) > Built-in DAP (option) dose area product monitoring system available separately for monitoring patient dose. ----- > Tilting Upright Chest Stand (easy manual movements) 15-75" travel >>> RIGHT Side loading bucky <<< > Motorized OTC automatically tracks vertical movement of Wall Stand bucky > Grids - user removable stationary grids built in > standard 103 lines per inch grids > Upright: 10:1, FD 70.1" > GPR grid pattern removal software also included ----- > SpeedLink Integration of Generator Console to FDX Console - fully automates the exposure technique settings for the X-ray generator based on the specific exam type and series selected at the Fuji FDX Console.				



**FUJIFILM MEDICAL SYSTEMS USA, INC.**  
 419 WEST AVENUE, SUITE 165  
 STAMFORD, CT 06902-6300  
 203-363-3934 203-363-1887 (FAX)

**Ermon Owens**  
**VA Jacksonville Outpatient Clinic**  
 1833 Boulevard St.  
 Jacksonville, FL 32206  
 Purchasing Group: VA

Date:	1/18/2012
Quote #:	0394003201100344-6
Expires:	2/17/2012
PO:	

1	XDEVO-1PNLG43I	<p>XDEVO-1PNLG43I DEVO WRLS - 1 G43I FPD, FDX CNSL &amp; INTF</p> <p>=====</p> <p>FDR D-EVO WIRELESS, 17"x17" single panel system - digital x-ray FPD, MP &amp; MC units, exposure interface &amp; FDX Console technologist workstation.</p> <p>&gt; (2) Days Professional Services: On-site Application training            workflow and image processing parameters customization</p> <p>&gt; Warranty: 1 Year, full system (valid from original install date)            exception of batteries: covered 1st 90 days</p> <p>-----</p> <p>FDR-D-EVO model G43I (17"x17" wireless flat panel detector):</p> <p>&gt; Patented ISS (Irradiated Side Sampling) capture circuitry design            Significantly increases DQE, dose efficiency &amp; sharpness</p> <p>&gt; Fast Image Preview 1-2 Seconds &amp; 8-10s cycle times</p> <p>&gt; High Resolution: 16bit, 150 micron capture (2880 x 2880pxls)</p> <p>&gt; 17"x17" size - Easily fits standard bucky's &amp; holders</p> <p>&gt; Light wt (only 8 lbs) convenient for table top &amp; free cassette exams</p> <p>&gt; Wireless battery operation, single quick change battery design            each charge lasts up to 400 exposures or 3.5 hours, recharge 3hrs max</p> <p>Early warnings &amp; safety lockout prevents exposures when battery gets low</p> <p>Continuous status and clearly noticeable flashing warnings at workstation</p> <p>&gt; Wireless N 5.2GHz secure in room (32ft range) closed network (detector to MP unit)</p> <p>Proprietary paring/handshake protocol ensures transmission, data completion            integrity without transmitting patient records and completely isolated from network.</p> <p>&gt; Exposure Time: programmable up to 3.8s max to accommodate breathing techniques and larger patients</p> <p>&gt; GoS: Gadolinium Oxysulfide scintillator layer</p> <p>&gt; a-Si: (Amorphous Silicon) readout layer</p> <p>&gt; Detector withstands 275 lbs. distributed weight load</p> <p>&gt; Includes master s.w. disks &amp; manuals</p> <p>Power Supply (MP box)</p> <p>&gt; integrates wireless to FPD(s), panel activation w/exposure            &amp; supplies power to detectors for optional corded use</p> <p>&gt; Dimensions: 4.7x15.2x13.8", Wt 17.2 lbs.</p> <p>Control unit (FDR D-EVO-MC)</p>				
---	----------------	---	--	--	--	--



**FUJIFILM MEDICAL SYSTEMS USA, INC.**  
419 WEST AVENUE, SUITE 165  
STAMFORD, CT 06902-6300  
203-363-3934 203-363-1887 (FAX)

**Ermon Owens**  
**VA Jacksonville Outpatient Clinic**  
1833 Boulevard St.  
Jacksonville, FL 32206  
Purchasing Group: VA

Date:	1/18/2012
Quote #:	0394003201100344-6
Expires:	2/17/2012
PO:	

> Desktop CPU: 2.93 GHz (no monitor required)  
> Memory: 2GB, OS: Linux  
> Dimens: 4.5x13.9x15.7", Wt 18.3 lbs.  
Interface Box:  
> Integrated connectivity to generator exposure switch  
> Includes Hand Switch: coiled wire w/2-stage prep & expose  
-----  
FDX Console: Technologist Workstation image acquisition, preview, automated & manual processing  
> Application s.w. for simplified patient ID and QA  
> QC exam reprocessing, sensitivity, latitude, density and contrast  
> Technologist tools - automatic and manual Shutters (black borders) and movable annotation markers  
> Auto Trimming: optimizes display size for small anatomy & off center positioned exams  
> FNC (Flexible Noise Control) - Suppresses noise without loss of diagnostic information or sharpness  
> MFP (Multi-Frequency Processing) - Optimizes multiple frequencies, improving dense & peripheral tissues  
> Basic security features - customizable log in/log out & user restrictions  
> Statistical Analysis reporting including reason for image rejection coding, for reject or other performance analyses  
> Free Text Annotation - comment text annotation markers  
> Image Magnification - enhanced full screen, mag & zoom tools  
> Hardware: desktop CPU (3.0GHz, 4G RAM, 250G Hdd, Windows 7 OS), keyboard, mouse, 19 in. color touch screen monitor, barcode scanner.  
> DICOM Worklist Management interface to RIS/HIS  
> DICOM Store connectivity to PACS  
> Networks with other FDX Consoles, FCR & FDR devices for flexibility  
-----  
\* \* \* Special Package Options Included \* \* \*  
> (1) Detachable detector cord for extended use with or without battery  
25ft length, supplies continuous power, charging & image transmission  
> Magnetic cord holders: neatly keeps detachable cord within easy reach  
> Charging Dock: charges up to 3 batteries simultaneously  
> Batteries: 3 included, (1 primary, 2 spare)  
> Wireless Access Point: Fuji preferred model for optimal speed & data integrity  
=====

NOTE: Retrofit to existing x-ray room equipment greater than ~10 years old may require upgrading components not optimal for use with a digital detector. Extra costs may include replacement of Grids and faulty or outdated ION chambers or oscillating mechanisms.  
=====

**FUJIFILM MEDICAL SYSTEMS USA, INC.**

419 WEST AVENUE, SUITE 165

STAMFORD, CT 06902-6300

203-363-3934 203-363-1887 (FAX)

**Ermon Owens****VA Jacksonville Outpatient Clinic**

1833 Boulevard St.

Jacksonville, FL 32206

Purchasing Group: VA

Date: 1/18/2012

Quote #: 0394003201100344-6

Expires: 2/17/2012

PO:

1	XDEVOGRID1038ALH	DEVO GRID 8:1/103/40-72 HNDL AL
1	XDEVOWBS-17	DEVO WEIGHT BEARING CAP 17"X17"
1	X-FDXDCMPRNT-SW	Enables DICOM Print function from the FDX Console workstation (Single License)
1	XSAUTOEXAM	Auto Exam Select enables mapping of RIS/HIS exam codes to Fuji MPM codes for automatic transfer of exam information to the FUJIFILM Digital Radiography Workstation. This feature is an excellent workflow-enhancing tool, as it enables transfer of a patient's ordered exam(s) with name from RIS/HIS. Can be used with or without Study Group option. One license is required for each set of RIS/HIS exam codes mapped to Fuji MPM codes.
2	16091611	Magnetic Cord Holder for FDR D-EVO manages and holds cord neatly within reach Works with the detachable cord for all D-EVO models
1	16099716	I/F Cable for Siemens Polydoros LX80
1	DEVOTRAINM	D-EVO TRAINING (2.5 DAYS OF TRAINING)
1	XIIPTRAINM	FLASH IIP/CONSOLE (ADVANCED)
1	SPSUTRAINM	Course #: SPSUTRAINM)  This course is designed to provide the student working knowledge surrounding installation, configuration, calibration, troubleshooting and maintenance of the FDR Velocity Speed Suite and the various peripheral components associated with it. (Classroom Lecture/PowerPoint and Lab, Written Test -  (Prerequisites - Intermediate X-ray)  3.24 CEUs
1	FUJITRAVEL	FUJIFILM will provide round trip airfare for the three training classes as configured into this quote. This offer does not include lodging or meals.
1	MISC_Dscnt	2 of the DEVO1PNL-CRDT-GVT takes form in the NO CHARGE Service Training as annotated on this quote
1	16169042	SE CABLE (MP-SE CONNECTION CABLE 10.0M)

**OTHER ITEMS**

<u>QTY</u>	<u>CATALOG</u>	<u>DESCRIPTION</u>
1	FREIGHT	Freight

**FUJIFILM MEDICAL SYSTEMS USA, INC.**

419 WEST AVENUE, SUITE 165

STAMFORD, CT 06902-6300

203-363-3934 203-363-1887 (FAX)

**Ermon Owens****VA Jacksonville Outpatient Clinic**

1833 Boulevard St.

Jacksonville, FL 32206

Purchasing Group: VA

Date: 1/18/2012

Quote #: 0394003201100344-6

Expires: 2/17/2012

PO:

## OPTIONAL ITEMS

<u>QTY</u>	<u>CATALOG</u>	<u>DESCRIPTION</u>	<u>LIST PRICE</u>	<u>EXTENDED</u>	<u>%</u>	<u>NET PRICE</u>
1	X-FDXPRECISE-OPT	Precise Enlargement - A second high resolution 2MP color monitor connected to the FDX Console for image verification. - Study information is displayed at the four corners - PACS comparable preview before sending - Magnification loop tool - Full size QA display, pan & zoom - Retrieve and view priors from Synapse PACS browser ----- Includes software key and 2MP color monitor				

Bill To:

**VA Jacksonville Outpatient Clinic**

1833 Boulevard St.

Jacksonville, FL 32206

Ship To:

**VA Jacksonville Outpatient Clinic**

1833 Boulevard St.

Jacksonville, FL 32206

Submitted By:

Customer Signature:

Approved By:

Title:

Date: