

Questions for VA101V-16-R0494, IL Construction, Montoursville, PA

1. The second paragraph under the 'Rear Entrance' scope of work states that the contractor is to provide wheelchair ramp from new addition to driveway at rear of home. Is there a drawing or sketch of this addition so that we may calculate this cost?

The Contractor to provide all sketches for ramps and landings at the front and rear of the home. Contractor to also provide all necessary documentation with which to draw building permits for the ramps and landings. New ramp and landings at the rear of the home to tie into the rear exit door of the new addition as well as tying into the rear exit doors for the sunroom. Ramp is to provide the appropriate slope for ADA compliance and tie into the existing drive at both the front and rear of the home. Ramps and landings shall be constructed of appropriately sized "Pressure Treated" lumber with concrete footings for all support posts. Footings and ramps/landings shall be constructed in accordance with all Federal, State and Local Building Codes."