



SYMBOL LEGEND

▼ WALL/VOICE/DATA OUTLET WITH TWO (2) RJ-45 CONNECTORS FOR DATA AT 18" ABOVE FIN. PROVIDE 3/4"C WITH TWO (2) CAT 6 PLENUM RATED CABLES EACH WITH 4 PAIRS UTP. EXTEND 3/4"C FROM BOX TO ABOVE ACCESSIBLE CEILING. PROVIDE INSULATED BUSINETS WHERE REQUIRED. ROUTE PLENUM RATED CABLE TO AREA NOTED ON PLANS.

TV WALL TV OUTLET WITH ONE(1) COAX RG CONNECTOR FOR TV. COORDINATE WITH ARCHITECT FOR MOUNTING HEIGHT. PROVIDE 3/4"C WITH ONE(1) COAX CABLE EXTENDING FROM OUTLET TO ACCESSIBLE CEILING. ROUTE CONDUIT AND CABLE TO AREA NOTED ON PLANS.

— VOICE/DATA CABLEING

TV TV/ANTENNA CABLEING

SCALE: 1/8" = 1'-0"

BLD: 11

SCHEMATIC DESIGN SUBMISSION	08/02/10
DESIGN DEVELOPMENT SUBMISSION	09/03/10
CONSTRUCTION DOCUMENT SUBMISSION	11/22/10
ISSUE FOR BIDS	12/19/11
Revisions:	Date

CONSULTANTS:



12-19-11

Date _____

Burns, DeLotte & McCoy, Inc.
Texas Registered Engineering Firm
5-685

ARCHITECT/ENGINEERS:

WILSON ARCHITECTURAL GROUP

5051 WESTHEIMER, SUITE 1000 HOUSTON, TEXAS 77056 TELEPHONE (713) 621-8714

MEP ENGINEERS
STRUCTURAL ENGINEERS
FIRE PROTECTION ENGINEERS
CIVIL ENGINEERS

BURNS DeLATTE AND McCOY, INC.
PINNACLE STRUCTURAL
PROTECTION DEVELOPMENT INC.
BREWER AND ESCALANTE

Drawing Title	FIRST FLOOR PLAN- SPECIAL SYSTEMS
---------------	--------------------------------------

SCALE: 1/8"=1'-0"

Approved: Project Director

Project Title	Project Number	Office of Construction
BUILDING 11 ADDITION AND INTERIOR RENOVATIONS	674A4-CSI-516	
	Building Number	

Project Number	674A4-CSI-516
----------------	---------------

Building Number
11

	11
	Drawing Number 11

ES301

Office of
Construction
and Facilities
Management

