

CONCRETE MOWING STRIP (4" DEPTH) TO BE INSTALLED BELOW/ALONG ENTIRE FENCE. THIS CONCRETE MOWING STRIP SHALL EXTEND TO THE SIDEWALK (WHERE THE SIDEWALK EXISTS) AND SHALL MAINTAIN THE SAME WIDTH THROUGHOUT. THE CONCRETE MOWING STRIP SHALL HAVE A SLOPE OF 1/8" PER FOOT. APPROXIMATE FENCE LENGTH (INCLUDING GATES) IS + OR - 2150 FEET. CONTRACTOR TO VERIFY TOTAL FENCE LENGTH.

SECTIONS OF EXISTING CONCRETE SIDEWALK ARE IN NEED OF REPAIR. CONTRACTOR TO VERIFY CONDITIONS AND REPLACE SIDEWALK IN NEED OF REPAIR.

ALL SLIDING GATES, EXCEPT FOR THE MAIN ENTRANCE, SHALL BE SIMILAR IN STYLE TO ITS CONNECTING FENCE.

ALL ELECTRICAL EXTERIOR RUNS SHALL BE IN-GROUND AND IN CONDUIT/PVC PER THE SPECIFICATIONS. SUBMIT METHODS, MATERIAL, AND LOCATION TO COTR.

CONTRACTOR TO PERFORM UTILITIES DETECTION AND LOCATE BY SURVEYOR TO DEVELOP A DRAWING OF EXISTING UTILITIES TO SUBMIT TO THE GOVERNMENT IN ORDER TO OBTAIN A DIGGING PERMIT.

CONTRACTOR WILL PERFORM HIS HER WORK BASE ON THE UTILITIES DETECTION MAP AND WILL TAKE FULL RESPONSIBILITY FOR ANY UTILITIES THAT ARE DISTURB OR DAMAGED.

CONTRACTOR TO PROVIDE ANY PERMITS NEEDED TO COMPLETE SCOPE OF WORK FROM CITY, AND/OR STATE AGENCIES.

- Existing
-
- Fence

Existing
Fence

SCALE 1/8" = 1"

[illegible]

RECOMMEND APPROVAL			
REQUESTER	Date		
CHIEF OF SERVICE	Date	CHIEF OF STAFF	Date
ASSOC. DIR. PATIENT CARE SVC.	Date	ASSOC. DIR. for OPERATIONS	Date
APPROVAL BY:			Date
MEDICAL CENTER DIRECTOR			

Drawing Title	PERIMETER FENCE AND SECURITY GATE(S) WORK DESCRIPTION
Approved: Safety Manager/M&O Supervisor	
Approved: Chief of Facilities Management Svr.	

Project Title		CAMPUS	
PERIMETER FENCE AND SECURITY GATE			
Building Number	Checked	Drawn	
CAMPUS		BLF	
Location	W.G.(Bill) Hefner Medical Center 1601 Brenner Ave. Salisbury NC 28144		

Date	10 NOV 2011
Project No.	659 11 239
DRAWING NO.	A-101
DWG. 3	OF 8



Department of Veterans Affairs