

## **SECTION 13 05 41**

### **SEISMIC RESTRAINT REQUIREMENTS FOR NON-STRUCTURAL COMPONENTS**

#### **PART 1 – GENERAL**

##### **1.1 DESCRIPTION:**

- A. Provide seismic restraint in accordance with the requirements of this section in order to maintain the integrity of nonstructural components of the building so that they remain safe and functional in case of seismic event.
- B. The design to resist seismic load shall be based on Seismic Design Categories per section 4.0 of the VA Seismic Design Requirements (H-18-8) dated August 2013, <http://www.cfm.va.gov/til/etc/seismic.pdf>.
- C. Definitions: Non-structural building components are components or systems that are not part of the building's structural system whether inside or outside, above or below grade. Non-structural components of buildings include:
  - 1. Architectural Elements: Facades that are not part of the structural system and its shear resistant elements; cornices and other architectural projections and parapets that do not function structurally; glazing; nonbearing partitions; suspended ceilings; stairs isolated from the basic structure; cabinets; bookshelves; medical equipment; and storage racks.
  - 2. Electrical Elements: Power and lighting systems; substations; switchgear and switchboards; auxiliary engine-generator sets; transfer switches; motor control centers; motor generators; selector and controller panels; fire protection and alarm systems; special life support systems; and telephone and communication systems.
  - 3. Mechanical Elements: Heating, ventilating, and air-conditioning systems; medical gas systems; plumbing systems; sprinkler systems; pneumatic systems; boiler equipment and components.
  - 4. Transportation Elements: Mechanical, electrical and structural elements for transport systems, i.e., elevators and dumbwaiters, including hoisting equipment and counterweights.

##### **1.3 QUALITY CONTROL:**

- A. Shop-Drawing Preparation:
  - 1. Have seismic-force-restraint shop drawings and calculations prepared by a professional structural engineer experienced in the area of seismic force restraints. The professional structural engineer shall be registered in the state where the project is located.
  - 2. Submit design tables and information used for the design-force levels, stamped and signed by a professional structural engineer registered in the State where project is located.
- B. Coordination:
  - 1. Do not install seismic restraints until seismic restraint submittals are approved by the Resident Engineer.

Solicitation/Contract Attachment C  
VA246-17-Q-0130  
Section 13 05 41  
Seismic Restraint Requirements for Non-Structural Components

2. Coordinate and install trapezes or other multi-pipe hanger systems prior to pipe installation.

C. Seismic Certification:

In structures assigned to IBC Seismic Design Category C, D, E, or F, permanent equipments and components are to have Special Seismic Certification in accordance with requirements of section 13.2.2 of ASCE 7 except for equipment that are considered rugged as listed in section 2.2 OSHPD code application notice CAN No. 2-1708A.5, and shall comply with section 13.2.6 of ASCE 7.

**1.4 SUBMITTALS:**

A. Submit a coordinated set of equipment anchorage drawings prior to installation including:

1. Description, layout, and location of items to be anchored or braced with anchorage or brace points noted and dimensioned.
2. Details of anchorage or bracing at large scale with all members, parts brackets shown, together with all connections, bolts, welds etc. clearly identified and specified.
3. Numerical value of design seismic brace loads.
4. For expansion bolts, include design load and capacity if different from those specified.

B. Submit prior to installation, a coordinated set of bracing drawings for seismic protection of piping, with data identifying the various support-to-structure connections and seismic bracing structural connections, include:

1. Single-line piping diagrams on a floor-by-floor basis. Show all suspended piping for a given floor on the same plain.
2. Type of pipe (Copper, steel, cast iron, insulated, non-insulated, etc.).
3. Pipe contents.
4. Structural framing.
5. Location of all gravity load pipe supports and spacing requirements.
6. Numerical value of gravity load reactions.
7. Location of all seismic bracing.
8. Numerical value of applied seismic brace loads.
9. Type of connection (Vertical support, vertical support with seismic brace etc.).
10. Seismic brace reaction type (tension or compression): Details illustrating all support and bracing components, methods of connections, and specific anchors to be used.

C. Submit prior to installation, bracing drawings for seismic protection of suspended ductwork and suspended electrical and communication cables, include:

1. Details illustrating all support and bracing components, methods of connection, and specific anchors to be used.
2. Numerical value of applied gravity and seismic loads and seismic loads acting on support and bracing components.

Solicitation/Contract Attachment C  
VA246-17-Q-0130  
Section 13 05 41  
Seismic Restraint Requirements for Non-Structural Components

3. Maximum spacing of hangers and bracing.
4. Seal of registered structural engineer responsible for design.
- D. Submit design calculations prepared and sealed by the registered structural engineer specified above in paragraph 1.3A.
- E. Submit for concrete anchors, the appropriate ICBC evaluation reports, OSHPD pre-approvals, or lab test reports verifying compliance with OSHPD Interpretation of Regulations 28-6.

**1.5 APPLICABLE PUBLICATIONS:**

- A. The Publications listed below (including amendments, addenda revisions, supplements and errata) form a part of this specification to the extent referenced. The publications are referenced in text by basic designation only.

SPEC WRITER NOTE: Edit applicable publications to indicate the most recent edition.

- B. American Concrete Institute (ACI):  
355.2-07 .....Qualification for Post-Installed Mechanical Anchors in Concrete and  
Commentary
- C. American Institute of Steel Construction (AISC):  
Load and Resistance Factor Design, Volume 1, Second Edition
- D. American Society for Testing and Materials (ASTM):  
A36/A36M-08 .....Standard Specification for Carbon Structural Steel  
A53/A53M-10 .....Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-  
Coated, Welded and Seamless  
A307-10.....Standard Specification for Carbon Steel Bolts and Studs; 60,000 PSI  
Tensile Strength.  
A325-10.....Standard Specification for Structural Bolts, Steel, Heat Treated,  
120/105 ksi Minimum Tensile Strength  
A325M-09 .....Standard Specification for High-Strength Bolts for Structural Steel  
Joints [Metric]  
A490-10.....Standard Specification for Heat-Treated Steel Structural Bolts, 150 ksi  
Minimum Tensile Strength  
A490M-10 .....Standard Specification for High-Strength Steel Bolts, Classes 10.9 and  
10.9.3, for Structural Steel Joints [Metric]  
A500/A500M-10 .....Standard Specification for Cold-Formed Welded and Seamless Carbon  
Steel Structural Tubing in Rounds and Shapes  
A501-07.....Specification for Hot-Formed Welded and Seamless Carbon Steel  
Structural Tubing

Solicitation/Contract Attachment C  
VA246-17-Q-0130  
Section 13 05 41  
Seismic Restraint Requirements for Non-Structural Components

- A615/A615M-09 .....Standard Specification for Deformed and Plain Billet-Steel Bars for  
Concrete Reinforcement
- A992/A992M-06 .....Standard Specification for Steel for Structural Shapes for Use in  
Building Framing
- A996/A996M-09 .....Standard Specification for Rail-Steel and Axel-Steel Deformed Bars for  
Concrete Reinforcement
- E488-96(R2003).....Standard Test Method for Strength of Anchors in Concrete and  
Masonry Element
- E. American Society of Civil Engineers (ASCE 7) Latest Edition.
- F. International Building Code (IBC) Latest Edition
- G. VA Seismic Design Requirements, H-18-8, August 2013
- H. National Uniform Seismic Installation Guidelines (NUSIG)
- I. Sheet Metal and Air Conditioning Contractors National Association  
(SMACNA): Seismic Restraint Manual - Guidelines for Mechanical Systems, 1998 Edition and  
Addendum

**1.6 REGULATORY REQUIREMENT:**

- A. IBC Latest Edition.

**PART 3 – EXECUTION**

**3.1 CONSTRUCTION, GENERAL:**

- A. Provide equipment supports and anchoring devices to withstand the seismic design forces, so that when seismic design forces are applied, the equipment cannot displace, overturn, or become inoperable.
- B. Provide anchorages in conformance with recommendations of the equipment manufacturer and as shown on approved shop drawings and calculations.
- C. Construct seismic restraints and anchorage to allow for thermal expansion.
- D. Testing Before Final Inspection:
1. Test 10-percent of anchors in masonry and concrete per ASTM E488, and ACI 355.2 to determine that they meet the required load capacity. If any anchor fails to meet the required load, test the next 20 consecutive anchors, which are required to have zero failure, before resuming the 10-percent testing frequency.
  2. Before scheduling Final Inspection, submit a report on this testing indicating the number and location of testing, and what anchor-loads were obtained.

- - - E N D - - -