



Provide New Through Wall Air Conditioner 3 phase 208V, 30 Amp circuit. 30Amp CB Fed from panel 5-1-P3 or reuse pole 2,4,6 in IRM panel to subfeed a panel to feed existing AC and New AC unit.

Remove existing 78"X39" Window and window AC unit.

Install new through wall unit to allow access to all external components. New unit shall measure less than 34" W, 18" D, and 71" H. Flash unit against weather. Direct condensate to the bottom window well.

Supply grill shall be directed below the 93" clear under drip pan.

Return Low in opening.

CORRIDOR

IRM Computer Closet in Building 5