

SITE LIGHTING NOTES:

1. 4-#8 & 1-#10 GRD IN 1-2" GALVANIZED STEEL CONDUIT. EXTEND GALVANIZED STEEL CONDUIT 2' BACK OF EXISTING OR PROPOSED CURB FACE.
2. INSTALL LIGHTING STANDARDS 2'-6" BACK OF CURB FACE UNLESS OTHERWISE NOTED.
3. FIXTURE MOUNTING HEIGHT TO BE 25' ABOVE FINISHED GRADE OF ROADWAY UNLESS OTHERWISE NOTED.
4. CONTRACTOR TO VERIFY LOCATION OF ALL SITE LIGHTING CONDUIT & LIGHTING STANDARDS IN RELATION TO PROPOSED TREES.

EXISTING AMERITECH UNDERGROUND TELEPHONE CONDUITS

EXISTING AMERITECH MANHOLE

INTERNALLY ILLUMINATED SIGN

RELOCATED TYPE "S1" LIGHT AND POLE. PROVIDE NEW POLE BASE AND GROUND

SEE NOTES 2, 3 & 4 (TYP)

PS 108 LOCATED AT 6694E, 6082N

PS LOCATED AT 6968E, 6025N

FOR CONTINUATION SEE DWG. E5.B1

FOR CONTINUATION SEE DWG. E3.N1

1" C., 4#8 & 1#10 GRD TO 1-LB-01 VIA CONTACTOR 1-B-05 IN WEST SERVICE BAY ELECTRICAL ROOM. FOR CONTINUATION SEE DWG. E3.N1

1" C., 4#8 & 1#10 GRD TO 1-LB-02-15,17,19 VIA CONTACTOR 1-B-03. FOR CONTINUATION SEE DWG. E4.B1

TYPE "S8" (TYP) SEE NOTE 4  
INSTALL 2'-6" BACK OF EDGE OF SIDEWALK (TYP OF FOUR)

TYPE "S2" (TYP)

NEW CLINICAL ADDITION FIN FIRST FL EL 827.25

EAST PARKING STRUCTURE

Project No:  
506-12-122

Project Title:  
INSTALL EXTERIOR LED LIGHTS

Drawing Title:  
FRONT SITE

Approved: JAY H. MILLER  


Drawn By:  
ROD IPAKCHIAN

Date:  
JANUARY 11, 2012

Drawing No.  
1 OF 3

1

VA ANN ARBOR  
HEALTH CARE  
SYSTEM