



**ATTIC FLOOR PLAN**  
 MECHANICAL - NEW WORK  
 GRAPHIC SCALE (FEET)  
 0 2 4 6 8 16

- GENERAL NOTES:**
1. VERIFY EXISTING CONDITIONS IN FIELD PRIOR TO BEGINNING WORK.
  2. SPACE IS LIMITED. CAREFUL COORDINATION WITH ELECTRICAL, PLUMBING AND PIPING INSTALLATION.
  3. PROVIDE NECESSARY OFFERS IN PIPING AND DUCTWORK AS REQUIRED TO ACCOMMODATE NEW WORK. DIMENSIONS ARE DIAGNOSTIC AND DO NOT NECESSARILY INDICATE THE EXACT LOCATION OF THE WORK. DIMENSIONS ARE NECESSARY FOR COMPLETE INSTALLATION.
  4. COORDINATE EXACT SIZE, LOCATION, AND COLOR OF WALL MOUNTED LOUVERS WITH ARCHITECT PRIOR TO ORDERING.
  5. SPILL CONDENSATE FROM AHUS INTO NEAREST FLOOR DRAIN. PROVIDE PUMP IF NECESSARY.
  6. PROVIDE AUXILIARY CONDENSATE DRAIN PAN OF WELDED CONSTRUCTION, 2" DEEP, WITH 1/2" DIA. DRAIN TO NEAREST FLOOR DRAIN.
  7. SPONGE CURE CABLE WIRE, STEAM AND CONDENSATE RETURN.
  8. COORDINATION SHOP DRAWINGS SHALL BE PREPARED FOR THE ENTIRE PROJECT DRAWN TO 1/4" = 1'-0" SCALE (MINIMUM). DRAWINGS SHALL BE FULLY DIMENSIONED, INCLUDING ELEVATIONS OF DUCTWORK AND PIPING.
- DRAWING NOTES:**
1. SET RISER DRAWING ON DRAWING 1 - WAS FOR TIE-IN TO EXISTING RETURN CHASE.
  2. SET LARGE SCALE PLUMBING DRAWING 1 - WAS FOR PIPING CONNECTIONS.
  3. TIE-IN TO EXISTING FLOOR DRAIN. EXISTING DUCT MAKE NECESSARY OFFERS TO RELOCATE.



**CONSTRUCTION DOCUMENTS**

REVISION A - ADDENDUM NO. 1 - 3/21/12

Revisions	Date

**Tennessee Valley Healthcare System**

**MURFREESBORO CAMPUS**

<p>Approved: ---</p> <p>Approved: Facility Manager</p> <p>Approved: Director</p>	<p>Drawing Title: <b>NEW WORK FLOOR PLAN</b></p> <p>Project Title: <b>REPLACE ATTIC AHUS BUILDING 1</b></p> <p>Location: TMS - YORK CAMPUS</p>
<p>Project No. 628A4-11-203</p> <p>Building Number 1</p> <p>Location TMS - YORK CAMPUS</p>	<p>Date 01/20/2012</p> <p>Project No. 628A4-11-203</p> <p>Building Number 1</p> <p>Location TMS - YORK CAMPUS</p>