



**C BAGHOUSE SECTION**  
1/4" = 1'-0"

## FLAG NOTES: ○

1. AUGER ROUTING, AUGER TO BE LOCATED IN NEW TRENCH. RE: STRUCTURAL AND ARCHITECTURAL DRAWINGS FOR TRENCH DETAILS. COORDINATE EXACT TRENCH DIMENSIONS REQUIRED WITH AUGER BEING PURCHASED AFTER SUBMITTAL REVIEW PROCESS.
2. ASH COLLECTION PIPING FROM BAGHOUSE TO AUGER. PROVIDE WEATHER PROOF OPENING INTO AUGER TRENCH FOR ASH COLLECTION PIPING.
3. CATWALK AND PLATFORM FOR FAN AND BAGHOUSE ACCESS. SEE ARCHITECTURAL AND STRUCTURAL FOR FURTHER DETAILS.
4. DUCTWORK TO EXISTING STACK. SEAL ALL OPENINGS IN EXISTING STACK NOT REUSED.
5. CONCRETE PAD FOR SF-1 AND SF-2. RE: STRUCTURAL FOR DETAILS.
6. ROTARY AIRLOCK PROVIDED WITH BAGHOUSE.
7. FLEXIBLE DUCT CONNECTIONS AT INLET AND OUTLET OF BAGHOUSES AS WELL AS INLET AND OUTLET OF STACK FANS. FLEXIBLE CONNECTIONS TO BE RATED FOR 500°F FLUE GAS TEMPERATURE. PROVIDE SUNSHIELDS ON FLEXIBLE CONNECTIONS.
8. B-3 BOILER FLUE.

VA FORM 08-6231