


three inches = one foot
 one and one-half inches = one foot
 one inch = one foot
 three-quarters inch = one foot
 one-half inch = one foot
 three-eighths inch = one foot
 one-quarter inch = one foot
 one-eighth inch = one foot

- GENERAL NOTES:**
1. PROVIDE FIRE ALARM SMOKE DUCT DETECTOR IN RETURN AND SUPPLY DUCT OF AHU-17 & 18. PROVIDE SHUTDOWN RELAY AND INDICATOR LIGHT AS REQUIRED. VERIFY EXACT LOCATION OF SMOKE DUCT DETECTOR AND SAMPLING TUBE IN SUPPLY AND RETURN DUCT WITH MECHANICAL CONTRACTOR. CONNECT SMOKE DUCT DETECTORS AND RELAYS TO EXISTING FIRE ALARM CONTROL PANEL (FACP). FIRE ALARM SYSTEM FOR THE BUILDING SHALL BE RECERTIFIED AFTER DEMOLITION OF FIRE ALARM DEVICES AND ALSO AFTER NEW DEVICES INSTALLED FOR AHU-17 & 18.
- NOTES:**
1. LOCATE DISCONNECT SWITCH WITHIN SIGHT OF RETURN FAN (RF). COORDINATE LOCATION WITH DUCT WORK, EQUIPMENT AND MECHANICAL CONTRACTOR.
 2. LOCATE DISCONNECT SWITCH WITHIN SIGHT OF SUPPLY FAN OF AIR HANDLING UNIT. COORDINATE LOCATION WITH DUCTWORK, EQUIPMENT AND MECHANICAL CONTRACTOR.
 3. HOMERUN TO EXISTING MAIN FIRE ALARM CONTROL (FACP) LOCATED ON GROUND FLOOR.



ATTIC FLOOR PLAN
 ELECTRICAL - NEW WORK
 0 2 4 6 8 10
 GRAPHIC SCALE (FEET)



CONSTRUCTION DOCUMENTS



Revisions	Date

Tennessee Valley Healthcare System

MURFREESBORO CAMPUS

SAJJADI ENGINEERING GROUP, P.C.
 1501 45th Street, Suite 101
 Murfreesboro, TN 37132
 615.833.7033 Fax: 615.833.7030
 www.sajjadiengineering.com
 PROJECT: 11-37

Drawing Title	ATTIC PLAN- NEW WORK - ELECTRICAL
Approved: ---	Approved: Facility Manager
Approved: ---	Approved: Director

Project Title	REPLACE ATTIC AHU's- BLDG 6
Building Number	6
Location	VAMC - MURFREESBORO

Date	01/20/2012
Project No.	626A4-11-204
DRAWING NO.	6-E5
FILE NAME	---

Veterans Administration