



FOOD SERVICE EQUIPMENT SCHEDULE															
EQUIPMENT SPECIFICATIONS						PREFERRED ENERGY SOURCE			PLUMBING			ALTERNATE ENERGY SOURCE			VENTILATION
NO.	ITEM	MODEL	SIZE L/W/H	SUPPLIER/INSTALLER	ELECTRICAL WALL VOLTS	POWER KW/AMPS	STEAM	GAS	WATER HOT	COLD	WASTE FLOOR DRAIN	ELEC	STEAM	GAS	GREASE LADEN
1	PASTRY/COOLER DISPLAY CASE	STRUCT CONCEPTS HMB04	50 3/4 x 56	KC	18" AFF	208/1	11.5A	NEMA 14	20P						
2A	FRONT COUNTER UNIT	FABRICATED	89/34/36	KC											
2B	SIDE COUNTER UNIT W/ SINK	FABRICATED	84/34/36	KC					X	X	X				
3A	BACKBAR COUNTER UNIT W/ SINK	FABRICATED	101 1/2 x 36	KC					X	X	X		* SEE NOTE	BELOW	
3B	BACKBAR COUNTER UNIT	FABRICATED	58/28/36	KC											
3C	BACKBAR COUNTER UNIT	FABRICATED	42/28/36	KC											
4	UNDERCOUNTER REFRIGERATOR (2)	BEVERAGE AIRE UCR27Y-23	27/27/31	KC	12" AFF	115/1	4.0A								
6	ESPRESSO MACHINE W/WATER FILTER	VERISMO 701	17/21/30	KC	48" AFF	220/1	30A	NEMA L6	30P	3/8"	FLOOR DRAIN				
7	ICE MAKER (2)	MANITOWAC QM45 W/ 4" LEGS	19/22/32	KC	12" AFF	115/1	5.2A			3/4"	FLOOR DRAIN				
8	COFFEE BREWER	FETCO CBS-2052e	22/22/37	KC	48" AFF	120/208V 1-phase	23A			3/8"		(3-Wires + Ground)			
9	MENU BOARD	MAINSTREET	30/3/36	KC											
10	TRASH CAN	VCS BUYOUT		KK											
11	BLENDER (2)	PROVIDED BY STARBUCKS	7/8/16	KC	48" AFF	120/1	13A								
12	AIR POT (6)	FETCO	8dia./13	KK											
13	1 SECTION DISPLAY REFRIGERATOR	TRUE GDM-23 (REVERSE DOOR)	27/30/79	KC	48" AFF	115/1	7.2A								
14	CONDIMENT STAND	FABRICATED	48/24/36	KC											
15	CASH REGISTER	VCS BUYOUT		KC	12" AFF	115/1	15A								
16	TORNADO OVEN	TURBO-CHEF NGC	26/26/19	KC	40" AFF	208/1	30A								
17	SELF-SERVE MERCHANDISER -- HOT	FEDERAL-CH2428 (NO BASE)	24/30/25	KC	48" AFF	120/1	5.8A								
18	PENDANT LIGHTS	TECH LIGHTING HOL#700FJ FIRAS LED		KC	ABV CLG	120/1	15A	USES	12 VOLT LED	LAMPS					
19	30" DIA TABLE W/ THREE CHAIRS (4)	TBD	30dia./30	KC											
20	PERIMETER COUNTER & SEATING	TBD		KC											

CC = CONTRACTOR SUPPLY AND MEDICAL CENTER INSTALL * NOTE: FABRICATE COUNTER PIECES NO LONGER THAN 8'-0" FOR EASE OF DELIVERY. IF SHOWN LARGER ABOVE, BREAK INTO MULTIPLE PARTS
KC = CANTEEN SUPPLY AND MEDICAL CENTER INSTALL
KK = CANTEEN SUPPLY AND CANTEEN INSTALL

NOTE TO MEDICAL CENTER:

- ALL CONSTRUCTION IS THE RESPONSIBILITY OF THE MEDICAL CENTER, OR ITS DESIGNATED REPRESENTATIVE / CONTRACTOR, INCLUDING, BUT NOT LIMITED TO, EQUIPMENT REMOVAL, WALL DEMOLITION, DISCONNECTING & INSTALLING NEW UTILITIES, CONSTRUCTING NEW WALLS & SOFFITS, INSTALLATION OF SHEETROCK / WALL TREATMENTS / PAINTING / CHAIR RAIL, REMOVAL AND DISPOSAL OF OLD FURNISHINGS, RECEIVING AND INSTALLATION OF NEW FURNITURE, DEMOLITION OF CEILINGS / LIGHTING, INSTALLATION OF NEW CEILING / LIGHTING, AND PROVIDE A ROLLOFF DUMPSTER.
- ALL FOOD EQUIPMENT MUST BE PROPERLY RECEIVED AND SECURELY STORED BY THE MEDICAL CENTER AS IT ARRIVES. REQUESTED DELIVERY DATES SHOULD BE SCHEDULED WITH THE VCS CENTRAL OFFICE AS SOON AS POSSIBLE TO ENSURE TIMELY DELIVERY FOR THE PROJECT. THE MEDICAL CENTER IS RESPONSIBLE FOR THE MOVEMENT, ASSEMBLY AND INSTALLATION OF ALL FOOD COUNTERS AND EQUIPMENT IDENTIFIED ON THE EQUIPMENT SCHEDULE WITH THE NOTATION, "CC" AND "KC".
- EQUIPMENT CUT SHEETS ARE AVAILABLE ONLINE AT "HTTP://VAVW.PORTAL.VA.GOV/SITES/VACANTEEN/ENG/EQUIPMENT%20CUT%20SHEETS/FORMS/ALLITEMS.ASPX" AND IS LISTED BY MANUFACTURER & MODEL NUMBER, NOT BY THE ITEM NUMBER AS SHOWN ON THIS DRAWING.

LEGEND	
	= EXISTING WALLS TO BE REMOVED
	= NEW FULL HEIGHT WALL
	= NEW 60" HIGH WALL (48" + 12" ETCHED GLASS)
	= EXISTING WALL TO REMAIN

CASH REGISTER WIRING DIAGRAMS ARE AVAILABLE ON THE VCS WEBSITE:
<https://vavw.portal.va.gov/sites/vacanteen/01/Cash%20Registers/Wiring%20Diagram.doc>
CONTACT LORETTA KREUTSBERG FOR SPECIFIC WIRING INSTRUCTIONS. INSTRUCTIONS DO VARY FROM LOCATION TO LOCATION.

UTILITY REQUIREMENTS

	120V OUTLET WITH EQUIPMENT NUMBER
	208V OUTLET WITH EQUIPMENT NUMBER
	SPARE OUTLET 120V
	J-BOX WITH EQUIPMENT NUMBER
	MULTI J-BOX WITH EQUIPMENT NUMBER
	STUB UP WITH EQUIPMENT NUMBER
	TELEPHONE JACK
	COLD WATER INLET
	HOT WATER INLET
	DRAIN REQUIRED
	GAS REQUIRED
	STEAM REQUIRED
	CAT5 NETWORK LINE

DATE	REVISIONS	NAME
------	-----------	------

COORDINATIONS	DATE
---------------	------

DRAWN BY:	CHECKED BY:
JMB	

APPROVED: MEDICAL CENTER DIRECTOR

DRAWING TITLE
**NEW VCS
STARBUCKS SHOP**

LOCATION
WILKES-BARRE, PA

PROJECT NUMBER
693-SB-12

DATE
00/00/12

DRAWING NO.
SB693

DWG. 2 OF 2

T:\Engineer\ SUPPORT\ VCS_logs_final.jpg