

Replace building 38 Parking lots

Date: 3/16/12

Quantities below are for reference only and must be verified to prepare bids

Replace building 38 Parking lots is a lump sum bid.

North Parking Lot

Item	Description	Unit	Quantity
1	Mobilization	LS	1
2	Traffic Control	LS	1
3	Remove Curb & Gutter	LF	63
4	Remove Curb & Gutter Special	LF	4
5	Remove Concrete approach paving	SY	70
6	Remove Asphalt Paving /Cold Mill in place	SY	4974
7	Subgrade Remediation	CY	300
8	Linear Grading/Shaping Compacting	SY	4974
9	Concrete Curb & Gutter	LF	63
10	Concrete Curb & Gutter Special	LF	4
11	Concrete approach paving	SY	70
12	4" Asphalt Paving(includes tack oil)	Ton	1000
13	Parking Lot Striping	LS	1

West Parking Lot

Item	Description	Unit	Quantity
1	Traffic Control	LS	1
1	Remove Curb & Gutter	LF	70
2	Concrete Curb & Gutter	LF	70
3	6" Valley Gutter	SY	15
3	Cold Milling Concrete	SY	472
4	Asphalt Patching	Ton	5
5	2" Asphalt Overlay(includes tack oil)	Ton	100
6	Parking Lot Striping	LS	1

South Parking Lot

Item	Description	Unit	Quantity
1	Saw Asphalt	LF	155
1	Remove & Grub Tree	EA	1
2	Remove Curb & Gutter	LF	154
3	Strip 6" Topsoil	SY	1370
4	Shaping	CY	912
5	Scarify & Recompact	SY	1370
6	2.5' Concrete Curb & Gutter	LF	308
7	6" Aggregate Base Course	Ton	440
8	4" Asphalt Paving	Ton	300
9	Parking lot Striping	LS	1
10	Erosion control mats	SY	40