



NOTES:

1. PLOG CONT. TO CONNECT TO FILL SPOUT FURNISHED & INSTALLED BY POOL CONTR.
2. CUT AND CAP EXISTING DOMESTIC COLDWATER & FILTER DISCHARGE LINES.
3. CONNECT TO EXIST 4" CW LINE & RUN TO & CONNECT TO FILL SPOUT.
4. POINT OF CONNECTION TO PIPING FURNISHED & INSTALLED BY POOL CONTR.
5. CONNECT TO EXISTING 4" GUTTER DRAIN LINE.
6. EXISTING 4" GUTTER DRAIN. CUT OFF & CAP ABOVE DECK DRAIN INLET.
7. REMOVE EXIST PUMP SUCTION PIPING & CONNECT NEW PIPING. PROVIDE REDUCER OR INCREASER AS REQUIRED. DISCONNECT PUMP DISC. & RECONNECT TO NEW PUMP USING ADAPTERS AS REQ'D.
8. GENERAL: ALL PIPING BY POOL CONTR. TO BE SCHEDULE 40 PUG/SOLVENT WELDED. ALL PIPING BY PLOG CONTR. TO BE SAME WITH PROPER ADAPTERS WHERE CONNECTIONS ARE MADE TO METAL PIPE.

THIS DRAWING WAS SCAN FROM THE ORIGINAL DRAWING AND THE SCALES MIGHT NOT BE ACCURATE.

Mullinax/Wash Architects, P.A.

SUITE 1400
UCC BUILDING
CHARLOTTE, NORTH CAROLINA 28201
TEL. (704) 333-9881

Drawing Title Plumbing Plan		Project Title Therapeutic Pool Renovations		Date 7/2/84
Approved: Division Chief	Drawn	Building Number Six	Project No. 651037	
Approved: Service Director	Checked	Location Salisbury, N.C.	DRAWING NO. P-2	
			Dwg. OF 3	

Veterans Administration