

BEARDSLEY DESIGN ASSOCIATES
Architecture, Engineering & Landscape Architecture, P.C.
64 South Street
Auburn, New York 13021

ADDENDUM #1

SEPARATE LIFE SAFETY CIRCUITS PHASE II

DEPARTMENT OF VETERANS AFFAIRS

SYRACUSE, NEW YORK

BDA PROJECT #11148

April 10, 2012

Drawings and Project Manual dated January 24, 2012, entitled "Separate Life Safety Circuits Phase II, Department of Veterans Affairs, Syracuse, NY" are hereby amended, clarified, and modified as follows:

- ITEM 1 - REFER TO DRAWING A-102, FLOOR PLANS – DUMBWAITERS 1 AND 2:
- Plan B, Demolition Plan – 5th Floor
 - Replace temporary dust barrier with temporary construction partition. Reconfigure temporary construction partition to provide 3'-6" minimum clearance in front of (on Prosthetics Workshop B502 side of door) door between Prosthetics Workshop B502 and Elev Lobby B501. Outer width of temporary construction partition (6'-0") to remain.
 - Add note, "2-hour fire-rated temporary construction partition – refer to Detail 2/G-003."
 - Add 3'-0" wide door T502 at temporary construction partition.
 - Plan E, Demolition Plan – 6th Floor
 - Replace temporary dust barrier with temporary construction partition.
 - Add note, "2-hour fire-rated temporary construction partition – refer to Detail 2/G-003." Outer dimensions of temporary construction partition to remain.
 - Add 3'-0" wide door T604 at temporary construction partition.
 - Plan F, Demolition Plan – 7th Floor
 - Delete in its entirety.
 - Plan H, Alteration Plan – 7th Floor
 - Delete in its entirety.

- ITEM 2 - REFER TO DRAWING A-103, FLOOR PLANS – DUMBWAITERS 1 AND 2:
- Plan A, Demolition Plan – 8th Floor
 - Provide closer per Specification Section 08 71 00 on door between Elev Lobby 801 and Passage 802.
- ITEM 3 - REFER TO DRAWING A-104, FLOOR PLANS – DUMBWAITERS 3 AND 4:
- Plan A, Demolition Plan – Ground Floor
 - Replace “temporary construction partition full-height to underside of existing ceiling system” with “2-hour fire-rated temporary construction partition. Construct full-height to underside of structure above (refer to Detail 2/G-003 (similar) for partition construction. Modify existing ceiling system as needed for partition. Carefully remove ceiling tiles and grid as needed.”
 - Plan E, Demolition Plan – 2nd Floor
 - Provide closer per Specification Section 08 71 00 on door between Corridor 200 and Elect Room C203.
 - Plan F, Demolition Plan – 3rd Floor
 - Provide closer per Specification Section 08 71 00 on door between Corridor 330 and Distrib Room C303.
- ITEM 4 - REFER TO DRAWING A-105, FLOOR PLANS – DUMBWAITERS 3 AND 4:
- Plan A, Demolition Plan – 4th Floor
 - Provide closer per Specification Section 08 71 00 on door between Corridor and Distrib Room 407.
 - Plan B, Demolition Plan – 5th Floor
 - Provide closer per Specification Section 08 71 00 on door between Corridor and Elect Room C507.
 - Plan E, Demolition Plan – 6th Floor
 - Provide closer per Specification Section 08 71 00 on door between Corridor C600 and Distrib Room C607.
 - Plan F, Demolition Plan – 7th Floor
 - Provide closer per Specification Section 08 71 00 on door between Passage C705 and Distrib Room C703.
- ITEM 5 - REFER TO DRAWING A-106, FLOOR PLANS – DUMBWAITERS 3 AND 4:
- Plan A, Demolition Plan – 8th Floor
 - Provide closer per Specification Section 08 71 00 on door between Corridor 800 and Distrib Room C808.
 - In Conference C810, replace temporary dust barrier with temporary construction partition.
 - In Conference C810, add note, “2-hour fire-rated temporary construction partition – refer to Detail 2/G-003.”
 - Plan B, Demolition Plan – 9th Floor
 - Provide closer per Specification Section 08 71 00 on door between Corridor 935 and Machine Room C905.

- ITEM 6 - REFER TO DRAWING A-601, DOOR SCHEDULE AND DETAILS:
- Door Schedule
 - Add Door T502 – to be same as Door TG02.
 - Add Door T604 – to be same as Door TG02.
 - Delete Door C705.
 - Delete Door T705.
 - Revise Door TCG04 to 90 minute fire rating.
- ITEM 7 - REFER TO DRAWING F-102, FLOOR PLANS – DUMBWAITERS 1 AND 2:
- Plan F, Demolition Plan – 7th Floor
 - Delete in its entirety.
 - Plan G, Alteration Plan – 6th Floor
 - Extend sprinkler head and piping to underside of 8th floor grating.
 - Plan H, Alteration Plan – 7th Floor
 - Delete in its entirety.
- ITEM 8 - REFER TO DRAWING F-103, FLOOR PLANS – DUMBWAITERS 1 AND 2:
- Section E, Section Dumbwaiters 1 and 2
 - Delete sprinkler work at 7th floor and extend 6th floor sprinkler head and piping to underside of 8th floor grating.
- ITEM 9 - REFER TO DRAWING E-102, FLOOR PLANS – DUMBWAITERS 1 AND 2:
- Plan B, Alteration Plan – 7th Floor
 - Delete light switch from 7th floor. Circuit light fixture to fixture located at 6th floor.
- ITEM 10 - REFER TO DRAWING E-107, GROUND FLOOR PLAN:
- Revise Keyed Note 1 as follows, “Disconnect EGAA from existing emergency riser. Feeder to be reused for EGAA-1. Re-feed panel EGAA from new Life Safety disconnect switch located in CG04. Provide 4#3 and 1#8 ground in 1 1/4” conduit. Remove existing 70A-3P circuit breaker that feeds EGAA-1 to be reused. Provide blank covers and update panel schedule.”
 - Revise Keyed Note 2 as follows, “Disconnect and remove supply feeder for EGAA-1. Extend and re-feed panel from existing emergency riser. Provide 4#3 and 1#8 ground tap in 1 1/4” conduit. Use existing 70A-3P circuit breaker in EGAA as the main circuit breaker for EGAA-1. Label breaker as “MAIN.”
 - Revise Keyed Note 5 as follows, “Not Used.”
 - Add Keyed Note 6 at location of panel ELSGA-A as follows, “Disconnect and remove panel ELSGA-A and turnover panel to the VA. Provide a 100 amp, 3 phase, 4 wire fused disconnect switch (fused at 100 amp) at existing panel ELSGA-A location and connect to the Life Safety Riser. Re-feed panel EGAA from this disconnect switch.”

April 10, 2012

- ITEM 11 - REFER TO DRAWING E-108, FIRST FLOOR PLAN:
 - Revise Keyed Note 1 as follows, "Not Used."
- ITEM 12 - REFER TO DRAWING E-111, FOURTH FLOOR PLAN:
 - Revise Keyed Note 3 as follows, "Splice and extend branch circuit
 #11 from panel 4DA to panel E2DA (on second floor D-wing)."

END OF ADDENDUM #1