



- NOTES:**
1. SALVAGE AND REPLACE EXISTING TOPSOIL. SCREEN PRIOR TO PLACEMENT, AND FERTILIZE UPON STABILIZATION.
  2. ORANGE CONSTRUCTION FENCE SHALL BE PROVIDED AROUND ENTIRE PERIMETER OF CONSTRUCTION AREA. SEE DETAIL 14, SHEET C1.0. CONTRACTOR SHALL COORDINATE ACCESS THROUGH CONSTRUCTION FENCE WITH DAILY CONSTRUCTION ACTIVITY. ALL ENTRANCES/ OPENINGS IN FENCE SHALL BE ENCLOSED AT THE END OF EACH WORKING DAY.
  3. ALL SIDEWALKS SHALL MEET A.D.A REQUIREMENTS AND NOT EXCEED 2.00% CROSS SLOPE, OR 5.00% LONGITUDINAL SLOPE.
  4. PROVIDE ORANGE SAFETY CONES AND CONSTRUCTION SAFETY TAPE AROUND SIDEWALK CONSTRUCTION.
  5. PROTECT TREES DURING CONSTRUCTION.
- PARKING INFORMATION:**
- TOTAL NUMBER OF STALLS = 87 (9x19' STALLS)

100% CDs - For Construction

